

Call 02 Storm Damage on SR 57 NE Intersection with Williams Drive, known as Federal Aid Project No. ER-0230-00(015) / 108005301 in Greene County.

Q1. Is it the intent of the "Removal of Box Culverts" pay items to remove a portion of the culvert in order to tie-in the extensions or to only remove the headwalls? If a portion of the culvert has to be removed, how will the length be determined?

A1. The intent is to remove the headwalls only, and place a collar around the joint where the extensions begin.

Q2. **1.)** If asphalt is damaged while removing the guardrail, will asphalt patching be required? If so, will this be an absorbed item? **2.)** The asphalt is currently separating at the guardrail location. Is this supposed to be repaired under this contract? If so, will this be an absorbed item?

A2. **1.)** Yes, patching (only) will be required and will be an absorbed item. **2.)** No.