

Slide Repair on US 45 NB outside fill slope between Railroad bridge and SR 2, known as Federal Aid Project Nos. ER-0002-08(021) / 108060301 & ER-0002-08(022) / 108059301 in Alcorn County.					Michael Pittman Construction Co., Inc.	Century Construction Group, Inc.	Colom Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$670,922.25					\$592,650.50	\$632,987.26	\$747,563.00
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	203-EX021	Borrow Excavation, AH, FME, Class B9-6	3,338.000	CY	12.00	22.61	22.00
0020	203-G001	Excess Excavation, FM, AH	7,857.000	CY	6.00	15.59	7.00
0030	209-A004	Geotextile Stabilization, Type V	1,912.000	SY	2.50	3.27	12.00
0040	211-B001	Topsoil for Slope Treatment, Contractor Furnished	242.000	CY	40.00	24.87	20.00
0050	221-A001	Concrete Paved Ditch	2.000	CY	1,500.00	1,346.24	450.00
0060	225-A001	Grassing	2.000	ACRE	1,846.25	2,187.46	1,750.00
0070	225-C001	Mulch, Vegetative Mulch	4.000	TON	400.00	468.74	650.00
0080	234-A001	Temporary Silt Fence	375.000	LF	6.00	7.50	10.00
0090	234-C001	Super Silt Fence	100.000	LF	13.50	16.87	15.00
0100	237-A002	Wattles, 20"	80.000	LF	10.00	12.50	25.00
0110	249-B001	Remove and Reset Riprap	300.000	CY	100.00	26.82	15.00
0120	304-D004	Granular Material, Size 57	25.000	TON	75.00	60.55	36.00
0130	605-AA001	Geotextile for Subsurface Drainage, Type III	544.000	SY	6.00	3.10	10.00
0140	605-O004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	515.000	LF	25.00	11.83	25.00
0150	605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	260.000	LF	25.00	10.21	22.00
0160	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	47.000	CY	40.00	101.95	45.00
0170	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	192.000	CY	40.00	101.38	45.00
0180	605-Z003	Underdrain Appurtenances, Sign	7.000	EA	100.00	130.79	300.00
0190	605-Z006	Underdrain Appurtenances, Small Animal Guard	7.000	EA	50.00	150.21	300.00
0200	618-A001	Maintenance of Traffic	1.000	LS	35,000.00	40,000.00	80,000.00
0210	620-A001	Mobilization	1.000	LS	50,000.00	60,000.00	160,000.00
0220	815-A002	Loose Riprap, Size 100	7,500.000	TON	43.00	34.00	36.00
0230	907-228-A002	Erosion Control Blanket, Type II	1,892.000	SY	3.00	3.75	12.00