

Repairing 8 Slides on I-22 & US 45, known as Federal Aid Project Nos. ER-0002-06(030) / 108055301, ER-0006-02(035) / 108050301, ER-0002-06(031) / 108052301, ER-0006-02(034) / 108053301, ER-0006-02(033) / 108054301, & ER-0006-02(032) / 108062301 in Lee County.					Phillips Contracting Co., Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,052,075.95					\$1,387,839.80		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-B063	Removal of Concrete Paved Ditch	166.000	SY	10.00		
0020	203-EX021	Borrow Excavation, AH, FME, Class B9-6	24,115.000	CY	20.00		
0030	203-G001	Excess Excavation, FM, AH	24,115.000	CY	12.00		
0040	206-A001	Structure Excavation	27.000	CY	50.00		
0050	211-B001	Topsoil for Slope Treatment, Contractor Furnished	1,732.000	CY	10.00		
0060	216-A001	Solid Sodding	132.000	SY	11.50		
0070	221-A001	Concrete Paved Ditch	2.000	CY	1,000.00		
0080	225-A001	Grassing	8.000	ACRE	1,650.00		
0090	225-C001	Mulch, Vegetative Mulch	16.000	TON	275.00		
0100	229-A001	Erosion Mat	289.000	SY	50.00		
0110	234-A001	Temporary Silt Fence	1,925.000	LF	5.00		
0120	234-C001	Super Silt Fence	200.000	LF	11.50		
0130	237-A002	Wattles, 20"	310.000	LF	8.80		
0140	246-A001	Sandbags	58.000	LF	6.60		
0150	249-B001	Remove and Reset Riprap	300.000	CY	50.00		
0160	304-D004	Granular Material, Size 57	25.000	TON	100.00		
0170	601-B001	Class "B" Structural Concrete, Minor Structures	24.000	CY	2,000.00		
0180	602-A001	Reinforcing Steel	150.000	LBS	5.00		
0190	603-CA011	18" Reinforced Concrete Pipe, Class III	16.000	LF	70.00		
0200	603-CA026	24" Reinforced Concrete Pipe, Class III	16.000	LF	70.00		
0210	603-CA066	42" Reinforced Concrete Pipe, Class III	8.000	LF	200.00		
0220	603-CA111	66" Reinforced Concrete Pipe, Class III	24.000	LF	400.00		
0230	603-RA002	18" Pipe Removed and Relaid	22.000	LF	50.00		
0240	603-RA003	24" Pipe Removed and Relaid	24.000	LF	50.00		
0250	603-RA007	42" Pipe Removed and Relaid	75.000	LF	100.00		
0260	603-RA011	66" Pipe Removed and Relaid	56.000	LF	150.00		

Repairing 8 Slides on I-22 & US 45, known as Federal Aid Project Nos. ER-0002-06(030) / 108055301, ER-0006-02(035) / 108050301, ER-0002-06(031) / 108052301, ER-0006-02(034) / 108053301, ER-0006-02(033) / 108054301, & ER-0006-02(032) / 108062301 in Lee County.					Phillips Contracting Co., Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,052,075.95					\$1,387,839.80		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	605-AA001	Geotextile for Subsurface Drainage, Type III	826.000	SY	3.50		
0280	605-O004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	750.000	LF	20.00		
0290	605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	340.000	LF	20.00		
0300	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	68.000	CY	100.00		
0310	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	1,483.000	CY	50.00		
0320	605-Z003	Underdrain Appurtenances, Sign	8.000	EA	150.00		
0330	605-Z006	Underdrain Appurtenances, Small Animal Guard	8.000	EA	150.00		
0340	618-A001	Maintenance of Traffic	1.000	LS	90,000.00		
0350	620-A001	Mobilization	1.000	LS	125,000.00		
0360	815-A002	Loose Riprap, Size 100	1,575.000	TON	55.00		
0370	815-E001	Geotextile under Riprap	1,375.000	SY	3.50		
0380	815-F002	Sediment Control Stone	20.000	TON	100.00		
0390	907-228-A002	Erosion Control Blanket, Type II	12,343.000	SY	2.50		