

Repairing 4 slides on US 45 and SR 30, known as Federal Aid Project Nos. ER-0926-00(027) / 108067301, & ER-2839-00(021) / 108064301 in Prentiss County.					Phillips Contracting Co., Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$360,876.50					\$488,448.50		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-B063	Removal of Concrete Paved Ditch	90.000	SY	10.00		
0020	203-EX021	Borrow Excavation, AH, FME, Class B9-6	6,920.000	CY	25.00		
0030	203-G001	Excess Excavation, FM, AH	6,920.000	CY	15.00		
0040	211-B001	Topsoil for Slope Treatment, Contractor Furnished	189.000	CY	30.00		
0050	221-A001	Concrete Paved Ditch	4.000	CY	1,000.00		
0060	225-A001	Grassing	4.000	ACRE	1,650.00		
0070	225-C001	Mulch, Vegetative Mulch	8.000	TON	275.00		
0080	229-A001	Erosion Mat	90.000	SY	50.00		
0090	234-A001	Temporary Silt Fence	595.000	LF	5.00		
0100	237-A002	Wattles, 20"	160.000	LF	8.80		
0110	605-AA001	Geotextile for Subsurface Drainage, Type III	747.000	SY	3.50		
0120	605-O004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	665.000	LF	20.00		
0130	605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	320.000	LF	20.00		
0140	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	63.000	CY	100.00		
0150	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	691.000	CY	50.00		
0160	605-Z003	Underdrain Appurtenances, Sign	13.000	EA	150.00		
0170	605-Z006	Underdrain Appurtenances, Small Animal Guard	13.000	EA	150.00		
0180	618-A001	Maintenance of Traffic	1.000	LS	45,000.00		
0190	620-A001	Mobilization	1.000	LS	60,000.00		
0200	907-228-A002	Erosion Control Blanket, Type II	3,777.000	SY	3.00		