

Call 05 Bridge Replacement on SR 7 over Cypress Creek, Bridge No. 85.9, known as Federal Aid Project No. BR-0019-02(055) / 106969301 in Yalobusha County.

Q1. Item 606-E005 Guard Rail, Terminal End Section, Flared appears to have a quantity discrepancy with the plans. Please confirm.

A1. See addendum.

Q2. Sheet 8003 requires that pipe piles receive a protective coating from the bottom of the cap extending to the 100 year scour elevation. Since the end bent piling are fully embedded, do the end bent piles require the protective coating?

A2. No.

Q3. The pay item for Concrete Bridge End Barrier, 33.5" is included in the plans, but not in the proposal. Is this an error in the proposal or the plans?

A3. See addendum.

Q4. Item 815-A008 Loose Rip Rap, Size 300 is shown as 1195 tons in the plans; however, it is shown as 1195 SY in the AASHTOWare Project Bids bid file. Please clarify.

A4. See addendum.