

Call 02 Reconstruction of US 11 from Cayten Street to Lakeshore Drive, also known as Federal Aid Project No. STP-2170-00(022) / 102246304 in Pearl River County.

Q1. I did not see any line items for slip casing of the traffic signal foundations. Is slip casing to be absorbed or was it not added in error?

A1. Slip casing is to be considered an absorbed item.

Q2. Notice to Bidders No. 15 does not allow precast inlets and junction boxes. In regards to the inlets, does this mean the entire structure or just the tops?

A2. ~~The non use of precast units applies to the entire structure.~~ **Revised Answer:** The bottoms may be precast; however, the tops shall be cast-in-place.

Q3. Is box culvert allowed to be precast? Please advise.

A3. No.

Q4. Will precast junction boxes be allowed?

A4. Only the precast junction boxes specifically shown and designated in the plans will be allowed. All others shall be cast-in-place.