

Repair of Bridges on Interstate 20 over Lynch Creek, known as Federal Aid Project No. BR-0020-01(249) / 107884301 in Hinds County.					Key, LLC	Gibson & Associates, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,016,314.95					\$2,087,464.00	\$2,147,409.00	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	202-B126	Removal of Fence, All Types	360.000	LF	32.50	1.20	
0020	618-A001	Maintenance of Traffic	1.000	LS	147,500.00	177,000.00	
0030	619-A1002	Temporary Traffic Stripe, Continuous White	440.000	LF	2.50	2.40	
0040	619-A2002	Temporary Traffic Stripe, Continuous Yellow	440.000	LF	2.50	3.00	
0050	619-A3002	Temporary Traffic Stripe, Skip White	880.000	LF	2.50	1.80	
0060	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	23.000	SF	7.50	9.00	
0070	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	1,158.000	SF	7.50	9.00	
0080	619-E1001	Flashing Arrow Panel, Type C	8.000	EA	800.00	960.00	
0090	619-G4005	Barricades, Type III, Single Faced	180.000	LF	13.00	15.60	
0100	619-G5001	Free Standing Plastic Drums	250.000	EA	35.00	42.00	
0110	619-G7001	Warning Lights, Type "B"	40.000	EA	95.00	114.00	
0120	620-A001	Mobilization	1.000	LS	260,500.00	200,000.00	
0130	626-A002	6" Thermoplastic Double Drop Traffic Stripe, Skip White	880.000	LF	6.00	3.60	
0140	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	440.000	LF	5.00	5.40	
0150	626-F002	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	440.000	LF	5.00	4.80	
0160	627-C001	Red-Clear Reflective Raised Markers	50.000	EA	25.00	12.00	
0170	907-618-M2001	Work Zone Law Enforcement	480.000	HRS	60.00	60.00	
0180	907-618-Q001	Traffic Queue Protection	390.000	HRS	140.00	168.00	
0190	907-619-E3001	Changeable Message Sign	14.000	EA	5,500.00	6,600.00	
0200	234-A001	Temporary Silt Fence	504.000	LF	15.50	14.40	
0210	815-A007	Loose Riprap, Size 300	2,103.000	TON	170.00	150.00	
0220	815-E001	Geotextile under Riprap	1,311.000	SY	8.50	4.20	
0230	907-202-B001	Removal of Bridge Deck, Hydrodemolition	2,208.000	SY	135.00	115.00	
0240	907-420-A001	Undersealing	21,600.000	LBS	4.95	5.76	
0250	907-804-O001	Bridge Deck Overlay Concrete	124.000	CY	2,575.00	2,400.00	
0260	907-808-A003	Joint Repair Without Epoxy	482.000	LF	10.00	12.00	

Repair of Bridges on Interstate 20 over Lynch Creek, known as Federal Aid Project No. BR-0020-01(249) / 107884301 in Hinds County.					Key, LLC	Gibson & Associates, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,016,314.95					\$2,087,464.00	\$2,147,409.00	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	907-823-A001	Preformed Joint Seal, Type I	481.000	LF	35.00	42.00	
0280	907-823-A002	Preformed Joint Seal, Type II	241.000	LF	38.00	45.60	
0290	907-823-B001	Saw Cut, Type I	962.000	LF	9.00	10.80	
0300	907-823-B002	Saw Cut, Type II	482.000	LF	10.00	12.00	
0310	907-824-PP003	Bridge Repair, Removal of Bridge Deck	719.000	SF	70.00	35.00	
0320	907-824-PP005	Bridge Repair, Epoxy Repair	5.000	CF	2,300.00	3,800.00	
0330	907-824-PP006	Bridge Repair, Bearing Replacement	108.000	EA	2,250.00	3,850.00	
0340	907-824-PP006	Bridge Repair, Cap Cleaning	8.000	EA	1,500.00	2,200.00	