

**Call 02 Bridge Replacements on US Highway 49 over Flat Branch, Bridge Nos. 8.0A & 8.0B, known as Federal Aid Project No. BRNH-0008-01(144)V21 / 102111303 in Harrison County.**

- Q1. The plans show pay item 618-E001 Detour Bridge Piling. The ebsx file does not include the pay item. Please revise to include.
- A1. See addendum.
- Q2. This project calls for 217-A001 Ditch Liner Pay Item. The proposal includes specifications for Flexamat concrete ditch liner. Which product is required on this project? Ditch Liner, per 2017 MDOT specifications is excelsior, jute mesh blanket which is not the same as concrete Flexamat. Please advise.
- A2. Both pay items 217-A001, Ditch Liner, and 907-240-A001, Interlocking Flexible Block Erosion Control System, are to be used on the project, and will be placed at the locations shown on Working Sheet Number 3-LT and 3-RT in the plans.
- Q3. On Sheet 8005 the Note states "Existing Piling in conflict with concrete piling shall be removed. Payment therefore will be made under pay item 202-B036 Removal of Piling." I do not see this item included in the pay item schedule.
- A3. The reference to Pay Item 202-B036, Removal of Piling, on Sheet 8005 is in error and should be disregarded. Removal of piling is to be included in Pay Item 202-A001, Removal of Obstructions.