

Bridge Replacement on SR 4 over the BNSF Railway & MS Central Railroad Company, Bridge No. 75.3, known as Federal Aid Project No. BR-0060-03(020) / 105333301 in Marshall County.					Century Construction Group, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,427,915.13						\$5,282,346.50	
Ref#	Item	Item Description	Item Qty	Units	1		
0010	201-A001	Clearing and Grubbing	1.000	LS		70,000.00	
0020	201-B001	Clearing and Grubbing	1.000	ACRE		3,949.42	
0030	202-A001	Removal of Obstructions	1.000	LS		346,000.00	
0040	202-B005	Removal of Asphalt Paved Ditch, All Depths	6,024.000	SY		8.75	
0050	202-B050	Removal of Concrete Combination Curb & Gutter	802.000	LF		12.50	
0060	202-B052	Removal of Concrete Driveways, All Depths	421.000	SY		15.00	
0070	202-B080	Removal of Concrete Sidewalk	461.000	SY		15.00	
0080	202-B165	Removal of Inlets, All Sizes	6.000	EA		1,499.97	
0090	202-B191	Removal of Pipe, 8" And Above	767.000	LF		12.50	
0100	202-B215	Removal of Sign Including Post & Footing	16.000	EA		156.25	
0110	203-A001	Unclassified Excavation, FM, AH	12,417.000	CY		7.50	
0120	203-EX020	Borrow Excavation, AH, FME, Class B9	7,944.000	CY		15.00	
0130	203-G001	Excess Excavation, FM, AH	500.000	CY		7.50	
0140	206-A001	Structure Excavation	848.000	CY		15.43	
0150	209-A005	Geotextile Stabilization, Type V, Non-Woven	7,763.000	SY		3.75	
0160	211-B001	Topsoil for Slope Treatment, Contractor Furnished	3,543.000	CY		1.25	
0170	213-C001	Superphosphate	4.000	TON		937.49	
0180	216-A001	Solid Sodding	1,018.000	SY		5.00	
0190	217-A001	Ditch Liner	10.000	SY		5.00	
0200	219-A001	Watering	453.000	KGAL		20.00	
0210	220-A001	Insect Pest Control	4.000	ACRE		30.00	
0220	221-A001	Concrete Paved Ditch	30.000	CY		745.31	
0230	223-A001	Mowing	7.000	ACRE		50.00	
0240	224-A001	Soil Reinforcing Mat	1,200.000	SY		5.00	
0250	225-A001	Grassing	7.000	ACRE		1,874.96	
0260	225-B001	Agricultural Limestone	4.000	TON		125.00	

Bridge Replacement on SR 4 over the BNSF Railway & MS Central Railroad Company, Bridge No. 75.3, known as Federal Aid Project No. BR-0060-03(020) / 105333301 in Marshall County.					Century Construction Group, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,427,915.13						\$5,282,346.50	
Ref#	Item	Item Description	Item Qty	Units	1		
0270	225-C001	Mulch, Vegetative Mulch	15.000	TON		312.50	
0280	226-A001	Temporary Grassing	7.000	ACRE		1,187.48	
0290	234-A001	Temporary Silt Fence	2,500.000	LF		5.00	
0300	237-A002	Wattles, 20"	2,728.000	LF		7.50	
0310	239-A001	Temporary Slope Drains	800.000	LF		11.25	
0320	246-A001	Sandbags	1,300.000	LF		6.25	
0330	249-A001	Riprap for Erosion Control	100.000	TON		93.75	
0340	304-B002	Granular Material, Class 3, Group D	3,610.000	TON		40.00	
0350	403-A003	12.5-mm, ST, Asphalt Pavement	1,047.000	TON		146.43	
0360	403-A006	19-mm, ST, Asphalt Pavement	1,178.000	TON		126.25	
0370	403-A015	9.5-mm, ST, Asphalt Pavement	768.000	TON		138.77	
0380	407-A001	Asphalt for Tack Coat	854.000	GAL		3.75	
0390	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	70.000	LF		12.50	
0400	502-A001	Reinforced Cement Concrete Bridge End Pavement	149.000	SY		350.16	
0410	503-C010	Saw Cut, Full Depth	60.000	LF		31.25	
0420	601-B001	Class "B" Structural Concrete, Minor Structures	44.000	CY		2,527.67	
0430	601-B002	Class "C" Structural Concrete, Minor Structures	2.000	CY		3,552.04	
0440	602-A001	Reinforcing Steel	3,198.000	LBS		2.38	
0450	603-ALT003	18" Type A Alternate Pipe	528.000	LF		37.18	
0460	603-CA011	18" Reinforced Concrete Pipe, Class III	936.000	LF		45.62	
0470	603-CA026	24" Reinforced Concrete Pipe, Class III	792.000	LF		60.00	
0480	603-CB003	18" Reinforced Concrete End Section	4.000	EA		1,249.97	
0490	603-CB004	24" Reinforced Concrete End Section	2.000	EA		1,562.47	
0500	603-CE002	22" x 13" Concrete Arch Pipe, Class A III	40.000	LF		62.50	
0510	603-CE008	29" x 18" Concrete Arch Pipe, Class A III	64.000	LF		78.12	
0520	603-CE028	58" x 36" Concrete Arch Pipe, Class A III	32.000	LF		356.24	

Bridge Replacement on SR 4 over the BNSF Railway & MS Central Railroad Company, Bridge No. 75.3, known as Federal Aid Project No. BR-0060-03(020) / 105333301 in Marshall County.					Century Construction Group, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,427,915.13						\$5,282,346.50	
Ref#	Item	Item Description	Item Qty	Units	1		
0530	603-CF002	22" x 13" Concrete Arch Pipe End Section	2.000	EA		1,499.97	
0540	603-CF003	29" x 18" Concrete Arch Pipe End Section	2.000	EA		1,749.96	
0550	603-CF007	58" x 36" Concrete Arch Pipe End Section	2.000	EA		4,499.90	
0560	604-A001	Castings	1,027.000	LBS		5.60	
0570	605-AA003	Geotextile for Subsurface Drainage, Type V, Non-Woven	36.000	SY		13.07	
0580	605-O003	4" Perforated Sewer Pipe for Underdrains, SDR 35	64.000	LF		19.82	
0590	605-P003	4" Non-perforated Sewer Pipe for Underdrains, SDR 35	52.000	LF		20.41	
0600	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	2.000	CY		124.07	
0610	606-B001	Guard Rail, Class A, Type 1	175.000	LF		25.17	
0620	606-D022	Guard Rail, Bridge End Section, Type 1	4.000	EA		2,999.94	
0630	606-E007	Guard Rail, Terminal End Section, Non-Flared	4.000	EA		3,487.43	
0640	608-B001	Concrete Sidewalk, With Reinforcement	1,010.000	SY		69.25	
0650	609-D001	Combination Concrete Curb and Gutter Type 1	78.000	LF		38.34	
0660	609-D012	Combination Concrete Curb and Gutter Type 3A Modified	1,314.000	LF		34.56	
0670	612-B001	Flowable Fill, Non-Excavatable	24.000	CY		268.08	
0680	613-D005	Adjustment of Manhole	7.000	EA		3,173.32	
0690	614-A001	Concrete Driveway, Without Reinforcement	600.000	SY		80.94	
0700	614-B001	Concrete Driveway, With Reinforcement	253.000	SY		87.81	
0710	615-A002	Concrete Bridge End Barrier, 33.5"	40.000	LF		81.00	
0720	617-A001	Right-of-Way Marker	48.000	EA		190.39	
0730	618-A001	Maintenance of Traffic	1.000	LS		103,000.00	
0740	619-A1003	Temporary Traffic Stripe, Continuous White, Paint	5,291.000	LF		0.94	
0750	619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	5,822.000	LF		0.94	
0760	619-A5002	Temporary Traffic Stripe, Detail, Paint	349.000	LF		1.25	
0770	619-A6004	Temporary Traffic Stripe, Legend, Paint	311.000	LF		1.87	
0780	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	221.000	SF		7.50	

Bridge Replacement on SR 4 over the BNSF Railway & MS Central Railroad Company, Bridge No. 75.3, known as Federal Aid Project No. BR-0060-03(020) / 105333301 in Marshall County.					Century Construction Group, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,427,915.13						\$5,282,346.50	
Ref#	Item	Item Description	Item Qty	Units	1		
0790	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	224.000	SF		7.50	
0800	619-G4001	Barricades, Type III, Double Faced	12.000	LF		30.00	
0810	619-G4005	Barricades, Type III, Single Faced	72.000	LF		15.00	
0820	619-G5001	Free Standing Plastic Drums	60.000	EA		43.75	
0830	619-G7001	Warning Lights, Type "B"	3.000	EA		125.00	
0840	620-A001	Mobilization	1.000	LS		525,000.00	
0850	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	5,291.000	LF		1.87	
0860	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	5,822.000	LF		1.87	
0870	626-G004	Thermoplastic Double Drop Detail Stripe, White	349.000	LF		3.75	
0880	626-H002	Thermoplastic Double Drop Legend, White	311.000	LF		6.25	
0890	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	63.000	EA		22.50	
0900	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	25.000	SF		25.00	
0910	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	27.000	SF		30.00	
0920	630-C003	Steel U-Section Posts, 3.0 lb/ft	97.000	LF		10.00	
0930	630-F006	Delineators, Guard Rail, White	22.000	EA		22.50	
0940	630-F007	Delineators, Guard Rail, Yellow	22.000	EA		22.50	
0950	630-G005	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	4.000	EA		100.00	
0960	699-A001	Roadway Construction Stakes	1.000	LS		85,588.37	
0970	815-A007	Loose Riprap, Size 300	25.000	TON		93.75	
0980	815-E001	Geotextile under Riprap	67.000	SY		3.75	
0990	815-F002	Sediment Control Stone	12.000	TON		145.40	
1000	907-619-E3001	Changeable Message Sign	4.000	EA		8,749.81	
1010	907-899-A001	Railway-Highway Provisions	1.000	LS		120,000.00	
1020	304-F001	3/4" and Down Crushed Stone Base	7,513.000	TON			
1030	304-F002	Size 610 Crushed Stone Base	7,513.000	TON		56.25	
1040	304-F003	Size 825B Crushed Stone Base	7,513.000	TON			

Bridge Replacement on SR 4 over the BNSF Railway & MS Central Railroad Company, Bridge No. 75.3, known as Federal Aid Project No. BR-0060-03(020) / 105333301 in Marshall County.					Century Construction Group, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,427,915.13					\$5,282,346.50		
Ref#	Item	Item Description	Item Qty	Units	1		
1050	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	16.000	CY	77.57		
1060	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	16.000	CY			
1070	501-K001	Transverse Grooving	853.000	SY	3.13		
1080	803-D007	HP 14 x 89 Steel Piling	2,625.000	LF	80.00		
1090	803-P003	30" Steel Pipe Piling, Wall Thickness 0.500"	845.000	LF	181.52		
1100	804-C026	110' Prestressed Concrete Beam, Type IV	764.000	LF	248.27		
1110	804-C095	65' Prestressed Concrete Beam, Type IV	902.000	LF	233.91		
1120	805-A001	Reinforcement	97,542.000	LBS	1.13		
1130	813-A002	Concrete Railing, 32"	484.000	LF	81.00		
1140	813-B001	Concrete-Steel Railing	480.000	LF	432.32		
1150	815-D001	Concrete Slope Paving	95.000	CY	617.23		
1160	907-803-B001	Conventional Static Pile Load Test	1.000	EA	5,000.00		
1170	907-803-I003	PDA Test Pile, HP Steel Pile	1.000	EA	20,000.00		
1180	907-803-I004	PDA Test Pile, Steel Pipe Pile	1.000	EA	40,000.00		
1190	907-803-J001	Pile Restrike	2.000	EA	1,116.17		
1200	907-804-A002	Bridge Concrete, Class AA	226.000	CY	1,016.79		
1210	907-804-A004	Bridge Concrete, Class BD	336.000	CY	1,150.25		