

Intersection Collision Warning System installation on SR 1 at Friars Point Road, known as Federal Aid Project No. STP-0052-01(010) / 107684301 in Coahoma County.					Webster Electric Co., LLC			
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$426,306.12							\$659,381.90	
Ref#	Item	Item Description	Item Qty	Units	1			
0010	202-B007	Removal of Asphalt Pavement, All Depths	78.000	SY			114.35	
0020	202-B191	Removal of Pipe, 8" And Above	4.000	LF			860.00	
0030	202-B217	Removal of Sign Post and Footing	2.000	EA			570.00	
0040	203-EX040	Borrow Excavation, AH, LVM, Class B9	783.000	CY			57.20	
0050	209-A005	Geotextile Stabilization, Type V, Non-Woven	961.000	SY			5.75	
0060	225-A001	Grassing	1.000	ACRE			4,575.00	
0070	225-C001	Mulch, Vegetative Mulch	1.000	TON			460.00	
0080	234-A001	Temporary Silt Fence	1,220.000	LF			4.55	
0090	237-A002	Wattles, 20"	260.000	LF			8.00	
0100	304-B002	Granular Material, Class 3, Group D	73.000	TON			206.00	
0110	403-A005	19-mm, MT, Asphalt Pavement	154.000	TON			300.00	
0120	403-A014	9.5-mm, MT, Asphalt Pavement	388.000	TON			270.00	
0130	406-A002	Cold Milling of Bituminous Pavement, All Depths	2,400.000	SY			8.50	
0140	407-A001	Asphalt for Tack Coat	412.000	GAL			4.20	
0150	503-C010	Saw Cut, Full Depth	152.000	LF			23.00	
0160	601-B001	Class "B" Structural Concrete, Minor Structures	3.000	CY			4,000.00	
0170	603-CE013	36" x 23" Concrete Arch Pipe, Class A III	16.000	LF			285.00	
0180	603-CF004	36" x 23" Concrete Arch Pipe End Section	2.000	EA			2,860.00	
0190	609-D003	Combination Concrete Curb and Gutter Type 2	152.000	LF			69.00	
0200	616-A002	Concrete Median and/or Island Pavement, 11-inch	38.000	SY			286.00	
0210	618-A001	Maintenance of Traffic	1.000	LS			60,000.00	
0220	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	60.000	SF			11.45	
0230	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	120.000	SF			11.45	
0240	620-A001	Mobilization	1.000	LS			60,000.00	
0250	626-C003	6" Thermoplastic Edge Stripe, Continuous White	2,292.000	LF			2.30	
0260	626-D004	6" Thermoplastic Traffic Stripe, Skip Yellow	603.000	LF			1.75	

Intersection Collision Warning System installation on SR 1 at Friars Point Road, known as Federal Aid Project No. STP-0052-01(010) / 107684301 in Coahoma County.					Webster Electric Co., LLC			
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$426,306.12							\$659,381.90	
Ref#	Item	Item Description	Item Qty	Units			1	
0270	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	1.000	MI			5,720.00	
0280	626-H004	Thermoplastic Legend, White	50.000	SF			23.30	
0290	626-H005	Thermoplastic Legend, White	651.000	LF			9.15	
0300	627-C001	Red-Clear Reflective Raised Markers	14.000	EA			45.75	
0310	627-D001	Two-Way Yellow Reflective Raised Markers	24.000	EA			45.75	
0320	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	107.000	SF			45.75	
0330	630-C001	Square Tube Posts, 4.0 lb/ft	40.000	LF			17.20	
0340	638-A004	Flasher Assembly, ICWS, Watch For Traffic	2.000	EA			3,705.00	
0350	638-A005	Flasher Assembly, ICWS, Watch For Entering Traffic	2.000	EA			4,010.00	
0360	660-A003	Equipment Cabinet, Type B	1.000	EA			10,185.00	
0370	699-A001	Roadway Construction Stakes	1.000	LS			6,410.00	
0380	907-630-O001	Remove and Reset Sign Assembly	1.000	EA			585.00	
0390	907-632-J001	Power Service Pedestal	1.000	EA			16,575.00	
0400	907-634-F002	Detector Pole with Foundation, 35' Pole	4.000	EA			7,180.00	
0410	907-636-B007	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 12, 5 Conductor	2,272.000	LF			2.20	
0420	907-636-B028	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 8, 3 Conductor	310.000	LF			3.00	
0430	907-637-A002	Pullbox Enclosure, Type 2	5.000	EA			1,155.00	
0440	907-637-A003	Pullbox Enclosure, Type 3	1.000	EA			1,345.00	
0450	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	1,732.000	LF			6.60	
0460	907-637-C030	Traffic Signal Conduit, Underground, Type 4, 3"	50.000	LF			7.70	
0470	907-637-D003	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3"	295.000	LF			17.10	
0480	907-641-A002	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2	2.000	EA			7,705.00	
0490	907-641-B002	Signal Advanced Radar Vehicle Detection Sensor, Type 2	2.000	EA			7,705.00	
0500	907-641-D001	Radar Vehicle Detection Cable	450.000	LF			3.20	
0510	304-F001	3/4" and Down Crushed Stone Base	645.000	TON				
0520	304-F002	Size 610 Crushed Stone Base	645.000	TON			91.50	

Intersection Collision Warning System installation on SR 1 at Friars Point Road, known as Federal Aid Project No. STP-0052-01(010) / 107684301 in Coahoma County.				Webster Electric Co., LLC			
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$426,306.12				\$659,381.90			
Ref#	Item	Item Description	Item Qty	Units	1		
0530	304-F003	Size 825B Crushed Stone Base	645.000	TON			

Letting Date: 9/24/2019

Call Number: 09

Page 3 of 3