

Mill & Overlay approximately 5 miles of SR 471 from Grant's Ferry Road to SR 25, known as State Project No. MP-5471-61(002) / 306549301 in Rankin County.					Dickerson & Bowen, Inc.	APAC - Mississippi, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,207,274.31					\$2,498,081.32	\$2,669,019.87	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	202-B003	Removal of Asphalt Curb	110.000	LF	10.75	17.96	
0020	202-B007	Removal of Asphalt Pavement, All Depths	3,293.000	SY	37.00	40.00	
0030	203-G001	Excess Excavation, FM, AH	353.000	CY	25.00	65.00	
0040	304-D002	Granular Material, Crushed Stone	1,340.000	TON	65.50	68.20	
0050	310-B001	Size I Stabilizer Aggregate, Coarse	50.000	TON	25.00	130.00	
0060	403-A002	12.5-mm, MT, Asphalt Pavement	11,265.000	TON	94.25	95.00	
0070	403-B002	12.5-mm, MT, Asphalt Pavement, Leveling	3,235.000	TON	130.50	115.00	
0080	406-D001	Fine Milling of Bituminous Pavement, All Depths	93,545.000	SY	3.00	2.60	
0090	407-A001	Asphalt for Tack Coat	5,188.000	GAL	3.15	3.86	
0100	609-E001	Bituminous Curb	110.000	LF	35.00	26.63	
0110	618-A001	Maintenance of Traffic	1.000	LS	135,000.00	250,000.00	
0120	619-A1001	Temporary Traffic Stripe, Continuous White	20.000	MI	750.00	750.00	
0130	619-A2001	Temporary Traffic Stripe, Continuous Yellow	17.000	MI	750.00	750.00	
0140	619-A3002	Temporary Traffic Stripe, Skip White	3,256.000	LF	0.50	0.50	
0150	619-A4002	Temporary Traffic Stripe, Skip Yellow	1.000	MI	1,000.00	1,000.00	
0160	619-A5001	Temporary Traffic Stripe, Detail	16,000.000	LF	0.05	0.05	
0170	619-A6001	Temporary Traffic Stripe, Legend	819.000	SF	0.75	0.75	
0180	619-A6002	Temporary Traffic Stripe, Legend	4,452.000	LF	0.25	0.25	
0190	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	195.000	SF	8.00	8.00	
0200	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	500.000	SF	8.00	8.00	
0210	619-G4001	Barricades, Type III, Double Faced	24.000	LF	15.00	15.00	
0220	620-A001	Mobilization	1.000	LS	150,000.00	250,000.00	
0230	626-A002	6" Thermoplastic Double Drop Traffic Stripe, Skip White	1,650.000	LF	1.00	1.00	
0240	626-B001	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	1,800.000	LF	0.65	0.65	
0250	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	10.000	MI	3,200.00	3,200.00	
0260	626-D001	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	1.000	MI	1,600.00	1,600.00	

Mill & Overlay approximately 5 miles of SR 471 from Grant's Ferry Road to SR 25, known as State Project No. MP-5471-61(002) / 306549301 in Rankin County.					Dickerson & Bowen, Inc.	APAC - Mississippi, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,207,274.31					\$2,498,081.32	\$2,669,019.87	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	9.000	MI	3,200.00	3,200.00	
0280	626-G002	Thermoplastic Detail Stripe, White	11,250.000	LF	1.15	1.15	
0290	626-G003	Thermoplastic Detail Stripe, Yellow	17,900.000	LF	1.15	1.15	
0300	626-H004	Thermoplastic Legend, White	820.000	SF	5.00	5.00	
0310	626-H005	Thermoplastic Legend, White	2,970.000	LF	2.50	2.50	
0320	627-J001	Two-Way Clear Reflective High Performance Raised Markers	600.000	EA	6.00	6.00	
0330	627-K001	Red-Clear Reflective High Performance Raised Markers	85.000	EA	6.00	6.00	
0340	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	930.000	EA	6.00	6.00	
0350	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	200.00	178.99	
0360	907-641-A002	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2	4.000	EA	8,093.53	8,097.05	
0370	907-641-D001	Radar Vehicle Detection Cable	300.000	LF	10.45	10.45	