

Safety Improvements on US 49 from the Stone County Line to South Gate Road, known as Federal Aid Project No. HSIP-0008-00(005) / 107464301 in Forrest County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Dunn Roadbuilders, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$40,095,523.41					\$40,974,061.56	\$44,142,358.23	\$49,722,973.40
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0008	201-B001	Clearing and Grubbing	215.000	ACRE	2,000.00	4,742.14	7,431.00
0020	201-D002	Random Clearing	4.000	ACRE	7,000.00	5,645.89	7,431.00
0030	202-B004	Removal of Asphalt Driveways, All Depths	1,964.000	SY	5.00	6.03	46.40
0040	202-B007	Removal of Asphalt Pavement, All Depths	82,909.000	SY	6.25	3.19	5.80
0050	202-B019	Removal of Box Culvert	213.000	LF	290.00	485.66	268.00
0060	202-B052	Removal of Concrete Driveways, All Depths	262.000	SY	13.00	9.05	10.00
0080	202-B063	Removal of Concrete Paved Ditch	153.000	SY	15.00	9.05	22.00
0082	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	25,582.000	SY	15.25	24.43	19.00
0090	202-B073	Removal of Concrete Pavement, All Depths	160.000	SY	215.00	13.58	170.00
0100	202-B092	Removal of Curb, All Types	186.000	LF	8.00	8.76	11.00
0110	202-B098	Removal of Debris and Sand From Box Culvert, Less Than 6-foot Width	3,300.000	LF	30.00	7.90	31.00
0120	202-B114	Removal of Debris and Sand From Pipe, All Sizes	11,500.000	LF	25.00	4.52	23.00
0130	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	975.000	LF	9.00	9.03	8.00
0140	202-B163	Removal of Inlet Tops	4.000	EA	600.00	387.92	710.00
0150	202-B165	Removal of Inlets, All Sizes	1.000	EA	600.00	646.54	710.00
0160	202-B170	Removal of Junction Box	1.000	EA	600.00	646.54	710.00
0170	202-B191	Removal of Pipe, 8" And Above	3,662.000	LF	10.00	6.47	20.00
0180	202-B215	Removal of Sign Including Post & Footing	318.000	EA	425.00	434.73	400.00
0190	202-B229	Removal of Soil Cement, All Depths	257.000	SY	9.50	27.27	9.00
0200	202-B240	Removal of Traffic Stripe	9,250.000	LF	2.25	2.26	2.10
0210	203-A001	Unclassified Excavation, FM, AH	404,900.000	CY	5.33	7.67	11.20
0220	203-EX018	Borrow Excavation, AH, FME, Class B7-6	83,850.000	CY	9.65	7.48	13.00
0230	203-G001	Excess Excavation, FM, AH	179,350.000	CY	4.26	6.28	9.20
0240	206-A001	Structure Excavation	6,291.000	CY	13.00	10.91	12.00
0250	206-B001	Select Material for Undercuts, Contractor Furnished, FM	1,028.000	CY	41.00	31.98	114.00
0260	209-A005	Geotextile Stabilization, Type V, Non-Woven	266,900.000	SY	1.50	1.61	2.10

Safety Improvements on US 49 from the Stone County Line to South Gate Road, known as Federal Aid Project No. HSIP-0008-00(005) / 107464301 in Forrest County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Dunn Roadbuilders, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$40,095,523.41					\$40,974,061.56	\$44,142,358.23	\$49,722,973.40
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	211-B001	Topsoil for Slope Treatment, Contractor Furnished	9,450.000	CY	0.85	11.29	0.10
0280	213-C001	Superphosphate	140.000	TON	950.00	846.88	312.00
0290	216-A001	Solid Sodding	3,719.000	SY	5.50	5.08	4.20
0300	217-A001	Ditch Liner	9,753.000	SY	2.50	2.20	1.30
0310	219-A001	Watering	80.000	KGAL	20.00	20.00	20.00
0320	220-A001	Insect Pest Control	140.000	ACRE	30.00	30.00	30.00
0330	221-A001	Concrete Paved Ditch	293.000	CY	550.00	908.61	437.00
0340	223-A001	Mowing	1,674.000	ACRE	50.00	50.00	50.00
0350	225-A001	Grassing	279.000	ACRE	1,100.00	1,129.18	1,404.00
0360	225-B001	Agricultural Limestone	140.000	TON	110.00	395.21	130.00
0370	225-C001	Mulch, Vegetative Mulch	558.000	TON	220.00	225.84	260.00
0380	226-A001	Temporary Grassing	279.000	ACRE	1,100.00	988.03	780.00
0390	227-A001	Hydroseeding	55.000	ACRE	2,500.00	2,540.65	1,820.00
0400	234-A001	Temporary Silt Fence	58,500.000	LF	3.12	3.27	1.60
0410	234-C001	Super Silt Fence	2,075.000	LF	11.00	7.90	12.50
0420	234-D001	Inlet Siltation Guard	48.000	EA	200.00	423.41	572.00
0430	234-E001	Reset Inlet Siltation Guard	48.000	EA	50.00	28.23	208.00
0440	234-F001	Turbidity Barrier	70.000	LF	16.00	13.55	30.00
0450	236-A008	Silt Basin, Type D	51.000	EA	200.00	1,900.00	1,420.00
0460	237-A002	Wattles, 20"	7,000.000	LF	5.35	5.36	6.80
0470	239-A001	Temporary Slope Drains	1,835.000	LF	3.50	10.00	10.50
0480	246-A001	Sandbags	3,080.000	LF	4.25	1.81	6.50
0490	247-A001	Temporary Stream Diversion	2.000	EA	100.00	10,909.35	41,600.00
0500	249-A001	Riprap for Erosion Control	13,800.000	TON	37.00	76.09	80.00
0510	403-A003	12.5-mm, ST, Asphalt Pavement	21,775.000	TON	100.00	105.00	91.00
0520	403-A004	19-mm, HT, Asphalt Pavement	4,726.000	TON	95.00	99.13	94.00

Safety Improvements on US 49 from the Stone County Line to South Gate Road, known as Federal Aid Project No. HSIP-0008-00(005) / 107464301 in Forrest County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Dunn Roadbuilders, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$40,095,523.41					\$40,974,061.56	\$44,142,358.23	\$49,722,973.40
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0530	403-A006	19-mm, ST, Asphalt Pavement	35,873.000	TON	99.00	99.64	86.00
0540	403-A015	9.5-mm, ST, Asphalt Pavement	17,576.000	TON	103.00	112.63	117.00
0550	403-C003	19-mm, ST, Asphalt Pavement, Trench Widening	1,167.000	TON	139.00	95.97	109.00
0560	403-D001	12.5-mm, HT, Asphalt Pavement, Polymer Modified	17,418.000	TON	90.00	91.34	84.00
0570	403-D007	9.5-mm, HT, Asphalt Pavement, Polymer Modified	14,276.000	TON	95.00	99.42	99.00
0580	406-A002	Cold Milling of Bituminous Pavement, All Depths	17,947.000	SY	3.80	4.40	2.60
0590	406-B001	Cold Milling of Concrete Pavement, All Depths	765.000	SY	23.70	15.52	13.00
0600	407-A001	Asphalt for Tack Coat	53,966.000	GAL	2.60	2.82	3.60
0610	413-D003	Cleaning and Filling Joints in PCC Pavement	600.000	LF	13.05	12.42	11.50
0620	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	40,152.000	LF	3.35	3.16	3.00
0630	423-A001	Rumble Strips, Ground In	17.000	MI	295.00	293.56	270.00
0640	501-D001	Expansion Joints, With Dowels	60.000	LF	22.00	22.58	21.00
0650	503-A003	9" and Variable Reinforced Concrete Pavement, Broom Finish	160.000	SY	375.00	363.56	335.00
0660	503-C010	Saw Cut, Full Depth	56,595.000	LF	5.75	5.93	5.50
0670	503-E002	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted	188.000	EA	17.00	17.70	16.30
0680	503-F002	1" Smooth Dowel Bars, Drilled & Epoxied or Grouted	144.000	EA	17.50	17.70	16.30
0690	601-A001	Class "B" Structural Concrete	1,015.000	CY	1,350.00	1,491.22	1,248.00
0700	601-B001	Class "B" Structural Concrete, Minor Structures	431.000	CY	1,350.00	1,433.34	1,548.00
0710	602-A001	Reinforcing Steel	180,537.000	LBS	1.00	1.44	1.05
0720	603-ALT003	18" Type A Alternate Pipe	1,412.000	LF	28.40	34.79	60.00
0730	603-ALT006	24" Type A Alternate Pipe	220.000	LF	38.00	42.04	71.00
0740	603-ALT014	42" Type A Alternate Pipe	64.000	LF	75.00	94.58	104.00
0750	603-CA012	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	4,792.000	LF	38.00	40.73	66.00
0760	603-CA027	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	1,384.000	LF	47.65	52.00	77.00
0762	603-CA038	24" Reinforced Concrete Pipe, Class V, Jacked or Bored	120.000	LF	450.00	911.02	590.00
0780	603-CA041	30" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	1,400.000	LF	59.00	64.61	87.40

Safety Improvements on US 49 from the Stone County Line to South Gate Road, known as Federal Aid Project No. HSIP-0008-00(005) / 107464301 in Forrest County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Dunn Roadbuilders, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$40,095,523.41					\$40,974,061.56	\$44,142,358.23	\$49,722,973.40
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0782	603-CA053	30" Reinforced Concrete Pipe, Class V, Jacked or Bored	120.000	LF	600.00	985.82	765.00
0800	603-CA056	36" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	768.000	LF	80.00	98.08	109.00
0804	603-CA065	36" Reinforced Concrete Pipe, Class V, Jacked or Bored	264.000	LF	700.00	1,007.61	896.00
0820	603-CA067	42" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	296.000	LF	84.00	123.13	115.00
0830	603-CA077	48" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	152.000	LF	103.00	131.86	137.00
0832	603-CA086	48" Reinforced Concrete Pipe, Class V, Jacked or Bored	88.000	LF	950.00	1,168.42	1,093.00
0850	603-CA088	54" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	96.000	LF	126.00	166.37	164.00
0860	603-CA100	60" Reinforced Concrete Pipe, Class III, Rubber Type Gasket	336.000	LF	153.00	186.88	186.00
0870	603-CB003	18" Reinforced Concrete End Section	96.000	EA	700.00	686.91	1,240.00
0880	603-CB004	24" Reinforced Concrete End Section	37.000	EA	760.00	978.60	1,311.00
0890	603-CB005	30" Reinforced Concrete End Section	29.000	EA	800.00	1,067.97	1,421.00
0900	603-CB006	36" Reinforced Concrete End Section	11.000	EA	1,200.00	1,425.53	1,749.00
0910	603-CB007	42" Reinforced Concrete End Section	5.000	EA	1,400.00	1,962.80	2,186.00
0920	603-CB008	48" Reinforced Concrete End Section	3.000	EA	1,500.00	2,220.63	2,295.00
0930	603-CB009	54" Reinforced Concrete End Section	2.000	EA	1,750.00	2,313.78	2,514.00
0940	603-CB010	60" Reinforced Concrete End Section	1.000	EA	2,100.00	2,910.32	2,732.00
0950	603-CE003	22" x 13" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	352.000	LF	43.50	49.47	71.00
0960	603-CE009	29" x 18" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	160.000	LF	52.50	58.41	82.00
0970	603-CE014	36" x 23" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	448.000	LF	65.00	80.62	93.00
0980	603-CE019	44" x 27" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	232.000	LF	78.00	110.45	109.00
0990	603-CE024	51" x 31" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	840.000	LF	95.00	129.03	131.00
1000	603-CE029	58" x 36" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	504.000	LF	115.00	161.09	153.00
1010	603-CF002	22" x 13" Concrete Arch Pipe End Section	11.000	EA	750.00	686.91	1,202.00
1020	603-CF003	29" x 18" Concrete Arch Pipe End Section	4.000	EA	770.00	856.27	1,366.00
1030	603-CF004	36" x 23" Concrete Arch Pipe End Section	6.000	EA	850.00	1,496.15	1,421.00
1040	603-CF005	44" x 27" Concrete Arch Pipe End Section	5.000	EA	1,100.00	2,037.20	1,885.00

Safety Improvements on US 49 from the Stone County Line to South Gate Road, known as Federal Aid Project No. HSIP-0008-00(005) / 107464301 in Forrest County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Dunn Roadbuilders, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$40,095,523.41					\$40,974,061.56	\$44,142,358.23	\$49,722,973.40
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1050	603-CF006	51" x 31" Concrete Arch Pipe End Section	14.000	EA	1,300.00	1,712.54	2,186.00
1060	603-CF007	58" x 36" Concrete Arch Pipe End Section	5.000	EA	1,400.00	2,220.63	2,339.00
1070	603-SB012	18" Branch Connections, Stub into Box Culvert	4.000	EA	1,200.00	1,529.21	1,639.00
1080	603-SB016	18" Branch Connections, Stub into Concrete Pipe	3.000	EA	1,200.00	1,835.05	1,639.00
1090	603-SB028	24" Branch Connections, Stub into Box Culvert	2.000	EA	1,300.00	1,835.05	1,639.00
1100	603-SB030	24" Branch Connections, Stub into Concrete Pipe	3.000	EA	1,300.00	1,835.05	1,639.00
1110	603-SB036	30" Branch Connections, Stub into Box Culvert	2.000	EA	1,300.00	1,835.05	1,639.00
1120	603-SB041	36" Branch Connections, Stub into Box Culvert	2.000	EA	1,300.00	2,446.73	1,639.00
1130	603-SB044	36" x 23" Branch Connections, Stub into Box Culvert	1.000	EA	1,300.00	2,446.73	1,639.00
1140	604-B001	Gratings	11,750.000	LBS	4.00	2.16	2.80
1150	606-B001	Guard Rail, Class A, Type 1	1,950.000	LF	25.00	25.97	24.00
1160	606-C003	Guard Rail, Cable Anchor, Type 1	8.000	EA	895.00	903.27	832.00
1170	606-D023	Guard Rail, Bridge End Section, Type I, Metal Post	2.000	EA	2,900.00	2,992.07	2,756.00
1180	606-E007	Guard Rail, Terminal End Section, Non-Flared	10.000	EA	3,200.00	3,330.79	3,068.00
1190	609-B002	Concrete Curb, Header	142.000	LF	39.00	38.53	37.00
1200	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	14,634.000	LF	26.00	27.17	23.50
1210	609-D012	Combination Concrete Curb and Gutter Type 3A Modified	234.000	LF	40.00	37.75	37.00
1220	612-B001	Flowable Fill, Non-Excavatable	68.000	CY	238.00	564.54	382.00
1230	614-B003	Concrete Driveway, With Reinforcement, 6-inch Thickness	225.000	SY	130.00	95.39	114.00
1240	615-A022	Concrete Type IV Modified Cast-in-Place Median Barrier	240.000	LF	340.00	199.92	303.00
1250	616-A001	Concrete Median and/or Island Pavement, 10-inch	322.000	SY	120.00	138.67	105.00
1260	616-A004	Concrete Median and/or Island Pavement, 4-inch	3,244.000	SY	65.00	71.06	59.00
1270	617-B001	Permanent Easement Marker	76.000	EA	295.00	169.36	214.00
1280	618-A001	Maintenance of Traffic	1.000	LS	800,000.00	886,038.91	2,000,000.00
1290	619-A1001	Temporary Traffic Stripe, Continuous White	23.000	MI	1,100.00	1,129.08	1,040.00
1300	619-A2001	Temporary Traffic Stripe, Continuous Yellow	20.000	MI	1,100.00	1,129.08	1,040.00

Safety Improvements on US 49 from the Stone County Line to South Gate Road, known as Federal Aid Project No. HSIP-0008-00(005) / 107464301 in Forrest County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Dunn Roadbuilders, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$40,095,523.41					\$40,974,061.56	\$44,142,358.23	\$49,722,973.40
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1310	619-A3001	Temporary Traffic Stripe, Skip White	23.000	MI	1,100.00	1,129.08	1,040.00
1320	619-A5001	Temporary Traffic Stripe, Detail	79,451.000	LF	0.11	0.11	0.10
1330	619-A6001	Temporary Traffic Stripe, Legend	1,512.000	SF	1.10	1.13	1.00
1340	619-A6002	Temporary Traffic Stripe, Legend	2,774.000	LF	1.10	1.13	1.00
1350	619-C6001	Red-Clear Reflective High Performance Raised Marker	224.000	EA	5.50	5.65	5.00
1360	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	301.000	SF	16.50	16.94	16.00
1370	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	2,954.000	SF	16.50	16.94	16.00
1380	619-E1001	Flashing Arrow Panel, Type C	5.000	EA	3,900.00	3,951.79	3,640.00
1390	619-F1001	Concrete Median Barrier, Precast	6,260.000	LF	20.00	46.33	21.80
1400	619-F2001	Remove and Reset Concrete Median Barrier, Precast	4,010.000	LF	15.00	13.57	8.00
1410	619-G4001	Barricades, Type III, Double Faced	48.000	LF	39.00	39.52	36.00
1420	619-G4005	Barricades, Type III, Single Faced	588.000	LF	39.00	39.52	36.00
1430	619-G5001	Free Standing Plastic Drums	396.000	EA	63.00	62.10	58.00
1440	619-G7001	Warning Lights, Type "B"	43.000	EA	165.00	169.36	156.00
1450	619-G8001	Warning Lights, Type "C"	203.000	EA	275.00	282.27	260.00
1460	619-J1005	Impact Attenuator, 70 MPH	2.000	EA	10,000.00	10,726.29	9,880.00
1470	619-J2005	Impact Attenuator, 70 MPH, Replacement Package	2.000	EA	2,900.00	2,992.07	2,756.00
1480	619-J3001	Remove and Reset Impact Attenuator	2.000	EA	2,900.00	2,992.07	2,756.00
1490	620-A001	Mobilization	1.000	LS	3,660,000.00	2,139,214.00	4,171,000.00
1500	626-A004	6" Thermoplastic Traffic Stripe, Skip White	40.000	MI	1,650.00	1,693.62	1,560.00
1510	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	34.000	MI	3,300.00	3,387.25	3,120.00
1520	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	30.000	MI	3,300.00	3,387.25	3,120.00
1530	626-G002	Thermoplastic Detail Stripe, White	126,569.000	LF	1.45	1.41	1.30
1540	626-G003	Thermoplastic Detail Stripe, Yellow	73,553.000	LF	1.45	1.41	1.30
1550	626-H004	Thermoplastic Legend, White	9,520.000	SF	6.75	6.77	6.30
1560	626-H005	Thermoplastic Legend, White	2,251.000	LF	2.20	2.26	2.10

Safety Improvements on US 49 from the Stone County Line to South Gate Road, known as Federal Aid Project No. HSIP-0008-00(005) / 107464301 in Forrest County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Dunn Roadbuilders, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$40,095,523.41					\$40,974,061.56	\$44,142,358.23	\$49,722,973.40
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1570	627-J001	Two-Way Clear Reflective High Performance Raised Markers	854.000	EA	5.55	5.65	5.20
1580	627-K001	Red-Clear Reflective High Performance Raised Markers	6,906.000	EA	5.55	5.65	5.20
1590	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	5,485.000	EA	5.55	5.65	5.20
1600	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	1,820.000	SF	23.00	23.71	21.90
1610	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	272.000	SF	25.00	25.97	24.00
1620	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	968.000	SF	25.00	24.84	23.00
1630	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	1,100.000	SF	32.00	32.74	30.00
1640	630-C002	Steel U-Section Posts, 2.0 lb/ft	301.000	LF	11.00	11.29	11.00
1650	630-C003	Steel U-Section Posts, 3.0 lb/ft	4,272.000	LF	13.00	13.55	13.00
1660	630-D008	Structural Steel Beams, W6 x 9	1,091.000	LF	73.00	73.39	68.00
1670	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	1,018.000	LBS	2.75	2.82	2.60
1680	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	1,054.000	LBS	2.75	2.82	2.60
1690	630-F002	Delineators, Flexible Post Mounted, Crossover, Type I, Yellow	80.000	EA	72.00	73.39	67.60
1700	630-F006	Delineators, Guard Rail, White	85.000	EA	20.00	20.32	18.70
1710	630-G005	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	6.000	EA	85.00	84.68	78.00
1720	630-K001	Welded & Seamless Steel Pipe Posts, 3 1/2"	343.000	LF	63.00	62.10	57.00
1730	630-K002	Welded & Seamless Steel Pipe Posts, 3"	662.000	LF	54.00	56.45	52.00
1740	630-K003	Welded & Seamless Steel Pipe Posts, 4"	34.000	LF	66.00	67.74	62.40
1750	699-A001	Roadway Construction Stakes	1.000	LS	400,000.00	564,541.07	380,000.00
1760	805-A001	Reinforcement	56,052.000	LBS	1.35	1.41	0.80
1770	815-A007	Loose Riprap, Size 300	3,330.000	TON	60.00	81.32	80.00
1780	815-E001	Geotextile under Riprap	3,159.000	SY	2.30	5.74	2.20
1790	815-F002	Sediment Control Stone	1,379.000	TON	30.00	67.43	108.00
1800	907-228-A001	Erosion Control Blanket, Type I	11,635.000	SY	2.55	2.09	2.30
1810	907-240-A001	Interlocking Flexible Block Erosion Control System	17,636.000	SY	80.00	50.81	51.00
1820	907-250-A001	Polyacrylamide (PAM)	1,096.000	LBS	7.25	9.60	1.00

Safety Improvements on US 49 from the Stone County Line to South Gate Road, known as Federal Aid Project No. HSIP-0008-00(005) / 107464301 in Forrest County.					T. L. Wallace Construction, Inc.	Necaise Brothers Construction Co., Inc.	Dunn Roadbuilders, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$40,095,523.41					\$40,974,061.56	\$44,142,358.23	\$49,722,973.40
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1830	907-253-A001	Coir Fiber Baffle	4,793.000	LF	3.45	5.36	5.00
1840	907-619-E3001	Changeable Message Sign	6.000	EA	11,000.00	11,290.82	10,400.00
1850	907-619-E4001	Portable Radar Display	2.000	EA	4,500.00	4,516.33	4,160.00
1860	907-804-B001	Box Bridge Concrete, Class B	578.000	CY	1,525.00	1,555.93	1,456.00
1870	907-906001	Trainees	1,040.000	HRS	5.00	5.00	5.00
1880	304-F001	3/4" and Down Crushed Stone Base	113,300.000	TON			
1890	304-F002	Size 610 Crushed Stone Base	113,300.000	TON	51.00		
1900	304-F003	Size 825B Crushed Stone Base	113,300.000	TON		48.23	53.00
1910	206-A001	Structure Excavation	1,191.000	CY	13.00	10.91	12.00
1920	209-A005	Geotextile Stabilization, Type V, Non-Woven	3,499.000	SY	1.50	1.90	2.35
1930	601-A001	Class "B" Structural Concrete	655.000	CY	750.00	2,500.00	2,513.00
1940	605-BB001	Prefabricated Sheet Drain	293.000	SY	14.00	169.36	104.00
1950	605-X003	Filter Material for Filter Beds, Type B	1,976.000	CY	30.00	70.00	49.00
1960	803-D002	HP 12 x 53 Steel Piling	4,940.000	LF	38.00	71.33	71.00
1970	803-D005	HP 14 x 117 Steel Piling	3,085.000	LF	67.00	105.00	104.00
1980	803-D006	HP 14 x 73 Steel Piling	760.000	LF	47.00	75.65	82.00
1990	803-D007	HP 14 x 89 Steel Piling	1,100.000	LF	54.00	86.94	88.00
2000	803-D009	HP 16 x 141 Steel Piling	475.000	LF	78.00	111.78	115.00
2010	805-A001	Reinforcement	63,275.000	LBS	1.30	1.58	2.50
2020	810-A006	Structural Steel, A 709, Grade 50	2,174.000	LBS	35.30	13.55	21.00
2030	820-A001	Treated Timber	31.000	KBF	2,400.00	3,454.99	4,590.00