

Bridge Replacement on I-20, Bridge No. 44.9B, known as Federal Aid Project Nos. BR-0020-01(216) / 105858302 & BR-0020-01(216) / 105858303 in Hinds & Rankin Counties.					Key, LLC	W. G. Yates & Sons Construction Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$36,436,089.70					\$42,286,426.20	\$51,246,949.60	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0009	201-B001	Clearing and Grubbing	7.000	ACRE	6,050.00	25,000.00	
0020	202-B006	Removal of Asphalt Paved Shoulders, All Depths	9,662.000	SY	8.50	20.00	
0030	202-B023	Removal of Bridge	1.000	EA	475,000.00	4,000,000.00	
0040	202-B029	Removal of Bridge End Pavement	428.000	SY	18.50	55.00	
0050	202-B042	Removal of Camera Pole	3.000	EA	2,100.00	2,150.00	
0060	202-B061	Removal of Concrete Median Barrier, Precast	2,083.000	LF	10.50	30.00	
0070	202-B063	Removal of Concrete Paved Ditch	1,595.000	SY	10.00	10.00	
0080	202-B079	Removal of Concrete Retaining Wall	175.000	LF	150.00	225.00	
0090	202-B083	Removal of Concrete Slope Paving	11,750.000	SY	10.00	10.00	
0100	202-B124	Removal of Electrical Conductors	1,280.000	LF	2.10	2.15	
0110	202-B136	Removal of Guard Rail	6,875.000	LF	5.00	5.10	
0120	202-B161	Removal of High Mast Lighting Foundation	1.000	EA	1,150.00	1,175.00	
0130	202-B162	Removal of Impact Attenuator	1.000	EA	1,500.00	1,530.00	
0140	202-B170	Removal of Junction Box	1.000	EA	205.00	220.00	
0150	202-B179	Removal of Low Mast Lighting Foundation	1.000	EA	610.00	625.00	
0160	202-B185	Removal of Overhead Sign Including Panels, Truss, Supports & Footing	2.000	EA	6,500.00	6,650.00	
0170	202-B188	Removal of Pavement, All Types and Depths	6,795.000	SY	14.25	11.00	
0180	202-B191	Removal of Pipe, 8" And Above	550.000	LF	40.00	30.00	
0190	202-B219	Removal of Sign, Ground Mounted with Posts	3.000	EA	350.00	375.00	
0200	202-B226	Removal of Soil Cement Treated Base, All Depths	20,742.000	SY	7.50	5.25	
0210	202-B241	Removal of Traffic Stripe	18.000	MI	10,560.00	10,750.00	
0220	203-A001	Unclassified Excavation, FM, AH	53,527.000	CY	4.00	17.00	
0230	203-EX021	Borrow Excavation, AH, FME, Class B9-6	29,227.000	CY	15.00	25.00	
0240	203-G001	Excess Excavation, FM, AH	38,658.000	CY	8.50	18.00	
0250	203-I002	Site Grading	3,112.000	SY	8.00	5.00	
0260	206-A001	Structure Excavation	936.000	CY	40.00	30.00	

Bridge Replacement on I-20, Bridge No. 44.9B, known as Federal Aid Project Nos. BR-0020-01(216) / 105858302 & BR-0020-01(216) / 105858303 in Hinds & Rankin Counties.					Key, LLC	W. G. Yates & Sons Construction Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$36,436,089.70					\$42,286,426.20	\$51,246,949.60	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	209-A004	Geotextile Stabilization, Type V	2,981.000	SY	3.15	5.00	
0280	209-A005	Geotextile Stabilization, Type V, Non-Woven	26,270.000	SY	3.15	4.00	
0290	213-C001	Superphosphate	20.000	TON	950.00	800.00	
0300	216-A001	Solid Sodding	1,032.000	SY	6.00	5.50	
0310	219-A001	Watering	1,936.000	KGAL	20.00	20.00	
0320	220-A001	Insect Pest Control	20.000	ACRE	30.00	30.00	
0330	221-A001	Concrete Paved Ditch	1,156.000	CY	865.00	700.00	
0340	223-A001	Mowing	1,000.000	ACRE	50.00	50.00	
0350	225-A001	Grassing	20.000	ACRE	1,200.00	1,550.00	
0360	225-B001	Agricultural Limestone	10.000	TON	120.00	110.00	
0370	225-C001	Mulch, Vegetative Mulch	40.000	TON	220.00	275.00	
0380	226-A001	Temporary Grassing	20.000	ACRE	100.00	1,500.00	
0390	234-A001	Temporary Silt Fence	20,000.000	LF	5.75	4.50	
0400	234-D001	Inlet Siltation Guard	40.000	EA	500.00	700.00	
0410	237-A002	Wattles, 20"	2,000.000	LF	5.00	5.50	
0420	239-A001	Temporary Slope Drains	500.000	LF	15.00	6.00	
0430	246-B001	Rockbags	500.000	EA	10.00	40.00	
0440	249-A001	Riprap for Erosion Control	1,000.000	TON	100.00	100.00	
0450	304-A004	Granular Material, LVM, Class 5, Group C	6,900.000	CY	51.50	70.00	
0490	402-A002	Open Graded Friction Course, 9.5-mm Mixture	2,564.000	TON	140.00	145.00	
0500	402-B001	Bituminous Tack Coat	5,513.000	GAL	3.25	4.00	
0510	403-A001	12.5-mm, HT, Asphalt Pavement	811.000	TON	101.00	135.00	
0520	403-A003	12.5-mm, ST, Asphalt Pavement	3,499.000	TON	97.50	120.00	
0530	403-A004	19-mm, HT, Asphalt Pavement	2,089.000	TON	89.90	120.00	
0540	403-A006	19-mm, ST, Asphalt Pavement	5,042.000	TON	86.00	110.00	
0550	403-A015	9.5-mm, ST, Asphalt Pavement	1,205.000	TON	95.70	165.00	

Bridge Replacement on I-20, Bridge No. 44.9B, known as Federal Aid Project Nos. BR-0020-01(216) / 105858302 & BR-0020-01(216) / 105858303 in Hinds & Rankin Counties.					Key, LLC	W. G. Yates & Sons Construction Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$36,436,089.70					\$42,286,426.20	\$51,246,949.60	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0560	403-B012	9.5-mm, ST, Asphalt Pavement, Leveling	48.000	TON	150.00	185.00	
0570	403-E004	9.5-mm, HT, Asphalt Pavement, Polymer Modified, Leveling	1,150.000	TON	115.00	150.00	
0580	403-S001	Joint Sealant	2.000	MI	2,000.00	6,500.00	
0590	405-A001	Stone Matrix Asphalt, 12.5 mm Mixture	640.000	TON	137.00	170.00	
0600	405-A002	Stone Matrix Asphalt, 9.5 mm Mixture	1,629.000	TON	139.00	165.00	
0610	406-A002	Cold Milling of Bituminous Pavement, All Depths	19,711.000	SY	8.25	6.00	
0620	407-A001	Asphalt for Tack Coat	15,420.000	GAL	3.25	3.50	
0630	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	40.000	LF	10.00	15.00	
0640	423-A001	Rumble Strips, Ground In	3.000	MI	1,385.00	500.00	
0650	501-K001	Transverse Grooving	394.000	SY	8.75	5.00	
0660	502-A001	Reinforced Cement Concrete Bridge End Pavement	430.000	SY	325.00	200.00	
0670	503-C010	Saw Cut, Full Depth	14,545.000	LF	6.00	7.00	
0680	601-B001	Class "B" Structural Concrete, Minor Structures	36.000	CY	3,275.00	3,000.00	
0690	602-A001	Reinforcing Steel	2,895.000	LBS	5.00	8.00	
0700	603-CA003	15" Reinforced Concrete Pipe, Class III	102.000	LF	57.20	70.00	
0710	603-CA011	18" Reinforced Concrete Pipe, Class III	790.000	LF	67.50	80.00	
0720	603-CA013	18" Reinforced Concrete Pipe, Class IV	84.000	LF	70.50	95.00	
0730	603-CA040	30" Reinforced Concrete Pipe, Class III	158.000	LF	115.00	150.00	
0740	603-CB002	15" Reinforced Concrete End Section	2.000	EA	1,265.00	3,000.00	
0750	603-CB003	18" Reinforced Concrete End Section	4.000	EA	1,265.00	3,000.00	
0760	603-CB005	30" Reinforced Concrete End Section	1.000	EA	1,650.00	4,000.00	
0770	604-B001	Gratings	4,864.000	LBS	5.25	7.50	
0780	605-AA003	Geotextile for Subsurface Drainage, Type V, Non-Woven	5,082.000	SY	3.15	6.00	
0790	605-O001	12" Perforated Sewer Pipe for Underdrains, SDR 35	5,700.000	LF	53.65	25.00	
0800	605-O004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	390.000	LF	24.50	20.00	
0810	605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	70.000	LF	23.00	20.00	

Bridge Replacement on I-20, Bridge No. 44.9B, known as Federal Aid Project Nos. BR-0020-01(216) / 105858302 & BR-0020-01(216) / 105858303 in Hinds & Rankin Counties.					Key, LLC	W. G. Yates & Sons Construction Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$36,436,089.70					\$42,286,426.20	\$51,246,949.60	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0820	605-T001	4" Perforated Pipe for Underdrains	160.000	LF	21.25	15.00	
0830	605-U001	4" Non-perforated Pipe for Underdrains	143.000	LF	20.75	15.00	
0840	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	30.000	CY	150.00	125.00	
0850	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	591.000	CY	115.00	60.00	
0860	605-W004	Filter Material for Combination Storm Drain and/or Underdrains, Type E, FM	1,875.000	CY	100.00	100.00	
0870	606-B001	Guard Rail, Class A, Type 1	5,050.000	LF	22.00	23.00	
0880	606-C003	Guard Rail, Cable Anchor, Type 1	1.000	EA	800.00	815.00	
0890	606-D020	Guard Rail, Bridge End Section, Type H, Metal Post	4.000	EA	1,350.00	1,375.00	
0900	606-D023	Guard Rail, Bridge End Section, Type I, Metal Post	17.000	EA	2,450.00	2,500.00	
0910	606-E005	Guard Rail, Terminal End Section, Flared	5.000	EA	2,750.00	2,850.00	
0920	606-E007	Guard Rail, Terminal End Section, Non-Flared	7.000	EA	2,850.00	2,900.00	
0930	607-B035	96" Type I Chain Link Fence, Class I	94.000	LF	52.50	75.00	
0940	613-D003	Adjustment of Inlet	5.000	EA	1,250.00	2,000.00	
0950	615-A003	Concrete Bridge End Barrier, 42"	113.000	LF	57.70	72.00	
0960	615-A006	Concrete Pier Protection Barrier, 42"	165.000	LF	360.00	445.00	
0970	615-A007	Concrete Pier Protection Barrier, 54"	1,387.000	LF	410.00	425.00	
0980	615-A011	Concrete Type I Cast-in-Place Median Barrier, 42" High	1,786.000	LF	155.00	165.00	
0990	615-A021	Concrete Type IV Cast-in-Place Median Barrier, 42" High	5,501.000	LF	157.50	165.00	
1000	618-A001	Maintenance of Traffic	1.000	LS	460,000.00	1,000,000.00	
1010	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	2.000	MI	13,000.00	13,250.00	
1020	619-A1005	Temporary Traffic Stripe, Continuous White, Type 1 Tape	655.000	LF	2.50	2.60	
1030	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	3.000	MI	13,000.00	13,250.00	
1040	619-A2006	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	908.000	LF	2.50	2.60	
1050	619-A3003	Temporary Traffic Stripe, Skip White, Paint	3.000	MI	13,000.00	13,250.00	
1060	619-A5002	Temporary Traffic Stripe, Detail, Paint	2,700.000	LF	2.50	2.60	
1070	619-A6001	Temporary Traffic Stripe, Legend	240.000	SF	6.00	6.50	

Bridge Replacement on I-20, Bridge No. 44.9B, known as Federal Aid Project Nos. BR-0020-01(216) / 105858302 & BR-0020-01(216) / 105858303 in Hinds & Rankin Counties.					Key, LLC	W. G. Yates & Sons Construction Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$36,436,089.70					\$42,286,426.20	\$51,246,949.60	
Ref#	Item	Item Description	Item Qty	Units	1	2	
1080	619-C6001	Red-Clear Reflective High Performance Raised Marker	1,824.000	EA	15.00	15.50	
1090	619-C9001	One-Way Yellow Reflective High Performance Raised Marker	240.000	EA	15.00	15.50	
1100	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	540.000	SF	7.00	11.00	
1110	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	2,324.000	SF	7.00	10.50	
1120	619-D3001	Remove and Reset Signs, All Sizes	110.000	EA	750.00	700.00	
1130	619-D4001	Directional Signs	1,821.000	SF	35.00	26.00	
1140	619-E1001	Flashing Arrow Panel, Type C	3.000	EA	2,000.00	4,500.00	
1150	619-F1001	Concrete Median Barrier, Precast	11,263.000	LF	75.00	80.00	
1160	619-F1004	Portable Median Barrier, 60 MPH	200.000	LF	90.00	175.00	
1170	619-F2001	Remove and Reset Concrete Median Barrier, Precast	12,571.000	LF	10.00	20.00	
1180	619-G4005	Barricades, Type III, Single Faced	144.000	LF	14.00	21.00	
1190	619-G5001	Free Standing Plastic Drums	86.000	EA	45.00	56.00	
1200	619-G7001	Warning Lights, Type "B"	22.000	EA	125.00	250.00	
1210	619-J1004	Impact Attenuator, 60 MPH	7.000	EA	7,500.00	9,500.00	
1220	619-J2004	Impact Attenuator, 60 MPH, Replacement Package	4.000	EA	3,750.00	3,000.00	
1230	619-J3001	Remove and Reset Impact Attenuator	13.000	EA	2,000.00	7,500.00	
1240	620-A001	Mobilization	1.000	LS	4,275,000.00	5,000,000.00	
1250	626-A001	6" Thermoplastic Double Drop Traffic Stripe, Skip White	3.000	MI	2,500.00	2,550.00	
1260	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	3.000	MI	4,500.00	4,600.00	
1270	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	3.000	MI	4,500.00	4,600.00	
1280	626-G004	Thermoplastic Double Drop Detail Stripe, White	10,899.000	LF	4.00	4.25	
1290	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	623.000	LF	4.00	4.25	
1300	626-H001	Thermoplastic Double Drop Legend, White	80.000	SF	15.00	15.50	
1310	627-K001	Red-Clear Reflective High Performance Raised Markers	841.000	EA	6.00	6.25	
1320	629-A002	Vehicular Impact Attenuator, 50 MPH	1.000	EA	50,000.00	45,000.00	
1330	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	114.000	SF	28.00	30.00	

Bridge Replacement on I-20, Bridge No. 44.9B, known as Federal Aid Project Nos. BR-0020-01(216) / 105858302 & BR-0020-01(216) / 105858303 in Hinds & Rankin Counties.					Key, LLC	W. G. Yates & Sons Construction Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$36,436,089.70					\$42,286,426.20	\$51,246,949.60	
Ref#	Item	Item Description	Item Qty	Units	1	2	
1340	630-B003	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Overhead Mounted	1,020.000	SF	32.00	34.00	
1350	630-C003	Steel U-Section Posts, 3.0 lb/ft	70.000	LF	12.00	15.00	
1360	630-D007	Structural Steel Beams, W6 x 15	43.000	LF	65.00	70.00	
1370	630-D008	Structural Steel Beams, W6 x 9	29.000	LF	55.00	60.00	
1380	630-E001	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles	53.000	LBS	2.50	3.00	
1390	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	22.000	LBS	2.50	3.00	
1400	630-F006	Delineators, Guard Rail, White	142.000	EA	18.00	20.00	
1410	630-F007	Delineators, Guard Rail, Yellow	148.000	EA	18.00	20.00	
1420	630-G004	Type 3 Object Markers, OM-3R or OM-3L	5.000	EA	75.00	80.00	
1430	630-I003	Metal Overhead Sign Supports, Assembly No. 1, Contractor Designed	1.000	LS	82,000.00	85,000.00	
1440	630-I015	Metal Overhead Sign Supports, Assembly No. 2, Contractor Designed	1.000	LS	62,000.00	65,000.00	
1450	630-I020	Metal Overhead Sign Supports, Assembly No. 3, Contractor Designed	1.000	LS	109,000.00	115,000.00	
1460	660-A003	Equipment Cabinet, Type B	4.000	EA	5,380.00	5,500.00	
1470	660-B001	Cabinet Modifications	2.000	EA	8,800.00	9,000.00	
1480	682-A018	Underground Branch Circuit, AWG 2, 3 Conductor	750.000	LF	13.15	15.00	
1490	682-B016	Underground Branch Circuit, Jacked or Bored, AWG 2, 3 Conductor	370.000	LF	16.50	20.00	
1500	682-D003	Underground Pull Box	1.000	EA	1,410.00	1,500.00	
1510	682-E002	Underground Junction Box	3.000	EA	1,410.00	1,500.00	
1520	683-B195	Lighting Assembly, Low Mast, LED, Type 40-1-15-171	1.000	EA	4,190.00	4,500.00	
1530	684-A003	Pole Foundation, 24" Diameter	1.000	CY	2,410.00	2,500.00	
1540	684-A006	Pole Foundation, 42" Diameter	8.000	CY	1,380.00	1,500.00	
1550	686-A001	Relocation of Existing Lighting Assemblies	1.000	EA	16,980.00	17,500.00	
1560	699-A001	Roadway Construction Stakes	1.000	LS	377,000.00	750,000.00	
1570	815-F002	Sediment Control Stone	1,000.000	TON	80.00	60.00	
1580	907-250-A001	Polyacrylamide (PAM)	200.000	LBS	50.00	25.00	
1590	907-619-E3001	Changeable Message Sign	4.000	EA	7,500.00	25,000.00	

Bridge Replacement on I-20, Bridge No. 44.9B, known as Federal Aid Project Nos. BR-0020-01(216) / 105858302 & BR-0020-01(216) / 105858303 in Hinds & Rankin Counties.					Key, LLC	W. G. Yates & Sons Construction Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$36,436,089.70					\$42,286,426.20	\$51,246,949.60	
Ref#	Item	Item Description	Item Qty	Units	1	2	
1600	907-626-U003	6" Thermoplastic Traffic Stripe, Skip White, 40-mil min.	8.000	MI	1,500.00	1,550.00	
1610	907-626-V003	6" Thermoplastic Traffic Stripe, Continuous White, 40-mil min.	6.000	MI	2,400.00	2,500.00	
1620	907-626-X003	6" Thermoplastic Traffic Stripe, Continuous Yellow, 40-mil min.	6.000	MI	2,400.00	2,500.00	
1630	907-626-Y002	Thermoplastic Detail Traffic Stripe, White, 6" Equivalent Length, 40-mil. min.	13,691.000	LF	1.00	1.10	
1640	907-626-Y004	Thermoplastic Detail Traffic Stripe, Yellow, 6" Equivalent Length, 40-mil. min.	257.000	LF	1.00	1.10	
1650	907-630-O004	Remove and Reset Sign, All Sizes	16.000	EA	1,800.00	1,900.00	
1660	907-632-B007	Remove and Replace Existing Traffic Signal Cabinet Assembly, Type III Cabinet, Type 1 Controller	1.000	EA	17,610.00	18,500.00	
1670	907-634-E001	Camera Pole with Foundation, 50' Pole	2.000	EA	17,440.00	18,500.00	
1680	907-634-F002	Detector Pole with Foundation, 35' Pole	1.000	EA	14,600.00	15,000.00	
1690	907-634-I001	Wood Pole, Class II Height 40'	3.000	EA	3,240.00	3,500.00	
1700	907-634-K001	Camera Lowering Device	1.000	EA	9,240.00	9,500.00	
1710	907-636-B042	Electric Cable, Underground in Conduit, THHN, AWG #2, 3 Conductor	2,260.000	LF	5.30	6.00	
1720	907-636-D018	Electric Cable, Aerial Supported in Conduit, THHN, AWG #2, 3 Conductor	11,565.000	LF	0.01	0.01	
1730	907-636-E001	Electric Cable, Underground in Conduit, Tracer Cable	22,760.000	LF	0.20	0.25	
1740	907-637-A002	Pullbox Enclosure, Type 2	15.000	EA	1,020.00	1,100.00	
1750	907-637-A004	Pullbox Enclosure, Type 4	20.000	EA	1,195.00	1,275.00	
1760	907-637-A005	Pullbox Enclosure, Type 5	18.000	EA	1,405.00	1,575.00	
1770	907-637-B001	Pull Box Enclosure, Structure Mounted, Type 1	8.000	EA	2,550.00	2,650.00	
1780	907-637-H001	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 2 @ 2"	8,700.000	LF	6.10	6.50	
1790	907-637-H002	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 2"	330.000	LF	10.30	11.00	
1800	907-637-H003	Traffic Signal Conduit Bank, Underground, Rolled Pipe, 3 @ 2"	3,670.000	LF	9.50	10.00	
1810	907-637-I001	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 2 @ 2"	8,815.000	LF	10.35	11.00	
1820	907-637-I002	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 2"	495.000	LF	8.10	9.00	
1830	907-637-I003	Traffic Signal Conduit Bank, Underground, Drilled or Jacked, Rolled Pipe, 3 @ 2"	750.000	LF	13.95	15.00	
1840	907-637-K001	Traffic Signal Conduit Bank, Aerial Supported, Type 1, 2 @ 2"	3,245.000	LF	87.00	90.00	
1850	907-637-K002	Traffic Signal Conduit Bank, Aerial Supported, Type 1, 3 @ 2"	700.000	LF	106.00	110.00	

Bridge Replacement on I-20, Bridge No. 44.9B, known as Federal Aid Project Nos. BR-0020-01(216) / 105858302 & BR-0020-01(216) / 105858303 in Hinds & Rankin Counties.					Key, LLC	W. G. Yates & Sons Construction Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$36,436,089.70					\$42,286,426.20	\$51,246,949.60	
Ref#	Item	Item Description	Item Qty	Units	1	2	
1860	907-641-C001	ITS Radar Detection Sensor	1.000	EA	6,735.00	7,000.00	
1870	907-650-A002	On Street Video Equipment, Fixed Type	9.000	EA	2,660.00	2,800.00	
1880	907-650-A003	On Street Video Equipment, PTZ Type	3.000	EA	4,890.00	5,000.00	
1890	907-659-A001	Traffic Management Center Modifications	1.000	LS	44,100.00	46,000.00	
1900	907-661-A004	Fiber Optic Cable, 72 SM	20,510.000	LF	1.95	2.25	
1910	907-661-A006	Fiber Optic Cable, Aerial, 72 SM	4,490.000	LF	2.35	2.75	
1920	907-661-B002	Fiber Optic Drop Cable, 12 SM	2,535.000	LF	2.10	2.35	
1930	907-663-A001	Network Switch, Type A	5.000	EA	1,865.00	2,000.00	
1940	907-663-A003	Network Switch, Type C	2.000	EA	91,765.00	95,000.00	
1950	907-663-D001	Category 6 Cable, Installed in Conduit	1,000.000	LF	2.20	2.50	
1960	907-664-D001	Communications Node Modifications	2.000	EA	11,690.00	12,500.00	
1970	907-672-B002	Remove and Reset ITS Equipment	4.000	EA	3,160.00	35,000.00	
1980	907-682-A1019	Branch Circuit Wire, AWG #4, 3 Conductor	530.000	LF	5.90	7.00	
1990	907-899-A001	Railway-Highway Provisions	1.000	LS	4,275,000.00	750,000.00	
2000	907-906001	Trainees	720.000	HRS	5.00	5.00	
2010	304-F001	3/4" and Down Crushed Stone Base	9,300.000	TON			
2020	304-F002	Size 610 Crushed Stone Base	9,300.000	TON	70.00	65.00	
2030	304-F003	Size 825B Crushed Stone Base	9,300.000	TON			
2040	308-A001	Cement	136.000	TON	225.00	240.00	
2050	308-B003	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	29,200.000	SY	2.25	2.50	
2060	308-S001	Bituminous Curing Seal	7,300.000	GAL	3.50	3.75	
2062	307-C004	6" Soil-Lime-Water Mixing, Class C	29,200.000	SY			
2064	307-D001	Lime	216.000	TON			
2066	307-S001	Bituminous Curing Seal	7,300.000	GAL			
2180	501-K001	Transverse Grooving	12,466.000	SY	3.50	2.75	
2190	605-AA002	Geotextile for Subsurface Drainage, Type V	12,563.000	SY	3.15	5.00	



Bridge Replacement on I-20, Bridge No. 44.9B, known as Federal Aid Project Nos. BR-0020-01(216) / 105858302 & BR-0020-01(216) / 105858303 in Hinds & Rankin Counties.					Key, LLC	W. G. Yates & Sons Construction Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$36,436,089.70					\$42,286,426.20	\$51,246,949.60	
Ref#	Item	Item Description	Item Qty	Units	1	2	
2200	605-T001	4" Perforated Pipe for Underdrains	3,751.000	LF	13.50	15.00	
2210	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	1,972.000	CY	110.00	125.00	
2220	802-A001	Permanent Steel Sheet Piling	3,494.000	SF	60.00	80.00	
2230	802-C001	Temporary Steel Sheet Piling	1,825.000	SF	35.00	70.00	
2240	803-D006	HP 14 x 73 Steel Piling	13,440.000	LF	82.50	95.00	
2250	803-K002	Drilled Shaft, 24" Diameter	50.000	LF	165.00	775.00	
2260	803-K007	Drilled Shaft, 54" Diameter	3,100.000	LF	315.00	475.00	
2270	803-K010	Drilled Shaft, 72" Diameter	348.000	LF	895.00	1,650.00	
2280	803-L003	Test Shaft, 54" Diameter	1.000	EA	250,000.00	215,000.00	
2290	803-M009	Trial Shaft, 72" Diameter	107.000	LF	1,500.00	3,000.00	
2300	803-N001	Exploration	560.000	LF	10.00	0.01	
2310	804-C172	64' Prestressed Concrete Beam, Type FIB-78	448.000	LF	340.00	380.00	
2320	804-C173	114' Prestressed Concrete Beam, Type FIB-78	857.000	LF	340.00	380.00	
2330	804-C174	145' Prestressed Concrete Beam, Type FIB-78	1,020.000	LF	340.00	425.00	
2340	804-C175	136' Prestressed Concrete Beam, Type FIB-78	1,713.000	LF	340.00	375.00	
2350	804-C176	148' Prestressed Concrete Beam, Type FIB-78	2,077.000	LF	340.00	375.00	
2360	804-C177	143' Prestressed Concrete Beam, Type FIB-78	1,708.000	LF	340.00	420.00	
2370	804-C178	147' Prestressed Concrete Beam, Type FIB-78	846.000	LF	340.00	425.00	
2380	804-C179	118' Prestressed Concrete Beam, Type FIB-78	674.000	LF	340.00	390.00	
2390	804-C180	120' Prestressed Concrete Beam, Type FIB-78	1,673.000	LF	340.00	400.00	
2400	804-C183	170' Prestressed Concrete Beam, Type FIB-84	1,186.000	LF	480.00	600.00	
2410	805-A001	Reinforcement	1,541,753.000	LBS	1.10	1.25	
2420	811-D001	Disc Bearing Device	2.000	EA	42,500.00	40,000.00	
2430	813-A003	Concrete Railing, 42"	3,717.000	LF	58.00	71.00	
2440	815-D001	Concrete Slope Paving	1,787.000	CY	625.00	750.00	
2450	907-607-PP001	Safety Fence	1,580.000	LF	90.00	100.00	

Bridge Replacement on I-20, Bridge No. 44.9B, known as Federal Aid Project Nos. BR-0020-01(216) / 105858302 & BR-0020-01(216) / 105858303 in Hinds & Rankin Counties.					Key, LLC	W. G. Yates & Sons Construction Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$36,436,089.70					\$42,286,426.20	\$51,246,949.60	
Ref#	Item	Item Description	Item Qty	Units	1	2	
2460	907-804-A002	Bridge Concrete, Class AA	1,632.000	CY	1,085.00	1,825.00	
2470	907-804-A002	Bridge Concrete, Class AA 6000 psi	380.000	CY	1,150.00	1,900.00	
2480	907-804-A004	Bridge Concrete, Class BD	4,568.000	CY	950.00	1,100.00	
2490	907-804-PP004	Post Tensioning System	1.000	LS	205,000.00	225,000.00	
2500	907-822-B005	4" Reinforced Elastomeric Molded Rubber Expansion Joint	290.000	LF	925.00	1,100.00	
2510	907-824-PP004	Bridge Repair, Remove and replace bridge railing and deck, per plans	1.000	LS	1,325,000.00	1,375,000.00	
2520	907-824-PP006	Bridge Repair, Cap Cleaning	12.000	EA	750.00	3,000.00	

Letting Date: 12/5/2019

Call Number: 08

Page 10 of 10