

Call 09 Bridge Replacements on SR 19 (Bridge Nos. 52.0, 52.1, 52.3, 52.4, & 52.5), known as Federal Aid Project No. BR-0026-01(078) / 106114301 in Neshoba County.

Q1. In the steel pipe piles notes on Sheet Number 8013, it makes reference to an out of position PDA Indicator Pile but is not reflected in the estimated quantities nor shown on the foundation plans. Please advise if a PDA Indicator Pile will be required for the 30" pipe piles.

A1. An indicator pile is not needed for this project.

Q2. For the Bridge Concrete Mat installed directly under the bridge deck, what type of crushed limestone is required and how will the stone be paid for?

A2. The crushed limestone to be placed in the open cell portion directly below the deck may be the same type limestone used for the roadway shoulders. The material will not be measured for separate payment and should be included in other items bid.

Q3. Will the crushed limestone be required in the portions of the Bridge Concrete Mat that is placed in the channel?

A3. No.