

Mill & Overlay approximately 20 miles on US 278 from the Coahoma County Line to Quitman/Panola Ditch Bridge, & from SR 161 to the Quitman County Line, known as Federal Aid Project Nos. NH-0070-02(016) / 107703301 & NH-0009-04(036) / 107702301 in Quitman & Coahoma Counties.					Lehman-Roberts Company		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$6,901,552.51					\$7,746,848.30		
Ref#	Item	Item Description	Item Qnty	Units	1		
0010	202-B007	Removal of Asphalt Pavement, All Depths	1,562.000	SY	110.00		
0020	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	3,272.000	SY	110.00		
0030	202-B148	Removal of Guard Rail End Section, All Types	8.000	EA	375.00		
0040	202-B240	Removal of Traffic Stripe	4,908.000	LF	4.50		
0050	203-G001	Excess Excavation, FM, AH	1,975.000	CY	5.00		
0060	304-B002	Granular Material, Class 3, Group D	12,795.000	TON	32.25		
0070	403-A005	19-mm, MT, Asphalt Pavement	680.000	TON	162.00		
0080	403-A006	19-mm, ST, Asphalt Pavement	1,630.000	TON	162.00		
0090	403-A014	9.5-mm, MT, Asphalt Pavement	26,867.000	TON	94.00		
0100	403-B011	9.5-mm, MT, Asphalt Pavement, Leveling	15,050.000	TON	98.00		
0110	406-D001	Fine Milling of Bituminous Pavement, All Depths	325,490.000	SY	1.95		
0120	407-A001	Asphalt for Tack Coat	42,387.000	GAL	3.25		
0130	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	62,000.000	LF	3.05		
0140	423-A001	Rumble Strips, Ground In	31.000	MI	575.00		
0150	503-C010	Saw Cut, Full Depth	12,125.000	LF	15.25		
0160	606-E001	Guard Rail, Terminal End Section	8.000	EA	3,000.00		
0170	618-A001	Maintenance of Traffic	1.000	LS	250,000.00		
0180	618-B001	Additional Construction Signs	11.000	SF	10.00		
0190	619-A1001	Temporary Traffic Stripe, Continuous White	91.000	MI	1,150.00		
0200	619-A2001	Temporary Traffic Stripe, Continuous Yellow	13.000	MI	1,150.00		
0210	619-A3001	Temporary Traffic Stripe, Skip White	3.000	MI	1,150.00		
0220	619-A4002	Temporary Traffic Stripe, Skip Yellow	44.000	MI	1,150.00		
0230	619-A5001	Temporary Traffic Stripe, Detail	37,963.000	LF	0.30		
0240	619-A6002	Temporary Traffic Stripe, Legend	6,973.000	LF	1.10		
0250	620-A001	Mobilization	1.000	LS	275,000.00		
0260	626-A004	6" Thermoplastic Traffic Stripe, Skip White	2.000	MI	2,000.00		

Mill & Overlay approximately 20 miles on US 278 from the Coahoma County Line to Quitman/Panola Ditch Bridge, & from SR 161 to the Quitman County Line, known as Federal Aid Project Nos. NH-0070-02(016) / 107703301 & NH-0009-04(036) / 107702301 in Quitman & Coahoma Counties.					Lehman-Roberts Company		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$6,901,552.51					\$7,746,848.30		
Ref#	Item	Item Description	Item Qnty	Units	1		
0270	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	880.000	LF	2.25		
0280	626-C004	6" Thermoplastic Edge Stripe, Continuous White	33.000	MI	3,900.00		
0290	626-D002	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	440.000	LF	2.25		
0300	626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	16.000	MI	2,000.00		
0310	626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	4.000	MI	3,900.00		
0320	626-G002	Thermoplastic Detail Stripe, White	9,537.000	LF	1.75		
0330	626-G003	Thermoplastic Detail Stripe, Yellow	12,654.000	LF	1.75		
0340	626-H005	Thermoplastic Legend, White	2,827.000	LF	3.80		
0350	627-J001	Two-Way Clear Reflective High Performance Raised Markers	696.000	EA	8.25		
0360	627-K001	Red-Clear Reflective High Performance Raised Markers	134.000	EA	8.25		
0370	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	2,110.000	EA	8.25		
0380	907-619-B001	Temporary Portable Rumble Strips	132.000	LF	275.00		
0390	304-F001	3/4" and Down Crushed Stone Base	1,105.000	TON			
0400	304-F002	Size 610 Crushed Stone Base	1,105.000	TON	175.00		
0410	304-F003	Size 825B Crushed Stone Base	1,105.000	TON			