

**Call 08 Bridge Replacements on SR 35 from Leake County Line to Kosciusko, Bridge Nos. 150.5 & 152.0, and US 49 across Hopson Bayou, Bridge No. 295.3, known as Federal Aid Project Nos. BR-0023-02(058) / 103334301 & BR-0008-05(038) / 105343301 in Attala & Tallahatchie Counties.**

- Q1. The summary of bid items in the Special Provisions includes two Pay Items for Clearing and Grubbing. One is listed as a LS and the other by the Acre. Neither the summary of quantities in the plans show the Clearing and Grubbing LS pay item. Could you define what work is included in each respective Pay Item?
- A1. The Clearing and Grubbing Lump Sum pay item is for the clearing of the ROW. The Clearing and Grubbing per acre item is for temporary easements. See addendum.
- Q2. In Attala County On sheet 8002, the quantities call out BT-63's. On sheet 8013, the 115' beam is listed as a BT-54 and they provide a BT-54 detail sheet. Are these going to be BT-54 or BT-63's?
- A2. See addendum.
- Q3. The project is currently set up for 308 Working Days. How will days be assessed if the Contractor is unable to progress work due to weather in Tallahatchie Co. as opposed to Attala Co. or vice versa?
- A3. Working days will be assessed in accordance with the approved progress schedule as outlined in Subsection 108.06.