

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. <u> 1 </u>	DATED <u> 2/14/2020 </u>	ADDENDUM NO. _____	DATED _____
ADDENDUM NO. _____	DATED _____	ADDENDUM NO. _____	DATED _____
ADDENDUM NO. _____	DATED _____	ADDENDUM NO. _____	DATED _____

Number	Description
1	Revised Table of Contents; Revised NTB No. 2156; Added NTB No. 2160; Deleted SP 907-420-2; Revised Bid Items; Revised Progress Schedule; Revised or Added Plan Sheet Nos. 2, 6-7, 13, & 18; Amendment EBSx Download Required.

TOTAL ADDENDA: 1
(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

Contractor

BY _____
Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

President Address

Secretary Address

Treasurer Address

The following is my (our) itemized proposal.

NH-0008-02(112) / 107617301

Covington County(ies)

Revised 01/26/2016

**MISSISSIPPI DEPARTMENT OF TRANSPORTATION
TABLE OF CONTENTS**

PROJECT: NH-0008-02(112)/107617301 - Covington

Section 901 - Advertisement

Section 904 - Notice to Bidders

#1	Governing Specification
#2	Status of ROW, w/ Attachments
#3	Final Cleanup
#9	Federal Bridge Formula
#113	Tack Coat
#296	Reduced Speed Limit Signs
#445	Mississippi Agent and Qualified Nonresident Agent
#516	Errata and Modifications to the 2017 Standard Specifications
#977	DUNS Requirement For Federal Funded Projects
#1225	Early Notice to Proceed
#1226	Material Storage Under Bridges
#1241	Fuel and Material Adjustments
#2061	Reflective Sheeting for Signs
#2156	Contract Time
#2157	Specialty Items
#2158	Cooperation Between Contractors
#2159	Additional Construction Requirements
#2160	Lane Closure Restrictions
#2206	MASH Compliant Devices
#2214	Disadvantaged Business Enterprise In Federal-Aid Highway Construction, w/ Supplement

906 Required Federal Contract Provisions -- FHWA 1273, w/Supplements

Section 907 - Special Provisions

907-102-2	Bidding Requirements and Conditions
907-109-1	Measurement and Payment
907-410-1	Asphalt for Fog Seal
907-624-1	Inverted Profile Thermoplastic Traffic Stripe
907-701-1	Hydraulic Cement
907-702-4	Bituminous Materials
907-703-1	Gradation
907-705-1	Stone Riprap
907-707-2	Joint Material
907-711-2	Plain Steel Wire
907-720-2	Acceptance Procedure for Glass Beads
907-721-1	Materials for Signing

Section 905 - Proposal, Proposal Bid Items, Combination Bid Proposal

Certification of Performance - Prior Federal-Aid Contracts

Certification Regarding Non-Collusion, Debarment and Suspension

SAM.GOV Registration and DUNS Number

PROJECT: NH-0008-02(112)/107617301 - Covington

Section 902 - Contract Form

Section 903 - Contract Bond Forms

Form -- OCR-485

Progress Schedule

(REVISIONS TO THE ABOVE WILL BE INDICATED ON THE SECOND SHEET
OF SECTION 905 AS ADDENDA)

02/14/2020 01:54 PM

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 2156

CODE: (SP)

DATE: 01/02/2020

SUBJECT: Contract Time

PROJECT: NH-0008-02(112) / 107617301 – Covington County

The completion of work to be performed by the Contractor for this project will not be a specified date but shall be when all allowable working days are assessed, or any extension thereto as provided in Subsection 108.06. It is anticipated that the Notice of Award will be issued no later than March 10, 2020 and the date for Notice to Proceed / Beginning of Contract Time will be April 9, 2020.

Should the Contractor request a Notice to Proceed earlier than April 9, 2020 and it is agreeable with the Department for an early Notice to Proceed, the requested date will become the new Notice to Proceed date. Regardless of whether or not an early Notice to Proceed is granted, contract time will start at the original Notice to Proceed date.

All requests for an early Notice to Proceed shall be sent to the Project Engineer who will forward it to the Contract Administration Division.

128 Working Days have been allowed for the completion of work on this project.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 2160

CODE: (SP)

DATE: 2/13/2020

SUBJECT: Lane Closure Restrictions

PROJECT: NH-0008-02(112) / 107617301 -- Covington County

Bidders are advised that lane closures will **NOT** be permitted in the South Bound lanes on Fridays from 12 P.M (noon) to 12 A.M. (midnight) from Memorial Day through Labor Day.

A lane rental fee of **\$500.00** per full or partial 5 minutes shall be assessed for closures or obstructions that occur during the time mentioned above.

For the purpose of this contract, official time shall be the announced time available at the Jackson area telephone number (601) 355-9311.

Mill & Overlay approximately 7 miles of US 49 from JCT US 84 (Collins) to JCT SR 149 (Mt. Olive), known as Federal Aid Project No. NH-0008-02(112) / 107617301 in Covington County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	202-B069		451	Square Yard	Removal of Concrete Pavement w/ Variable Depth Overlay
0030	202-B240		1,410	Linear Feet	Removal of Traffic Stripe
0040	203-G002	(E)	66	Cubic Yard	Excess Excavation, LVM, AH
0050	209-A004		526	Square Yard	Geotextile Stabilization, Type V
0060	403-D003	(BA1)	261	Ton	19-mm, HT, Asphalt Pavement, Polymer Modified
0070	403-D007	(BA1)	19,244	Ton	9.5-mm, HT, Asphalt Pavement, Polymer Modified
0080	406-D001		233,382	Square Yard	Fine Milling of Bituminous Pavement, All Depths
0090	407-A001	(A2)	17,442	Gallon	Asphalt for Tack Coat
0100	413-D002		362	Linear Feet	Cleaning and Filling Joints
0110	413-E001		48,223	Linear Feet	Sawing and Sealing Transverse Joints in Asphalt Pavement
0120	423-A001		28	Mile	Rumble Strips, Ground In
0160	503-C010		1,102	Linear Feet	Saw Cut, Full Depth
0200	618-A001		1	Lump Sum	Maintenance of Traffic
0210	618-B001		1	Square Feet	Additional Construction Signs [\$10.00]
0220	619-A1001		18	Mile	Temporary Traffic Stripe, Continuous White
0230	619-A2001		10	Mile	Temporary Traffic Stripe, Continuous Yellow
0240	619-A3001		14	Mile	Temporary Traffic Stripe, Skip White
0250	619-A5001		45,418	Linear Feet	Temporary Traffic Stripe, Detail
0260	619-A6001		895	Square Feet	Temporary Traffic Stripe, Legend
0270	619-A6002		4,586	Linear Feet	Temporary Traffic Stripe, Legend
0280	620-A001		1	Lump Sum	Mobilization
0290	626-A001		14	Mile	6" Thermoplastic Double Drop Traffic Stripe, Skip White
0300	626-C002		12	Mile	6" Thermoplastic Double Drop Edge Stripe, Continuous White
0310	626-F001		10	Mile	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow
0320	626-G002		22,507	Linear Feet	Thermoplastic Detail Stripe, White
0330	626-G003		22,911	Linear Feet	Thermoplastic Detail Stripe, Yellow
0340	626-H004		175	Square Feet	Thermoplastic Legend, White
0350	626-H005		1,786	Linear Feet	Thermoplastic Legend, White
0360	627-J001		999	Each	Two-Way Clear Reflective High Performance Raised Markers
0370	627-K001		2,563	Each	Red-Clear Reflective High Performance Raised Markers
0380	627-L001		2,062	Each	Two-Way Yellow Reflective High Performance Raised Markers
0390	627-P001		7	Each	Two-Way Blue Reflective High Performance Raised Markers

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0400	630-F002		52	Each	Delineators, Flexible Post Mounted, Crossover, Type I, Yellow
0410	630-F006		68	Each	Delineators, Guard Rail, White
0420	630-F007		20	Each	Delineators, Guard Rail, Yellow
0430	907-410-D001	(A2)	4,187	Gallon	Asphalt for Rejuvenating Fog Seal, Grade CMS-1PF
ALTERNATE GROUP AA NUMBER 1					
0450	304-H001	(GY)	1,540	Cubic Yard	3/4" and Down Crushed Stone Base, LVM
ALTERNATE GROUP AA NUMBER 2					
0460	304-H002	(GY)	1,540	Cubic Yard	Size 610 Crushed Stone Base, LVM
ALTERNATE GROUP AA NUMBER 3					
0470	304-H003	(GY)	1,540	Cubic Yard	Size 825B Crushed Stone Base, LVM
ALTERNATE GROUP BB NUMBER 1					
0480	907-624-A003		430	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Skip White, High Contrast
0490	907-624-B003		430	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White, High Contrast
0500	907-624-D001		430	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow, High Contrast
ALTERNATE GROUP BB NUMBER 2					
0510	628-G001		430	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Skip White
0520	628-H001		430	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous White
0530	628-J001		430	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow

ADDENDUM

REV. DATE DESCRIPTION OF SHEET WKG. NO. SH. NO. REV. DATE DESCRIPTION OF SHEET WKG. NO. SH. NO.

TITLE AND LAYOUT SHEET (1)	1		
DETAILED INDEX (1)	2	DI-1	
GENERAL NOTES (2)	3	GN-1	
	4	GN-2	
TYPICAL SECTION SHEETS (1)	5	TS-1	
TYPICAL SECTION-MAINLINE 4 LANE SECTION			
QUANTITY SHEETS (8)	6	SQ-1	CRP-1
SUMMARY OF QUANTITIES	7	SQ-2	6001
SUMMARY OF QUANTITIES	8	TCPQ-1	6051
ESTIMATED QUANTITIES FOR TRAFFIC CONTROL SIGNING	9	EQ-1	6056
ESTIMATED QUANTITIES FOR MILLING AND LEVELING	10	EQ-2	6062
ESTIMATED QUANTITIES FOR ASPHALT AND GRANULAR MATERIALS	11	EQ-3	6065
ESTIMATED GUARD RAIL QUANTITIES	12	EQ-4	6226
ESTIMATED BASE FAILURE REPAIR QUANTITIES	13	EQ-5	6316
ESTIMATED CONCRETE PUNCHOUTS REPAIR QUANTITIES			6317
PLAN & PROFILE SHEETS (13)			6354
STA. 1400+00 TO STA. 170+00	14	WK3	6355
STA. 170+00 TO STA. 200+00	15	WK4	6357
STA. 200+00 TO STA. 230+00	16	WK5	TCP-4
STA. 230+00 TO STA. 260+00	17	WK6	TCP-5
STA. 260+00 TO STA. 290+00	18	WK7	TCP-7
STA. 290+00 TO STA. 320+00	19	WK8	TCP-8
STA. 320+00 TO STA. 350+00	20	WK9	TCP-9
STA. 350+00 TO STA. 380+00	21	WK10	TCP-12
STA. 380+00 TO STA. 410+00	22	WK11	TCP-13
STA. 410+00 TO STA. 440+00	23	WK12	
STA. 440+00 TO STA. 470+00	24	WK13	
STA. 470+00 TO STA. 500+00	25	WK14	
STA. 500+00 TO STA. 508+00	26	WK15	
SPECIAL DESIGN SHEETS (12)			
DETAIL OF CONSTRUCTION SIGNING	27	DCS-1	
DETAIL FOR CURB AND ISLAND STRIPING	28	DCIS-1	
DETAIL OF STRIPING CHANNELIZED INTERSECTION	29	PMD-4	
CROSSOVER RPM D7 TYPICAL PAVEMENT MARKING DETAIL FOR MEDIAN CROSSEOVERS	30	D7-1	
CONCRETE LUG ANCHORS	31	SDLA-1	
TYPICAL CRC PAVEMENT REPAIR	32	PR-1B	
DETAIL OF EXISTING REINF CONCRETE PAVEMENT JOINT REPAIR	33	PR-2	
CONSTRUCTION DETAILS MAINLINE PUNCH-OUTS	34	MCD-2	
LANE CLOSURE DETAILS FOR FULL DEPTH CONCRETE PAVEMENT REPAIR	35	LCD-1	
TRAFFIC CONTROL DETAILS DRUM PLACEMENT & SHOULDER CLOSER	36	SDTCP-16	
UNDERSEALING DETAIL FOR JOINTED CONCRETE PAVEMENT	37	UDJC-1	
RUMBLE STRIPE AND DOUBLE RUMBLE STRIP FOR 4 LANE HIGHWAYS (ASPH. LANES, ASPH SHLD.)	38	SDRS-2	

STANDARD DRAWINGS (15)
CONTINUOUSLY REINFORCED CONCRETE PAVEMENT 24' - 0" WIDE
PAVEMENT MARKING DETAILS FOR 2-LANE AND 4-LANE DIVIDED HIGHWAYS
PAVEMENT MARKING LEGEND DETAILS
2-WAY CLEAR RAISED PAVEMENT MARKERS PLACED ON SIDE ROADS (4-LANE)
RUMBLE STRIPE 4-LANE HIGHWAYS (ASPHALT LANES, 2-FT. OR WIDER ASPHALT SHOULDER
CONCRETE MEDIAN BARRIER (PRECAST) (32")
TYPICAL CROSSOVER DELINEATION
TYPICAL GUARDRAIL DELINEATION
TRAFFIC CONTROL PLAN FOR POSTED SPEED LIMIT OF 65 OR 70 MPH (EXTENDED PERIOD)
TRAFFIC CONTROL PLAN FOR POSTED SPEED LIMIT OF 65 OR 70 MPH (WORK DAY ONLY)
SHORT DURATION CLOSING OF DIVIDED HIGHWAYS
HIGHWAY SIGN AND BARRICADE DETAILS FOR CONSTRUCTION PROJECTS
TRAFFIC CONTROL PLAN MOBILE OPERATIONS MULTILANE ROADS AND TWO-LANE ROADS
TRAFFIC CONTROL PLANS UNEVEN PAVEMENT DETAILS
TEMPORARY STRIPING FOR TRAFFIC CONTROL 2-LN. AND 4-LN DIVIDED HIGHWAYS.

TOTAL SHEETS 53

DISTRICT 7			
PS & E PLANS-DATE 8-30-19			
FMS_CON.# 107617/301000			
REVISIONS			
DATE	SHEET NO.	BY	
11/22/19	6	MA	
1/16/20	6	MA	
2/14/20	6.7.13 & 18	MA	

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

DETAILED INDEX

PROJ. NO.: NH-0008-02(112)
COUNTY: COVINGTON

WORKING NUMBER
DI-1

SHEET NUMBER
2

FILENAME: .02index#1.dgn
DESIGN TEAM _____ CHECKED _____ DATE _____

BY	
REVISION	
DATE	

ADDENDUM

STATE	PROJECT NO.
MISS	NH-0008-02(112)


SUMMARY OF QUANTITIES (SHEET 1)

PAY ITEM NO.	PAY ITEM	UNIT	COVINGTON : 107617-301000	
			Prelim	Final
202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	SY	451	
202-B240	Removal of Traffic Stripe	LF	1,410	
203-G002	Excess Excavation, LVM, AH	CY	66	
209-A004	Geotextile Stabilization, Type V	SY	526	
304-H001	3/4" and Down Crushed Stone Base, LVM	CY	1,540	
	OR			
304-H002	Size 610 Crushed Stone Base, LVM	CY	1,540	
	OR			
304-H003	Size 825B Crushed Stone Base, LVM	CY	1,540	
403-D003	19-mm, HT, Asphalt Pavement, Polymer Modified	TON	261	
403-D007	9.5-mm, HT, Asphalt Pavement, Polymer Modified	TON	19,244	
406-D001	Fine Milling of Bituminous Pavement, All Depths	SY	233,382	
407-A001	Asphalt for Tack Coat	GAL	17,442	
907-410-D001	Asphalt for Rejuvenating Fog Seal, Grade CMS-1PF	GAL	4,187	
413-D002	Cleaning and Filling Joints	LF	362	
413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	LF	48,223	
423-A001	Rumble Strips, Ground In	MI	28	
503-C010	Saw Cut, Full Depth	LF	1,102	
618-A001	Maintenance of Traffic	LS	1	
618-B001	Additional Construction Signs	SF	1	
619-A1001	Temporary Traffic Stripe, Continuous White	MI	18	
619-A2001	Temporary Traffic Stripe, Continuous Yellow	MI	10	
619-A3001	Temporary Traffic Stripe, Skip White	MI	14	
619-A5001	Temporary Traffic Stripe, Detail	LF	45,418	
619-A6001	Temporary Traffic Stripe, Legend	SF	895	
619-A6002	Temporary Traffic Stripe, Legend	LF	4,586	
620-A001	Mobilization	LS	1	
907-624-A003	6" Inverted Profile Thermoplastic Traffic Stripe, Skip White, High Contrast	LF	430	
907-624-B003	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White, High Contrast	LF	430	
907-624-D001	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow, High Contrast	LF	430	
	OR			
628-G001	6" High Performance Cold Plastic Traffic Stripe, Skip White	LF	430	
628-H001	6" High Performance Cold Plastic Traffic Stripe, Continuous White	LF	430	
628-J001	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow	LF	430	
626-A001	6" Thermoplastic Double Drop Traffic Stripe, Skip White	MI	14	
626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	MI	12	
626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	MI	10	
626-G002	Thermoplastic Detail Stripe, White	LF	22,507	
626-G003	Thermoplastic Detail Stripe, Yellow	LF	22,911	
626-H004	Thermoplastic Legend, White	SF	175	
626-H005	Thermoplastic Legend, White	LF	1,786	
627-J001	Two-Way Clear Reflective High Performance Raised Markers	EA	999	

- ① Shoulder Material 1,352 CY, Punch out Material 188 CY
- ② To be used on concrete Punch outs.
- ③ To be used for Asphalt Punch outs.

Date	Revision
02/14/2020	REVISD AND REMOVED PAY ITEMS
01/16/2020	ADDED PAY ITEMS
11/22/2019	Changed pay items.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES



PROJ NO: NH-0008-02(112)
COUNTY: COVINGTON

Working Number **SQ-1**

Design Team
FILENAME: SQ-1


Checked _____ Date _____

Sheet Number **6**

STATE	MISS	PROJECT NO.	NH-0008-02(112)
-------	------	-------------	-----------------

PAY ITEM NO.	PAY ITEM	UNIT	COVINGTON : 107617-301000	
			Prelim	Final
627-K001	Red-Clear Reflective High Performance Raised Markers	EA	2,563	
627-L001	Two-Way Yellow Reflective High Performance Raised Markers	EA	2,062	
627-P001	Two-Way Blue Reflective High Performance Raised Markers	EA	7	
630-F002	Delineators, Flexible Post Mounted, Crossover, Type I, Yellow	EA	52	
630-F006	Delineators, Guard Rail, White	EA	68	
630-F007	Delineators, Guard Rail, Yellow	EA	20	

SUMMARY OF QUANTITIES (SHEET 2)

		Working Number	SQ-2
		Sheet Number	7
MISSISSIPPI DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES			
PROJ NO: NH-0008-02(112) COUNTY: COVINGTON			
Date	Design Team	Checked	Date
by	Revision	FILENAME: SQ-1	

