

Interchange Construction on SR 304 at McIngvale Road, known as Federal Aid Project No. NHPP-0029-02(022) / 107114301 in Desoto County.					Tanner Construction Company, Inc.	Xcavators, Inc.	M & N Excavators, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$8,961,476.93					\$7,854,903.14	\$7,998,514.20	\$8,210,310.33
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	201-B001	Clearing and Grubbing	22.000	ACRE	4,650.00	3,000.00	5,802.50
0020	202-B052	Removal of Concrete Driveways, All Depths	844.000	SY	11.00	3.00	23.21
0030	202-B063	Removal of Concrete Paved Ditch	979.000	SY	11.00	3.00	17.41
0040	202-B080	Removal of Concrete Sidewalk	395.000	SY	11.00	3.00	17.08
0050	202-B088	Removal of Curb & Gutter, All Types	628.000	LF	5.00	5.00	15.94
0060	202-B126	Removal of Fence, All Types	9,768.000	LF	3.65	2.00	4.64
0070	202-B129	Removal of Flared End Section, All Sizes	7.000	EA	500.00	500.00	464.20
0080	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	472.000	LF	5.00	6.25	5.56
0090	202-B165	Removal of Inlets, All Sizes	2.000	EA	500.00	500.00	928.40
0100	202-B188	Removal of Pavement, All Types and Depths	100.000	SY	11.00	10.00	23.21
0110	202-B191	Removal of Pipe, 8" And Above	28.000	LF	5.00	15.00	17.41
0120	202-B207	Removal of Riprap	611.000	TON	11.00	15.00	29.01
0130	202-B240	Removal of Traffic Stripe	12,493.000	LF	4.50	5.50	5.22
0140	203-A001	Unclassified Excavation, FM, AH	111,049.000	CY	4.95	6.00	5.80
0150	203-G001	Excess Excavation, FM, AH	95,940.000	CY	4.95	6.00	6.67
0160	206-A001	Structure Excavation	723.000	CY	4.95	11.00	13.93
0170	206-B001	Select Material for Undercuts, Contractor Furnished, FM	29.000	CY	38.50	14.00	243.71
0180	211-B001	Topsoil for Slope Treatment, Contractor Furnished	19,138.000	CY	0.50	5.00	1.16
0190	213-C001	Superphosphate	24.000	TON	650.00	750.00	689.33
0200	216-A001	Solid Sodding	4,258.000	SY	3.00	3.75	3.71
0210	217-A001	Ditch Liner	2,167.000	SY	2.00	2.50	2.12
0220	219-A001	Watering	85.000	KGAL	20.00	20.00	20.00
0230	220-A001	Insect Pest Control	24.000	ACRE	30.00	30.00	30.00
0240	221-A001	Concrete Paved Ditch	339.000	CY	600.00	750.00	522.23
0250	223-A001	Mowing	96.000	ACRE	50.00	50.00	50.00
0260	225-A001	Grassing	48.000	ACRE	1,450.00	1,500.00	1,537.73

Interchange Construction on SR 304 at McIngvale Road, known as Federal Aid Project No. NHPP-0029-02(022) / 107114301 in Desoto County.					Tanner Construction Company, Inc.	Xcavators, Inc.	M & N Excavators, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$8,961,476.93					\$7,854,903.14	\$7,998,514.20	\$8,210,310.33
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	225-B001	Agricultural Limestone	24.000	TON	100.00	150.00	106.05
0280	225-C001	Mulch, Vegetative Mulch	96.000	TON	150.00	200.00	159.08
0290	226-A001	Temporary Grassing	48.000	ACRE	950.00	1,225.00	901.43
0300	234-A001	Temporary Silt Fence	20,450.000	LF	3.50	3.50	3.71
0310	235-A001	Temporary Erosion Checks	100.000	EA	5.00	40.00	5.30
0320	236-A008	Silt Basin, Type D	4.000	EA	2,100.00	1,650.00	2,553.10
0330	237-A002	Wattles, 20"	3,918.000	LF	6.00	5.00	6.36
0340	239-A001	Temporary Slope Drains	629.000	LF	8.00	5.00	8.48
0350	245-A001	Silt Dike	2,654.000	LF	7.50	6.25	7.95
0360	246-A001	Sandbags	2,724.000	LF	5.00	3.00	8.48
0370	246-B002	Rockbags	100.000	LF	15.00	12.00	15.91
0380	249-A001	Riprap for Erosion Control	1,026.000	TON	54.30	47.00	51.93
0390	249-B001	Remove and Reset Riprap	377.000	CY	12.90	16.00	37.14
0400	304-B002	Granular Material, Class 3, Group D	5,650.000	TON	12.80	17.50	27.85
0410	304-B008	Granular Material, Class 9, Group B	22,550.000	TON	7.70	6.50	16.25
0420	307-A004	6" Soil-Lime-Water Mixing, Class A	22,459.000	SY	2.00	2.30	2.12
0430	307-D001	Lime	303.000	TON	300.00	345.00	318.15
0440	307-S001	Bituminous Curing Seal	5,615.000	GAL	3.50	4.30	3.71
0450	308-A001	Cement	889.000	TON	184.00	211.60	195.13
0460	308-B002	Soil-Cement-Water Mixing, Optional Mixers, Base	22,459.000	SY	1.25	1.50	1.33
0470	308-B003	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	44,918.000	SY	1.25	1.55	1.33
0480	308-S001	Bituminous Curing Seal	16,844.000	GAL	3.50	4.35	3.71
0500	403-A001	12.5-mm, HT, Asphalt Pavement	2,406.000	TON	102.15	112.50	105.19
0510	403-A002	12.5-mm, MT, Asphalt Pavement	173.000	TON	156.75	172.50	161.42
0520	403-A003	12.5-mm, ST, Asphalt Pavement	1,464.000	TON	108.00	119.00	111.21
0530	403-A004	19-mm, HT, Asphalt Pavement	2,706.000	TON	89.80	99.00	92.44

Interchange Construction on SR 304 at McIngvale Road, known as Federal Aid Project No. NHPP-0029-02(022) / 107114301 in Desoto County.					Tanner Construction Company, Inc.	Xcavators, Inc.	M & N Excavators, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$8,961,476.93					\$7,854,903.14	\$7,998,514.20	\$8,210,310.33
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0540	403-A005	19-mm, MT, Asphalt Pavement	195.000	TON	156.75	172.50	161.42
0550	403-A006	19-mm, ST, Asphalt Pavement	6,041.000	TON	90.75	100.00	93.41
0560	403-A013	9.5-mm, HT, Asphalt Pavement	1,804.000	TON	113.75	125.00	117.13
0570	403-A014	9.5-mm, MT, Asphalt Pavement	1,298.000	TON	100.85	111.00	103.84
0580	403-A015	9.5-mm, ST, Asphalt Pavement	1,098.000	TON	123.35	136.00	126.98
0582	407-A001	Asphalt for Tack Coat	9,765.000	GAL	3.66	4.00	3.77
0590	406-A002	Cold Milling of Bituminous Pavement, All Depths	14,154.000	SY	2.90	1.75	2.96
0600	503-C010	Saw Cut, Full Depth	2,385.000	LF	6.50	3.00	11.61
0610	601-A001	Class "B" Structural Concrete	100.000	CY	1,540.00	800.00	1,856.80
0620	601-B001	Class "B" Structural Concrete, Minor Structures	55.000	CY	1,500.00	1,500.00	1,740.75
0630	602-A001	Reinforcing Steel	21,515.000	LBS	1.35	1.50	2.15
0640	603-CA011	18" Reinforced Concrete Pipe, Class III	312.000	LF	52.00	48.00	42.36
0650	603-CA026	24" Reinforced Concrete Pipe, Class III	224.000	LF	64.00	59.00	56.86
0660	603-CA040	30" Reinforced Concrete Pipe, Class III	160.000	LF	78.00	82.50	70.56
0670	603-CA055	36" Reinforced Concrete Pipe, Class III	360.000	LF	92.00	96.50	89.36
0680	603-CA076	48" Reinforced Concrete Pipe, Class III	104.000	LF	125.00	140.50	130.90
0690	603-CA087	54" Reinforced Concrete Pipe, Class III	104.000	LF	149.00	172.00	189.45
0700	603-CB003	18" Reinforced Concrete End Section	17.000	EA	815.00	1,060.00	1,145.41
0710	603-CB004	24" Reinforced Concrete End Section	4.000	EA	1,000.00	1,175.00	1,232.45
0720	603-CB005	30" Reinforced Concrete End Section	2.000	EA	1,200.00	1,235.00	1,302.08
0730	603-CB006	36" Reinforced Concrete End Section	6.000	EA	1,500.00	1,550.00	1,798.78
0740	603-CB008	48" Reinforced Concrete End Section	2.000	EA	2,150.00	2,200.00	2,553.10
0750	603-CB009	54" Reinforced Concrete End Section	2.000	EA	4,650.00	2,300.00	2,785.20
0760	603-CE028	58" x 36" Concrete Arch Pipe, Class A III	16.000	LF	140.00	200.00	230.94
0770	603-CF007	58" x 36" Concrete Arch Pipe End Section	1.000	EA	4,700.00	2,200.00	2,669.15
0780	604-A001	Castings	869.000	LBS	2.40	2.00	3.48

Interchange Construction on SR 304 at McIngvale Road, known as Federal Aid Project No. NHPP-0029-02(022) / 107114301 in Desoto County.					Tanner Construction Company, Inc.	Xcavators, Inc.	M & N Excavators, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$8,961,476.93					\$7,854,903.14	\$7,998,514.20	\$8,210,310.33
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0790	606-B001	Guard Rail, Class A, Type 1	325.000	LF	20.00	25.00	21.21
0800	606-D022	Guard Rail, Bridge End Section, Type I	4.000	EA	2,500.00	3,125.00	2,651.25
0810	606-E007	Guard Rail, Terminal End Section, Non-Flared	4.000	EA	2,850.00	3,562.50	3,022.43
0820	607-B018	60" Type I Chain Link Fence, Class II	14,287.000	LF	6.07	8.00	6.42
0830	607-P1008	Line Post, 7' x 1 1/2" Galvanized Steel	829.000	EA	38.67	30.00	40.99
0840	607-P1022	Line Post, 10' x 1 1/2" Galvanized Steel	166.000	EA	42.85	33.75	45.42
0850	607-P1031	Line Post, 9' x 1 1/2" Galvanized Steel	110.000	EA	41.80	43.75	44.31
0860	608-A001	Concrete Sidewalk, Without Reinforcement	1,387.000	SY	62.50	78.00	48.74
0870	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	808.000	LF	29.50	37.00	26.69
0880	609-D012	Combination Concrete Curb and Gutter Type 3A Modified	2,832.000	LF	22.00	27.50	23.21
0890	616-A001	Concrete Median and/or Island Pavement, 10-inch	63.000	SY	113.50	140.00	102.12
0900	616-A004	Concrete Median and/or Island Pavement, 4-inch	657.000	SY	50.50	63.00	48.74
0910	617-A001	Right-of-Way Marker	21.000	EA	238.87	630.00	261.11
0920	618-A001	Maintenance of Traffic	1.000	LS	455,000.00	46,875.00	60,926.25
0930	619-A1003	Temporary Traffic Stripe, Continuous White, Paint	17,994.000	LF	0.60	0.75	0.70
0940	619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	6,966.000	LF	0.60	0.75	0.70
0950	619-A3004	Temporary Traffic Stripe, Skip White, Paint	5,616.000	LF	0.60	0.75	0.70
0960	619-A5002	Temporary Traffic Stripe, Detail, Paint	24,798.000	LF	0.60	0.75	0.70
0970	619-A6003	Temporary Traffic Stripe, Legend, Paint	622.000	SF	2.50	3.10	2.90
0980	619-A6004	Temporary Traffic Stripe, Legend, Paint	881.000	LF	1.25	1.55	1.45
0990	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	81.000	SF	6.00	7.50	6.96
1000	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	888.000	SF	6.00	7.50	6.96
1010	619-G4001	Barricades, Type III, Double Faced	18.000	LF	14.00	17.50	16.25
1020	619-G4005	Barricades, Type III, Single Faced	288.000	LF	14.00	17.50	16.25
1030	619-G5001	Free Standing Plastic Drums	207.000	EA	40.00	50.00	46.42
1040	619-G7001	Warning Lights, Type "B"	6.000	EA	150.00	187.50	174.08

Interchange Construction on SR 304 at McIngvale Road, known as Federal Aid Project No. NHPP-0029-02(022) / 107114301 in Desoto County.					Tanner Construction Company, Inc.	Xcavators, Inc.	M & N Excavators, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$8,961,476.93					\$7,854,903.14	\$7,998,514.20	\$8,210,310.33
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1050	620-A001	Mobilization	1.000	LS	700,000.00	610,000.00	450,854.25
1060	621-A001	Field Laboratory	1.000	EA	15,000.00	31,250.00	27,693.75
1070	626-A002	6" Thermoplastic Double Drop Traffic Stripe, Skip White	4,816.000	LF	0.80	1.00	0.93
1080	626-B001	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	2,252.000	LF	0.95	1.20	1.10
1090	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	16,306.000	LF	0.95	1.20	1.10
1100	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	1,534.000	LF	0.95	1.20	1.10
1110	626-F002	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	6,271.000	LF	0.95	1.20	1.10
1120	626-G004	Thermoplastic Double Drop Detail Stripe, White	11,846.000	LF	2.00	2.50	2.32
1130	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	10,368.000	LF	2.00	2.50	2.32
1140	626-H001	Thermoplastic Double Drop Legend, White	702.000	SF	10.00	12.50	11.61
1150	626-H002	Thermoplastic Double Drop Legend, White	825.000	LF	4.00	5.00	4.64
1160	627-K001	Red-Clear Reflective High Performance Raised Markers	486.000	EA	8.00	10.00	9.28
1170	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	400.000	EA	8.00	10.00	9.28
1180	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	186.000	SF	22.00	27.50	24.44
1190	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	350.000	SF	23.00	28.75	25.55
1200	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	747.000	SF	29.00	36.25	32.22
1210	630-C002	Steel U-Section Posts, 2.0 lb/ft	68.000	LF	9.00	11.25	10.00
1220	630-C003	Steel U-Section Posts, 3.0 lb/ft	281.000	LF	11.00	13.75	12.22
1230	630-D004	Structural Steel Beams, W10 x 26	52.000	LF	95.00	118.75	105.55
1240	630-D006	Structural Steel Beams, W6 x 12	37.000	LF	65.00	81.25	72.22
1250	630-D007	Structural Steel Beams, W6 x 15	87.000	LF	70.00	87.50	77.77
1260	630-D008	Structural Steel Beams, W6 x 9	170.000	LF	60.00	75.00	66.66
1270	630-E001	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles	189.000	LBS	2.50	3.10	2.78
1280	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	184.000	LBS	2.50	1.10	2.78
1290	630-E003	Structural Steel Angles & Bars, 4" x 4" x 5/16" Angles	90.000	LBS	3.50	4.50	3.89
1300	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	393.000	LBS	2.50	3.10	2.78

Interchange Construction on SR 304 at McIngvale Road, known as Federal Aid Project No. NHPP-0029-02(022) / 107114301 in Desoto County.					Tanner Construction Company, Inc.	Xcavators, Inc.	M & N Excavators, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$8,961,476.93					\$7,854,903.14	\$7,998,514.20	\$8,210,310.33
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1310	630-F006	Delineators, Guard Rail, White	22.000	EA	18.00	22.50	20.00
1320	630-F010	Delineators, Post Mounted, Double White	98.000	EA	55.00	68.75	61.11
1330	630-F011	Delineators, Post Mounted, Double Yellow	15.000	EA	55.00	68.75	61.11
1340	630-F012	Delineators, Post Mounted, Single White	56.000	EA	45.00	56.25	50.00
1350	630-F013	Delineators, Post Mounted, Single Yellow	14.000	EA	45.00	56.25	50.00
1360	630-G004	Type 3 Object Markers, OM-3R or OM-3L	8.000	EA	75.00	93.75	83.33
1370	630-G008	Type 2 Object Markers, OM2-2	4.000	EA	65.00	81.25	72.22
1380	630-K001	Welded & Seamless Steel Pipe Posts, 3 1/2"	70.000	LF	55.00	68.75	61.11
1390	630-K002	Welded & Seamless Steel Pipe Posts, 3"	45.000	LF	50.00	62.50	55.55
1400	630-K003	Welded & Seamless Steel Pipe Posts, 4"	151.000	LF	60.00	75.00	66.66
1410	635-A059	Traffic Signal Head, Type 1	8.000	EA	884.00	1,105.00	1,025.88
1420	635-A061	Traffic Signal Head, Type 2	2.000	EA	884.00	1,105.00	1,025.88
1430	635-A065	Traffic Signal Head, Type 2 FYA	1.000	EA	1,500.00	1,875.00	1,740.75
1440	635-A073	Traffic Signal Head, Type 4	4.000	EA	1,350.00	1,687.50	1,566.68
1450	635-A076	Traffic Signal Head, Type 6	8.000	EA	738.00	922.50	856.45
1460	699-A001	Roadway Construction Stakes	1.000	LS	70,000.00	75,250.00	82,395.50
1472	815-A007	Loose Riprap, Size 300	15,320.000	TON	49.15	45.00	54.25
1480	815-E001	Geotextile under Riprap	26,449.000	SY	1.80	2.00	2.37
1490	815-F002	Sediment Control Stone	190.000	TON	54.50	45.00	47.87
1500	907-250-A001	Polyacrylamide (PAM)	960.000	LBS	20.00	20.00	11.55
1510	907-253-A001	Coir Fiber Baffle	567.000	LF	5.00	7.00	9.28
1520	907-608-C001	Detectable Warning Panels	160.000	SF	25.00	31.25	24.37
1530	907-619-E3001	Changeable Message Sign	2.000	EA	8,000.00	10,000.00	7,833.38
1540	907-630-O004	Remove and Reset Sign, All Sizes	10.000	EA	4,250.00	1,800.00	4,721.75
1550	907-632-A010	Solid State Traffic Cabinet Assembly, Type IV Cabinet, Type 1 Controller	2.000	EA	24,474.00	30,500.00	28,402.08
1560	907-632-J001	Power Service Pedestal	2.000	EA	4,000.00	5,000.00	4,642.00

Interchange Construction on SR 304 at McIngvale Road, known as Federal Aid Project No. NHPP-0029-02(022) / 107114301 in Desoto County.					Tanner Construction Company, Inc.	Xcavators, Inc.	M & N Excavators, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$8,961,476.93					\$7,854,903.14	\$7,998,514.20	\$8,210,310.33
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1570	907-633-A001	Uninterruptable Power Supply	2.000	EA	3,850.00	4,800.00	4,467.93
1580	907-634-A082	Traffic Signal Equipment Pole, Type II, 17' Shaft, 40' Arm	1.000	EA	9,075.00	11,500.00	10,531.54
1590	907-634-A083	Traffic Signal Equipment Pole, Type II, 17' Shaft, 45' Arm	1.000	EA	9,450.00	11,800.00	10,966.73
1600	907-634-A086	Traffic Signal Equipment Pole, Type II, 17' Shaft, 50' Arm	1.000	EA	9,562.00	12,000.00	11,096.70
1610	907-634-A088	Traffic Signal Equipment Pole, Type II, 17' Shaft, 60' Arm	1.000	EA	12,975.00	16,000.00	15,057.49
1620	907-634-A124	Traffic Signal Equipment Pole, Type II, 30' Shaft, 40' Arm	1.000	EA	9,262.00	11,500.00	10,748.55
1630	907-634-A129	Traffic Signal Equipment Pole, Type II, 30' Shaft, 60' Arm	1.000	EA	14,062.00	17,500.00	16,318.95
1640	907-634-A545	Traffic Signal Equipment Pole, Type VI, 8' Shaft	2.000	EA	1,125.00	1,400.00	1,305.56
1650	907-634-C001	Pole Foundations, Class "B" Concrete	17.000	CY	800.00	1,000.00	928.40
1660	907-636-B014	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 5 Conductor	1,451.000	LF	1.20	1.50	1.39
1670	907-636-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 8 Conductor	1,286.000	LF	1.90	2.35	2.20
1680	907-636-B028	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 8, 3 Conductor Power Cable	306.000	LF	2.25	2.80	2.61
1690	907-636-C009	Electric Cable, Aerial Supported, IMSA 20-1, AWG 14, 8 Conductor	102.000	LF	1.90	2.35	2.20
1700	907-637-A002	Pullbox Enclosure, Type 2	6.000	EA	850.00	1,000.00	986.43
1710	907-637-A003	Pullbox Enclosure, Type 3	4.000	EA	1,050.00	1,300.00	1,218.53
1720	907-637-C009	Traffic Signal Conduit, Underground, Rolled Pipe, 2"	426.000	LF	9.00	11.25	10.44
1730	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	100.000	LF	8.00	10.00	9.28
1740	907-637-C030	Traffic Signal Conduit, Underground, Type 4, 3"	72.000	LF	10.00	12.50	11.61
1750	907-637-D002	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 2"	134.000	LF	10.00	12.50	11.61
1760	907-637-D003	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3"	633.000	LF	12.00	15.00	13.93
1770	907-641-A002	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2	4.000	EA	8,205.00	10,000.00	9,521.90
1780	907-641-B002	Signal Advanced Radar Vehicle Detection Sensor, Type 2	4.000	EA	8,205.00	10,000.00	9,521.90
1790	907-641-D001	Radar Vehicle Detection Cable	1,601.000	LF	2.00	2.50	2.32
1800	907-645-B001	Accessible Pedestrian Detection Assembly	8.000	EA	898.00	1,100.00	1,042.13
1810	907-650-A002	On Street Video Equipment, Fixed Type	2.000	EA	2,898.00	3,600.00	3,363.13
1820	907-650-A003	On Street Video Equipment, PTZ Type	2.000	EA	7,698.00	9,600.00	8,933.53

Interchange Construction on SR 304 at McIngvale Road, known as Federal Aid Project No. NHPP-0029-02(022) / 107114301 in Desoto County.					Tanner Construction Company, Inc.	Xcavators, Inc.	M & N Excavators, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$8,961,476.93					\$7,854,903.14	\$7,998,514.20	\$8,210,310.33
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1830	907-653-A001	Traffic Sign	13.000	SF	23.00	28.75	26.69
1840	907-653-B001	Street Name Sign	12.000	SF	37.50	50.00	43.52
1850	907-661-B002	Fiber Optic Drop Cable, 12 SM	1,155.000	LF	4.00	5.00	4.64
1860	907-663-A002	Network Switch, Type B	2.000	EA	2,000.00	2,500.00	2,321.00
1870	907-663-D001	Category 6 Cable, Installed in Conduit	229.000	LF	1.00	2.00	1.16
1880	907-906001	Trainees	720.000	HRS	5.00	5.00	5.00