

Bridge Replacement on I-55 Replace Twin Bridges over Hickhala Creek and Relief Bridge, Bridge Nos. 266.8 A&B and 267.6 A&B, known as Federal Aid Project No. BR-0055-04(102) / 107214301 in Tate County.					Dement Construction Company, LLC	W. G. Yates & Sons Construction Company	Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$43,710,171.84					IRREGULAR		
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS	850,000.00	750,000.00	1,800,000.00
0020	202-A001	Removal of Obstructions	1.000	LS	1,131,000.00	2,850,000.00	925,000.00
0030	202-B007	Removal of Asphalt Pavement, All Depths	3,083.000	SY	10.00	6.00	15.00
0040	202-B039	Removal of Cable Barrier	2,909.000	LF	8.00	8.00	10.00
0050	202-B040	Removal of Cable Barrier Terminal Section	2.000	EA	2,000.00	2,500.00	2,000.00
0060	202-B058	Removal of Concrete Lug Anchor	80.000	EA	500.00	40.00	500.00
0070	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	44,396.000	SY	7.00	8.50	24.00
0080	202-B121	Removal of Edge Drain	3,140.000	LF	6.00	7.50	5.00
0090	202-B122	Removal of Edge Drain Outlet	157.000	EA	100.00	175.00	100.00
0100	202-B129	Removal of Flared End Section, All Sizes	5.000	EA	500.00	1,500.00	250.00
0110	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	1,715.000	LF	5.00	5.00	5.00
0120	202-B165	Removal of Inlets, All Sizes	5.000	EA	1,200.00	1,500.00	1,500.00
0130	202-B191	Removal of Pipe, 8" And Above	19.000	LF	10.00	100.00	20.00
0140	202-B229	Removal of Soil Cement, All Depths	100.000	SY	10.00	15.00	24.00
0150	202-B240	Removal of Traffic Stripe	1,120.000	LF	4.50	4.50	4.50
0160	203-A001	Unclassified Excavation, FM, AH	85,851.000	CY	5.00	5.00	5.00
0170	203-EX020	Borrow Excavation, AH, FME, Class B9	324,011.000	CY	10.80	11.50	18.50
0180	206-A001	Structure Excavation	520.000	CY	10.00	35.00	20.00
0190	206-B001	Select Material for Undercuts, Contractor Furnished, FM	17.000	CY	75.00	150.00	100.00
0200	209-A005	Geotextile Stabilization, Type V, Non-Woven	141,463.000	SY	3.00	3.25	3.50
0210	211-B001	Topsoil for Slope Treatment, Contractor Furnished	27,792.000	CY	1.00	3.50	1.00
0220	213-C001	Superphosphate	23.000	TON	650.00	660.00	650.00
0230	216-A001	Solid Sodding	244.000	SY	10.00	11.00	10.00
0240	217-A001	Ditch Liner	3,262.000	SY	1.50	2.00	1.50
0250	219-A001	Watering	5.000	KGAL	20.00	20.00	20.00
0260	220-A001	Insect Pest Control	46.000	ACRE	30.00	30.00	30.00

Bridge Replacement on I-55 Replace Twin Bridges over Hickhala Creek and Relief Bridge, Bridge Nos. 266.8 A&B and 267.6 A&B, known as Federal Aid Project No. BR-0055-04(102) / 107214301 in Tate County.					Dement Construction Company, LLC	W. G. Yates & Sons Construction Company	Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$43,710,171.84					IRREGULAR		
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	221-A001	Concrete Paved Ditch	32.000	CY	750.00	775.00	800.00
0280	223-A001	Mowing	92.000	ACRE	50.00	50.00	50.00
0290	224-A001	Soil Reinforcing Mat	1,769.000	SY	4.00	4.50	4.00
0300	225-A001	Grassing	46.000	ACRE	1,200.00	1,250.00	1,200.00
0310	225-B001	Agricultural Limestone	138.000	TON	50.00	60.00	50.00
0320	225-C001	Mulch, Vegetative Mulch	92.000	TON	150.00	155.00	150.00
0330	226-A001	Temporary Grassing	46.000	ACRE	850.00	900.00	850.00
0340	234-A001	Temporary Silt Fence	20,300.000	LF	3.50	3.75	3.50
0350	234-D001	Inlet Siltation Guard	5.000	EA	600.00	650.00	600.00
0360	234-E001	Reset Inlet Siltation Guard	5.000	EA	300.00	325.00	300.00
0370	234-F001	Turbidity Barrier	4,650.000	LF	20.00	21.00	20.00
0380	237-A002	Wattles, 20"	18,950.000	LF	5.00	5.25	5.00
0390	239-A001	Temporary Slope Drains	11,220.000	LF	8.00	11.00	5.00
0400	245-A001	Silt Dike	800.000	LF	7.00	7.50	7.00
0410	246-B001	Rockbags	8,400.000	EA	10.00	11.00	10.00
0420	249-A001	Riprap for Erosion Control	2,300.000	TON	65.00	65.00	75.00
0430	249-B001	Remove and Reset Riprap	1,150.000	CY	25.00	45.00	30.00
0440	304-B002	Granular Material, Class 3, Group D	37,370.000	TON	26.50	25.00	25.66
0450	307-C004	6" Soil-Lime-Water Mixing, Class C	36,480.000	SY	2.10	2.25	2.10
0460	307-D001	Lime	492.000	TON	320.00	330.00	320.00
0470	307-S001	Bituminous Curing Seal	9,120.000	GAL	3.50	3.75	3.50
0480	308-A001	Cement	309.000	TON	215.00	225.00	215.00
0490	308-B003	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	36,480.000	SY	2.10	2.25	2.10
0500	308-S001	Bituminous Curing Seal	9,120.000	GAL	3.50	3.75	3.50
0510	403-A001	12.5-mm, HT, Asphalt Pavement	6,406.000	TON	104.00	110.00	108.68
0520	403-A004	19-mm, HT, Asphalt Pavement	9,651.000	TON	98.00	105.00	102.41

Bridge Replacement on I-55 Replace Twin Bridges over Hickhala Creek and Relief Bridge, Bridge Nos. 266.8 A&B and 267.6 A&B, known as Federal Aid Project No. BR-0055-04(102) / 107214301 in Tate County.					Dement Construction Company, LLC	W. G. Yates & Sons Construction Company	Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$43,710,171.84					IRREGULAR		
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0524	403-A003	12.5-mm, ST, Asphalt Pavement	4,834.000	TON	100.50	110.00	105.02
0530	403-A006	19-mm, ST, Asphalt Pavement	9,746.000	TON	98.00	105.00	102.41
0540	403-A013	9.5-mm, HT, Asphalt Pavement	259.000	TON	135.00	145.00	141.08
0542	403-A015	9.5-mm, ST, Asphalt Pavement	1,780.000	TON	114.00	125.00	119.13
0550	403-S001	Joint Sealant	6.000	MI	4,000.00	4,250.00	4,180.00
0560	405-A001	Stone Matrix Asphalt, 12.5 mm Mixture	6,058.000	TON	133.00	145.00	138.99
0570	405-A002	Stone Matrix Asphalt, 9.5 mm Mixture	4,495.000	TON	140.00	150.00	146.30
0580	406-A002	Cold Milling of Bituminous Pavement, All Depths	21,523.000	SY	2.50	5.00	11.00
0590	406-D001	Fine Milling of Bituminous Pavement, All Depths	60,060.000	SY	2.25	4.00	5.00
0600	407-A001	Asphalt for Tack Coat	20,521.000	GAL	3.50	3.75	3.66
0610	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	359.000	LF	10.00	10.00	10.00
0620	423-A001	Rumble Strips, Ground In	7.000	MI	260.00	500.00	700.00
0630	502-A001	Reinforced Cement Concrete Bridge End Pavement	772.000	SY	225.00	245.00	234.50
0640	503-C010	Saw Cut, Full Depth	2,173.000	LF	10.00	10.00	20.00
0650	601-A001	Class "B" Structural Concrete	50.000	CY	1,000.00	2,500.00	2,000.00
0660	601-B001	Class "B" Structural Concrete, Minor Structures	20.000	CY	2,000.00	2,500.00	2,500.00
0670	601-B002	Class "C" Structural Concrete, Minor Structures	12.000	CY	2,000.00	2,500.00	1,200.00
0680	602-A001	Reinforcing Steel	9,428.000	LBS	1.00	2.50	3.00
0700	603-ALT003	18" Type A Alternate Pipe	1,444.000	LF	25.00	36.00	30.00
0710	603-CA011	18" Reinforced Concrete Pipe, Class III	544.000	LF	38.50	60.00	37.00
0720	603-CA026	24" Reinforced Concrete Pipe, Class III	528.000	LF	50.00	75.00	60.00
0730	603-CB003	18" Reinforced Concrete End Section	5.000	EA	2,500.00	2,000.00	1,100.00
0734	603-CB004	24" Reinforced Concrete End Section	8.000	EA	3,000.00	2,250.00	1,300.00
0740	604-B001	Gratings	2,500.000	LBS	4.00	6.50	5.00
0750	605-AA001	Geotextile for Subsurface Drainage, Type III	214.000	SY	3.00	5.50	5.00
0760	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	384.000	LF	18.00	12.00	18.00

Bridge Replacement on I-55 Replace Twin Bridges over Hickhala Creek and Relief Bridge, Bridge Nos. 266.8 A&B and 267.6 A&B, known as Federal Aid Project No. BR-0055-04(102) / 107214301 in Tate County.					Dement Construction Company, LLC	W. G. Yates & Sons Construction Company	Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$43,710,171.84					IRREGULAR		
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0770	605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	48.000	LF	19.00	15.00	19.00
0780	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	15.000	CY	80.00	150.00	100.00
0790	605-X005	Filter Material for Filter Beds, Type C	46,597.000	CY	75.00	30.00	39.98
0800	606-B001	Guard Rail, Class A, Type 1	1,400.000	LF	19.00	20.00	19.00
0810	606-D022	Guard Rail, Bridge End Section, Type 1	8.000	EA	2,450.00	2,500.00	2,450.00
0820	606-E005	Guard Rail, Terminal End Section, Flared	8.000	EA	2,500.00	2,550.00	2,500.00
0840	607-A002	60" Type "A" Woven Wire Fence, w/ Barbed Wire as Shown	8,998.000	LF	4.40	4.75	4.60
0850	607-E001	Barbed Wire Fence, Single Strand	150.000	LF	0.55	0.60	0.58
0860	607-G087	Gate, 12' x 52" Aluminum	9.000	EA	410.00	450.00	428.45
0870	607-G126	Gate, 3' x 52" Chain Link	4.000	EA	410.00	450.00	428.45
0880	607-P1011	Line Post, 7' x 4" Timber	562.000	EA	26.50	30.00	27.69
0890	607-P1019	Line Post, 9' x 4" Timber	112.000	EA	29.00	31.00	30.31
0900	607-P1022	Line Post, 10' x 1 1/2" Galvanized Steel	2.000	EA	36.00	40.00	37.62
0910	607-P1025	Line Post, 10' x 4" Timber	75.000	EA	30.00	32.00	31.35
0920	607-P2009	Brace Post, 8' x 6" Timber	116.000	EA	129.50	140.00	135.33
0930	607-P2015	Brace Post, 10' x 6" Timber	23.000	EA	136.00	145.00	142.12
0940	607-P2019	Brace Post, 12' x 6" Timber	15.000	EA	139.00	150.00	145.26
0950	607-P3006	Gate Post, 8' x 6" Timber	13.000	EA	129.50	140.00	135.33
0960	607-Z001	Concrete Anchors	185.000	EA	35.00	40.00	35.53
0970	610-B001	Cable Barrier Terminal Section	2.000	EA	2,500.00	5,500.00	5,000.00
0980	612-A001	Flowable Fill, Excavatable	95.000	CY	300.00	300.00	300.00
0990	615-A024	Concrete Bridge End Barrier, 37.5"	160.000	LF	100.00	50.00	76.00
1000	617-B001	Permanent Easement Marker	16.000	EA	225.00	275.00	500.00
1010	618-A001	Maintenance of Traffic	1.000	LS	300,000.00	400,000.00	620,000.00
1020	619-A1001	Temporary Traffic Stripe, Continuous White	14.000	MI	1,500.00	1,525.00	1,500.00
1030	619-A1005	Temporary Traffic Stripe, Continuous White, Type 1 Tape	5,222.000	LF	3.00	3.10	3.00

Bridge Replacement on I-55 Replace Twin Bridges over Hickhala Creek and Relief Bridge, Bridge Nos. 266.8 A&B and 267.6 A&B, known as Federal Aid Project No. BR-0055-04(102) / 107214301 in Tate County.					Dement Construction Company, LLC	W. G. Yates & Sons Construction Company	Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$43,710,171.84					IRREGULAR		
Ref#	Item	Item Description	Item Qty	Units	1	2	3
					\$51,159,353.28	\$52,458,410.10	\$56,052,072.18
1040	619-A2001	Temporary Traffic Stripe, Continuous Yellow	13.000	MI	1,500.00	1,525.00	1,500.00
1050	619-A2006	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	5,222.000	LF	3.00	3.10	3.00
1060	619-A3001	Temporary Traffic Stripe, Skip White	10.000	MI	1,500.00	1,525.00	1,500.00
1070	619-A3006	Temporary Traffic Stripe, Skip White, Type 1 Tape	5,222.000	LF	3.00	3.10	3.00
1080	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	75.000	SF	7.50	10.25	10.00
1090	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	960.000	SF	7.50	10.25	10.00
1100	619-D4001	Directional Signs	168.000	SF	7.50	165.00	160.00
1110	619-F1001	Concrete Median Barrier, Precast	17,617.000	LF	30.00	60.00	55.00
1120	619-F2001	Remove and Reset Concrete Median Barrier, Precast	11,398.000	LF	12.00	12.00	27.00
1130	619-G4005	Barricades, Type III, Single Faced	72.000	LF	13.50	25.00	24.00
1140	619-G5001	Free Standing Plastic Drums	23.000	EA	45.00	75.00	70.00
1150	619-G7001	Warning Lights, Type "B"	22.000	EA	150.00	210.00	200.00
1160	619-J1004	Impact Attenuator, 60 MPH	4.000	EA	8,500.00	7,500.00	6,500.00
1170	619-J2004	Impact Attenuator, 60 MPH, Replacement Package	4.000	EA	6,500.00	3,000.00	2,500.00
1180	620-A001	Mobilization	1.000	LS	5,000,000.00	4,000,000.00	5,700,000.00
1190	626-A001	6" Thermoplastic Double Drop Traffic Stripe, Skip White	4.000	MI	2,500.00	2,550.00	2,500.00
1200	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	4.000	MI	4,800.00	4,900.00	4,800.00
1210	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	4.000	MI	4,800.00	4,900.00	4,800.00
1220	627-K001	Red-Clear Reflective High Performance Raised Markers	318.000	EA	15.00	15.50	15.00
1230	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	43.000	SF	20.00	20.50	20.00
1240	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	136.000	SF	21.00	21.50	21.00
1250	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	527.000	SF	28.00	29.00	28.00
1260	630-C002	Steel U-Section Posts, 2.0 lb/ft	33.000	LF	11.00	11.50	11.00
1270	630-C003	Steel U-Section Posts, 3.0 lb/ft	183.000	LF	12.00	12.50	12.00
1280	630-D005	Structural Steel Beams, W12 x 26	117.000	LF	115.00	120.00	115.00
1290	630-D009	Structural Steel Beams, W8 x 18	82.000	LF	95.00	100.00	95.00

Bridge Replacement on I-55 Replace Twin Bridges over Hickhala Creek and Relief Bridge, Bridge Nos. 266.8 A&B and 267.6 A&B, known as Federal Aid Project No. BR-0055-04(102) / 107214301 in Tate County.					Dement Construction Company, LLC	W. G. Yates & Sons Construction Company	Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$43,710,171.84					IRREGULAR		
Ref#	Item	Item Description	Item Qty	Units	\$51,159,353.28	\$52,458,410.10	\$56,052,072.18
					1	2	3
1300	630-E001	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles	89.000	LBS	3.50	4.00	3.50
1310	630-E003	Structural Steel Angles & Bars, 4" x 4" x 5/16" Angles	129.000	LBS	3.50	4.00	3.50
1320	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	123.000	LBS	3.50	4.00	3.50
1330	630-F006	Delineators, Guard Rail, White	56.000	EA	18.00	20.00	18.00
1340	630-F007	Delineators, Guard Rail, Yellow	56.000	EA	18.00	20.00	18.00
1350	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	8.000	EA	75.00	80.00	75.00
1360	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	8.000	EA	75.00	80.00	75.00
1370	630-K003	Welded & Seamless Steel Pipe Posts, 4"	128.000	LF	58.00	60.00	58.00
1380	699-A001	Roadway Construction Stakes	1.000	LS	306,000.00	400,000.00	400,000.00
1390	907-402-A002	Open Graded Friction Course, 9.5-mm Mixture	2,715.000	TON	140.00	150.00	146.30
1400	907-402-B001	Bituminous Tack Coat	6,931.000	GAL	5.50	6.00	5.75
1402	907-513-A001	Cracking and Seating Concrete Pavement	18,550.000	SY	1.50	6.00	4.00
1410	907-619-E3001	Changeable Message Sign	4.000	EA	8,500.00	15,000.00	14,500.00
1420	907-906001	Trainees	1,040.000	HRS	5.00	5.00	5.00
1430	304-F001	3/4" and Down Crushed Stone Base	49,800.000	TON	43.00		46.36
1440	304-F002	Size 610 Crushed Stone Base	49,800.000	TON		36.00	
1450	304-F003	Size 825B Crushed Stone Base	49,800.000	TON			
1460	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	186.000	CY	80.00	50.00	
1470	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	186.000	CY			80.00
1480	501-K001	Transverse Grooving	12,566.000	SY	2.30	2.50	3.00
1490	802-C001	Temporary Steel Sheet Piling	59,854.000	SF	7.50	26.00	18.25
1500	803-D007	HP 14 x 89 Steel Piling	9,900.000	LF	48.00	60.00	52.80
1510	803-K013	Drilled Shaft, 96" Diameter	1,500.000	LF	960.00	2,000.00	960.00
1520	803-L008	Test Shaft, 96" Diameter	1.000	EA	275,000.00	450,000.00	275,000.00
1530	803-M011	Trial Shaft, 96" Diameter	132.000	LF	1,000.00	2,250.00	1,000.00
1540	803-N001	Exploration	120.000	LF	100.00	1.00	100.00

Bridge Replacement on I-55 Replace Twin Bridges over Hickhala Creek and Relief Bridge, Bridge Nos. 266.8 A&B and 267.6 A&B, known as Federal Aid Project No. BR-0055-04(102) / 107214301 in Tate County.					Dement Construction Company, LLC	W. G. Yates & Sons Construction Company	Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$43,710,171.84					IRREGULAR		
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1550	803-O014	Permanent Casing, 96" Diameter	720.000	LF	600.00	650.00	600.00
1560	803-P003	30" Steel Pipe Piling, Wall Thickness 0.500"	6,150.000	LF	200.00	160.00	180.00
1570	804-C192	100' Prestressed Concrete Beam, Type FIB-36	11,120.000	LF	300.00	235.00	257.00
1580	805-A001	Reinforcement	1,172,402.000	LBS	0.89	1.00	0.94
1590	805-C001	Reinforcement, Corrosion Resistant	18,168.000	LBS	1.10	1.75	2.00
1600	810-A007	Structural Steel, A 709, Grade 50W	4,278,900.000	LBS	2.00	1.63	1.86
1610	811-D001	Disc Bearing Device	40.000	EA	5,000.00	8,000.00	2,600.00
1620	813-A004	Concrete Railing, 36"	5,976.000	LF	85.00	50.00	67.29
1630	815-A002	Loose Riprap, Size 100	12,390.000	TON	50.00	55.00	57.56
1640	815-A007	Loose Riprap, Size 300	466.000	TON	80.00	60.00	80.00
1650	815-E001	Geotextile under Riprap	14,961.000	SY	2.40	3.75	2.50
1660	815-F002	Sediment Control Stone	70.000	TON	50.00	75.00	100.00
1670	907-803-B001	Conventional Static Pile Load Test	6.000	EA	5,000.00	5,000.00	5,000.00
1680	907-803-I003	PDA Test Pile, HP Steel Pile	8.000	EA	5,000.00	15,000.00	13,600.00
1690	907-803-I004	PDA Test Pile, Steel Pipe Pile	4.000	EA	20,000.00	25,000.00	25,500.00
1700	907-803-J001	Pile Restrike	6.000	EA	1,000.00	1,500.00	1,000.00
1710	907-804-A001	Bridge Concrete, Class BDX	2,034.000	CY	850.00	900.00	972.00
1720	907-804-A002	Bridge Concrete, Class AA	1,688.000	CY	900.00	900.00	900.00
1730	907-804-A004	Bridge Concrete, Class BD	1,740.000	CY	850.00	950.00	850.00