

Call 01 Slide Repair on HWY 16 approximately 1.5 miles East of US 49 West, known as Federal Aid Project No. ER-0037-04(067) / 108456301 in Yazoo County.

Q1. Would the Department furnish the geotechnical report and the boring logs for this project?

A1. The boring logs can be downloaded from the following link:

<https://file-exchange.mdot.state.ms.us/dl/?f=68f62a9e1dc3f28713d7f580f476ef51bf2d8e3c>

Q2. Will construction joints be allowed in the concrete buttress headwall so that this headwall can be constructed in sections? If so, what is the minimum joint spacing allowed?

A2. Yes, construction joints will be allowed. The Contractor shall submit proposed construction joint locations for approval to the Project Engineer.

Q3. There are some blue markers/pipes in the west bound lane that we assume are marking a water line. Does MDOT have any details on this or other Utilities that may affect the project?

A3. These are pipes installed by the Geotechnical Branch during their investigation of the slide. They are sacrificial and will be removed by the Contractor.