

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO.	<u>1</u>	DATED	<u>4/22/2020</u>	ADDENDUM NO.	_____	DATED	_____
ADDENDUM NO.	_____	DATED	_____	ADDENDUM NO.	_____	DATED	_____
ADDENDUM NO.	_____	DATED	_____	ADDENDUM NO.	_____	DATED	_____

Number	Description
1	Revised Bid Items; Revised or Added Plan Sheets No. 2 & 4; Amendment EBSx Download Required.

TOTAL ADDENDA: 1
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

 Contractor

BY _____
 Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

President	Address
Secretary	Address
Treasurer	Address

The following is my (our) itemized proposal.

MP-1371-29(005)/ 306967301000
 Itawamba County(ies)

Revised 01/26/2016

Scrub Seal & Overlay approximately 7 miles of SR 371 from Monroe County Line to Lee County Line, known as State Project No. MP-1371-29(005) / 306967301 in Itawamba County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	304-A003	(GY)	2,222	Cubic Yard	Granular Material, LVM, Class 3, Group D
0020	406-A002		4,500	Square Yard	Cold Milling of Bituminous Pavement, All Depths
0030	407-A001	(A2)	10,000	Gallon	Asphalt for Tack Coat
0040	618-A001		1	Lump Sum	Maintenance of Traffic
0050	618-B001		1	Square Feet	Additional Construction Signs [\$10.00]
0060	619-A1001		31	Mile	Temporary Traffic Stripe, Continuous White
0070	619-A2001		11	Mile	Temporary Traffic Stripe, Continuous Yellow
0080	619-A4002		13	Mile	Temporary Traffic Stripe, Skip Yellow
0090	619-A5001		7,632	Linear Feet	Temporary Traffic Stripe, Detail
0100	619-A6002		2,974	Linear Feet	Temporary Traffic Stripe, Legend
0110	620-A001		1	Lump Sum	Mobilization
0120	626-C004		13	Mile	6" Thermoplastic Edge Stripe, Continuous White
0130	626-D003		7	Mile	6" Thermoplastic Traffic Stripe, Skip Yellow
0140	626-E004		6	Mile	6" Thermoplastic Traffic Stripe, Continuous Yellow
0150	626-G002		3,820	Linear Feet	Thermoplastic Detail Stripe, White
0160	626-H005		1,990	Linear Feet	Thermoplastic Legend, White
0170	627-J001		530	Each	Two-Way Clear Reflective High Performance Raised Markers
0180	627-L001		470	Each	Two-Way Yellow Reflective High Performance Raised Markers
0190	907-411-A001	(BA1)	7,600	Ton	Ultra Thin Asphalt Pavement
0200	907-414-A001		125,000	Square Yard	Scrub Seal
0210	907-619-B001		66	Linear Feet	Temporary Portable Rumble Strips
ALTERNATE GROUP AA NUMBER 1					
0220	304-H001	(GY)	20	Cubic Yard	3/4" and Down Crushed Stone Base, LVM
ALTERNATE GROUP AA NUMBER 2					
0230	304-H002	(GY)	20	Cubic Yard	Size 610 Crushed Stone Base, LVM
ALTERNATE GROUP AA NUMBER 3					
0240	304-H003	(GY)	20	Cubic Yard	Size 825B Crushed Stone Base, LVM

ADDENDUM

DESCRIPTION OF SHEET

- TITLE SHEET (1)
- DETAILED INDEX & GENERAL NOTES (1)
- DETAILED INDEX & GENERAL NOTES
- TYPICAL SECTION SHEETS (1)
- TYPICAL OVERLAY SECTION FOR SR 371
- QUANTITY SHEETS (1)
- SUMMARY OF QUANTITIES
- SPECIAL DESIGN SHEETS (3)
- DETAIL OF CONSTRUCTION SIGNING
- DETAIL OF CONSTRUCTION SIGNING
- DETAIL OF MILLING
- SIGNING OF TWO-WAY TRAFFIC FOR NO PASSING ZONES
- STANDARD DRAWINGS - ROADWAY SHEETS (8)
- PAVEMENT MARKING DETAILS FOR 2 AND 4-LANE DIVIDED ROADWAYS
- 2-WAY RAISED PAVEMENT MARKERS AT INTERSECTING ROADS (2-LANE)
- TRAFFIC CONTROL PLAN WITH FLAGGER (ONE-LANE CLOSURE OF TWO-WAY TRAFFIC)
- TRAFFIC CONTROL PLAN FOR POSTED SPEED LIMIT LESS THAN 65 MPH
- HIGHWAY SIGN AND BARRICADE DETAILS FOR CONSTRUCTION PROJECTS
- TRAFFIC CONTROL PLAN MOBILE OPERATIONS MULTILANE ROADS AND TWO-LANE ROADS
- TRAFFIC CONTROL PLANS UNEVEN PAVEMENT DETAILS
- TEMPORARY STRIPING FOR TRAFFIC CONTROL 2-LANE AND 4-LANE DIVIDED HIGHWAYS

WKG. NO. SH. NO.

- 1
- DI-1 2
- TS-1 3
- SQ-1 4
- CS-1 5
- CS-2 6
- DM-1 7
- TC-1 8
- PM-1 6051
- PM-11 6061
- TCP-1 6351
- TCP-2 6352
- TCP-8 6358
- TCP-9 6359
- TCP-12 6362
- TCP-13 6363

GENERAL NOTES

- (1) THE LOCATION AND SPACING OF SIGNS, SHOWN ON THE TRAFFIC CONTROL PLANS, ARE APPROXIMATE AND MAY BE ADJUSTED AS NECESSARY TO FIT FIELD CONDITIONS.
- (2) MAXIMUM LANE CLOSURE ALLOWED IS 1 MILE. A MINIMUM DISTANCE OF 3 MILES IS REQUIRED FOR CLOSURES IN ADJACENT LANES. A MINIMUM OF 2 MILES IS REQUIRED FOR CLOSURES IN THE SAME LANE.
- (3) FLUORESCENT ORANGE SHEETING SHALL BE USED ON ALL CONSTRUCTION AND TRAFFIC CONTROL SIGNS EXCEPT FOR THOSE DESIGNATED ON THE PLANS TO BE BLACK LEGEND AND BORDER ON WHITE BACKGROUND.
- (4) ALL TRAFFIC CONTROL DEVICES ON THIS PROJECT SHALL COMPLY WITH PART VI OF THE MUTCD (LATEST EDITION).
- (5) BIDDER ARE ADVISED THAT HARD COPIES OF ANY ADDENDA FOR THIS PROJECT WILL NO LONGER BE MAILED. ALL ADDENDA FOR THIS PROJECT WILL BE POSTED TO WWW.MDOT.MS.GOV UNDER THE PROPOSAL ADDENDA COLUMN. IT IS THE BIDDERS RESPONSIBILITY TO CHECK AND SEE IF ANY ADDENDA HAVE BEEN POSTED FOR THIS PROJECT. PLEASE CONTACT CONTRACT ADMINISTRATION DIVISION AT 601-359-7700 FOR ANY QUESTIONS REGARDING ELECTRONIC ADDENDA.

PS & E PLANS-DATE...03/24/20	
FMS CON. # 306967/301000	
REVISIONS	
DATE	BY
04/14/20	TRG
2,4	

TRG	DATE	ADDED REVISION TO TABLE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

DETAILED INDEX

PROJ. NO.: MP-1371-29(005)
COUNTY: ITAWAMBA

FILENAME: MP-1371-29(005).dgn
DESIGN TEAM: _____
CHECKED: _____
DATE: _____

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

WORKING NUMBER
DI-1

SHEET NUMBER
2

TOTAL NUMBER OF SHEETS (15)

ADDENDUM

STATE	PROJECT NO.
MISS	MP-1371-29(005)

SUMMARY OF QUANTITIES (SHEET 1)

PAY ITEM NO.	PAY ITEM	UNIT	ITAWAMBA : 306967-301000	
			Prelim	Final
304-A003	Granular Material, LVM, Class 3, Group D	CY	2,222	
304-H001	3/4" and Down Crushed Stone Base, LVM	CY	20	
304-H002	OR	CY	20	
304-H003	Size 610 Crushed Stone Base, LVM	CY	20	
406-A002	OR	CY	20	
407-A001	Size 825B Crushed Stone Base, LVM	CY	20	
907-411-A001	Cold Milling of Bituminous Pavement, All Depths	SY	4,500	
907-414-A001	Asphalt for Tack Coat	GAL	10,000	
	Ultra Thin Asphalt Pavement	TON	7,600	
	Scrub Seal	SY	125,000	
618-A001	Maintenance of Traffic	LS	1	
618-B001	Additional Construction Signs	SF	1	
620-A001	Mobilization	LS	1	
619-A1001	Temporary Traffic Stripe, Continuous White	MI	31	
619-A2001	Temporary Traffic Stripe, Continuous Yellow	MI	11	
619-A4002	Temporary Traffic Stripe, Skip Yellow	MI	13	
619-A5001	Temporary Traffic Stripe, Detail	LF	7,632	
619-A6002	Temporary Traffic Stripe, Legend	LF	2,974	
626-C004	6" Thermoplastic Edge Stripe, Continuous White	MI	13	
626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	MI	7	
626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	MI	6	
626-G002	Thermoplastic Detail Stripe, White	LF	3,820	
626-H005	Thermoplastic Legend, White	LF	1,990	
627-J001	Two-Way Clear Reflective High Performance Raised Markers	EA	530	
627-L001	Two-Way Yellow Reflective High Performance Raised Markers	EA	470	

- ① 358 TONS FOR APRONS AND COUNTY ROADS.
- ② INCLUDES QUANTITY FOR BRIDGE, B.O.P, E.O.P AND COUNTY ROADS.
- ③ INCLUDES 50% FOR SHRINKAGE FACTOR.

③

② ▲

①

04/14/2020 TRG

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PROJ NO: MP-1371-29(005)
COUNTY: ITAWAMBA

Working Number
SQ-1

Sheet Number
4

REPLACED PAY ITEM 406-A001 WITH 406-A002.

Revision

Date	Checked	Date
04/14/2020	Design Team	
FILENAME: SQS		

