

PROJECT NUMBER BR-0020-01(248)

107878/101000





LENGTH DATA

LENGTH OF ROADWAY LENGTH OF BRIDGES LENGTH OF PROJECT (NET) LENGTH OF EXCEPTIONS LENGTH OF PROJECT (GROSS)


NONE



BRIDGE

NONE

ROADWAY



BR-0020-01(248)

HINDS COUNTY

COUNTY LINE

SECTION LINE

RAILROAD.

BRIDGES

SURVEY LINE

TOWN CORPORATION LINE


EXISTING ROAD OR TRAVELED WAY ----


PROPOSED ROAD OR TRAVELED WAY

									1100 0011.10707070010
st O.REV.				a			.4		STATE PROJECT N
	DESCRIPTION OF SHEET	REVISION DATE	WKG. NO.	SH. NO.	DESCRIPTION OF SHEET	REVISION DATE	WKG. NO.	SH. NO.	MISS. BR-0020-01(2
		DAIL	NO.	NO.	DOADWAY CTANDADD DDAWINGC - (11)	DAIL	INO.	INO.	
ROADWAY (11)					ROADWAY STANDARD DRAWINGS - (11)				
TITLE SHEET (1)				1	PAVEMENT (1)				
DETAILED INDEX &	GENERAL NOTES (2)				PAVEMENT MARKING DETAILS FOR 2-LANE AND 4-LANE DIVIDED ROADWAYS		PM-1	6051	
DETAILED IN			DI-1	2					
GENERAL NO	TES		GN-1	3	PROTECTIVE BARRIERS (1)				
TYPICAL SECTIONS	5 (1)				CONCRETE MEDIAN BARRIER (PRECAST) (32")		CMB-3	6226	
TYPICAL SEC	CTION - I-20		TS-1	4	SIGNING (3)				
QUANTITY SHEETS (3)					STANDARD ROADSIDE SIGNS		SN-3A	6304	
					STANDARD ROADSIDE SIGN ASSEMBLY AND INSTALLATION		SN-4	6306	
SUMMARY OF QUANTITIES			SQ-1	5	STANDARD ROADSIDE SIGN ASSEMBLY AND INSTALLATION		SN-4A	6307	
ESTIMATED QUANTITIES - PAVEMENT MARKINGS AND TRAFFIC CONTROL ITEMS			EQ-1	6					
ESTIMATED QUANTITIES - TRAFFIC CONTROL SIGNS			EQ-2	7	TRAFFIC CONTROL PLANS (6)				
SPECIAL DESIGN - ROADWAY ITEMS (4)					TRAFFIC CONTROL PLAN FOR POSTED SPEED LIMIT OF 65 OR 70 MPH (INTERSTATES AND OTHER 4-LANE DIVIDED HIGHWAYS)		TCP-4	6354	
CONSTRUCT	TION SIGNING DETAIL - I-20		DCS-1	8	(MEDIAN LANE OR OUTSIDE LANE CLOSURE) (EXTENDED PERIOD)				
	ONTROL PLAN - PHASE 1		TC-1	9	TRAFFIC CONTROL PLAN (WORK DAY ONLY)		TCP-5	6355	
	ONTROL PLAN - PHASE 2		TC-2	10	HIGHWAY SIGN AND BARRICADE DETAILS FOR CONSTRUCTION PROJECTS		TCP-8	6358	
	MARKING DETAIL - I-20		PMD-1	11	TEMPORARY STRIPING FOR TRAFFIC CONTROL 2-LANE AND 4-LANE DIVIDED HIGHWAYS		TCP-13	6363	
					LOCATION OF R16-3 SIGNS (SPEEDING FINES DOUBLED)		TCP-15	6365	
					TRAFFIC CONTROL DETAILS - DRUM PLACEMENT AND SHOULDER CLOSURE		TCP-16	6366	
					TOTAL SHEETS (NOT INCLUDING BRIDGE SHEETS) (22)				









ZUU HW

STATE	PROJECT NO				
MISS.	BR-0020-01(24				

GENERAL NOTES

- (1) THE LOCATION AND SPACING OF SIGNS, SHOWN ON THE TRAFFIC CONTROL PLANS, ARE APPROXIMATE AND MAY BE ADJUSTED AS NECESSARY TO FIT FIELD CONDITIONS.
- (2) ALL TRAFFIC CONTROL DEVICES ON THIS PROJECT SHALL COMPLY WITH PART VI OF THE **MUTCD** (LATEST EDITION).
- (3) ALL PLASTIC DRUMS SHALL HAVE A BALLASTING COLLAR MADE FROM RECYCLED TRUCK TIRES OR OTHER SUITABLE MATERIAL.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING EXISTING STRUCTURES SUCH AS, BUT NOT LIMITED TO, PIPES, INLETS, APRONS, AND BRIDGES FROM DAMAGE WHICH MIGHT OCCUR DURING CONSTRUCTION. THE CONTRACTOR SHALL REPLACE OR REPAIR, AS DIRECTED BY THE ENGINEER, ANY STRUCTURES DAMAGED DURING THE LIFE OF THE CONTRACT. NO PAYMENT WILL BE MADE FOR REPLACEMENT OR REPAIR OF DAMAGED ITEMS.
- (5) FLUORESCENT ORANGE SHEETING SHALL BE USED ON ALL CONSTRUCTION AND TRAFFIC CONTROL SIGNS EXCEPT FOR THOSE DESIGNATED ON THE PLANS TO BE BLACK LEGEND AND BORDER ON WHITE BACKGROUND.
- (6) THE CONTRACTOR SHALL COVER OR REMOVE ANY TEMPORARY TRAFFIC CONTROL SIGNS SHOWN IN THE TRAFFIC CONTROL PLAN THAT DO NOT APPLY TO THE CURRENT PHASE.
- REMOVAL OF RAISED PAVEMENT MARKERS THAT ARE IN CONFLICT WITH REQUIRED CONSTRUCTION IS NOT CONSIDERED A SEPARATE PAY ITEM. COST TO BE ABSORBED IN OTHER ITEMS BID.
- (8) TEMPORARY STRIPING SHALL CONFORM TO FINISHED STRIPE SPECIFICATIONS FOR ALIGNMENT, NEATNESS, AND STRAIGHTNESS.
- (9) SEE BRIDGE PLANS FOR DETAILED INDEX SHEET(S), ESTIMATED AND SUMMARY OF QUANTITY SHEETS, AND EROSION CONTROL SHEETS.
- (10) ALL ADDENDA TO THESE PLANS WILL BE POSTED TO WWW.MDOT.MS.GOV UNDER THE PROPOSAL ADDENDA COLUMN. BIDDERS ARE ADVISED THAT HARD COPIES OF ANY ADDENDA FOR THIS PROJECT WILL NOT BE MAILED. IT IS THE BIDDER'S RESPONSIBILITY TO CHECK AND SEE IF ANY ADDENDA HAVE BEEN POSTED FOR THIS PROJECT.
- (11) THE BRIDGE DECKS SHALL BE GROOVED AND ALL BRIDGE JOINTS SHALL BE SEALED PRIOR TO OPENING THE BRIDGES TO TRAFFIC.
- (12) STORAGE OF FLAMMABLE MATERIALS WILL NOT BE ALLOWED UNDER ANY BRIDGE STRUCTURES.
- (13) SOME WORK IS REQUIRED OUTSIDE THE PROJECT LIMITS. NO ADDITIONAL COMPENSATION WILL BE MADE FOR SUCH WORK EXCEPT AS PROVIDED BY SPECIFIC PAY ITEMS INCLUDED IN THE PLANS.
- (14) THE CONTRACTOR SHALL COORDINATE WITH THE CONTRACTOR FROM ADJACENT PROJECT(S) IN IMPLEMENTING THE TRAFFIC CONTROL PLAN AS DIRECTED BY THE ENGINEER. ALL CONFLICTING SIGNS SHALL BE COVERED OR REMOVED AS DIRECTED BY THE ENGINEER.

