

Call 08 Mill & Overlay approximately 1.3 miles of SR 19 from end of proposed 4-Lane to SR 16, known State Project No. MP-5019-50(014) / 306932301 in Neshoba County.

Q1. If the Contractor elects to mill for pavement removal in the failed areas instead of saw cuts, will payment be made for saw cuts not performed?

A1. No.

Q2. The base repairs that fall in the areas with 2"-4" Asphalt overlaid on 5.5" of JRCP, which appears to be the majority in the table provided. Is it the intent to saw cut full depth through the asphalt only, remove and repair just asphalt or does it mean saw cut full depth through concrete and asphalt, remove both and repair? If concrete is to be removed, how will the contractor be paid? There is no pay item for removal of concrete. Please clarify.

A2. See addendum.