

Bridge Replacements on SR 198 near Columbia, (Bridge Nos. 119.0 & 119.3), known as Federal Aid Project No. CHBP-0046-01(013) / 102471301 in Marion County.					T. L. Wallace Construction, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$9,398,510.53					\$8,871,455.76		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	201-B001	Clearing and Grubbing	4.000	ACRE	900.00		
0020	202-A001	Removal of Obstructions	1.000	LS	208,000.00		
0030	202-B007	Removal of Asphalt Pavement, All Depths	4,108.000	SY	5.70		
0040	202-B050	Removal of Concrete Combination Curb & Gutter	4,956.000	LF	10.15		
0050	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	2,888.000	SY	14.25		
0060	202-B129	Removal of Flared End Section, All Sizes	14.000	EA	573.25		
0070	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	598.000	LF	9.60		
0080	202-B165	Removal of Inlets, All Sizes	10.000	EA	802.00		
0090	202-B191	Removal of Pipe, 8" And Above	495.000	LF	15.85		
0100	202-B213	Removal of Sign	3.000	EA	89.95		
0110	202-B215	Removal of Sign Including Post & Footing	7.000	EA	419.75		
0120	202-B219	Removal of Sign, Ground Mounted with Posts	36.000	EA	275.00		
0130	203-A001	Unclassified Excavation, FM, AH	8,659.000	CY	6.75		
0140	203-EX021	Borrow Excavation, AH, FME, Class B9-6	23,402.000	CY	8.90		
0150	203-G001	Excess Excavation, FM, AH	3,291.000	CY	8.00		
0160	206-A001	Structure Excavation	169.000	CY	15.00		
0170	209-A005	Geotextile Stabilization, Type V, Non-Woven	17,200.000	SY	2.15		
0180	211-B001	Topsoil for Slope Treatment, Contractor Furnished	4,310.000	CY	1.00		
0190	213-C001	Superphosphate	6.000	TON	875.00		
0200	216-A001	Solid Sodding	9,182.000	SY	5.10		
0210	217-A001	Ditch Liner	650.000	SY	2.40		
0220	219-A001	Watering	182.000	KGAL	20.00		
0230	220-A001	Insect Pest Control	6.000	ACRE	30.00		
0240	221-A001	Concrete Paved Ditch	17.000	CY	875.00		
0250	223-A001	Mowing	22.000	ACRE	50.00		
0260	225-A001	Grassing	11.000	ACRE	1,150.00		

Bridge Replacements on SR 198 near Columbia, (Bridge Nos. 119.0 & 119.3), known as Federal Aid Project No. CHBP-0046-01(013) / 102471301 in Marion County.					T. L. Wallace Construction, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$9,398,510.53					\$8,871,455.76		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	225-B001	Agricultural Limestone	6.000	TON	108.00		
0280	225-C001	Mulch, Vegetative Mulch	22.000	TON	212.00		
0290	226-A001	Temporary Grassing	11.000	ACRE	1,000.00		
0300	234-A001	Temporary Silt Fence	100.000	LF	5.30		
0310	234-C001	Super Silt Fence	4,000.000	LF	11.00		
0320	234-D001	Inlet Siltation Guard	5.000	EA	585.00		
0330	234-F001	Turbidity Barrier	1,000.000	LF	16.00		
0340	237-A002	Wattles, 20"	1,000.000	LF	8.50		
0350	246-B001	Rockbags	100.000	EA	11.00		
0360	249-A001	Riprap for Erosion Control	400.000	TON	70.00		
0370	304-B006	Granular Material, Class 6, Group C	7,650.000	TON	22.50		
0380	403-A003	12.5-mm, ST, Asphalt Pavement	1,950.000	TON	108.00		
0390	403-A006	19-mm, ST, Asphalt Pavement	2,800.000	TON	95.00		
0400	403-A013	9.5-mm, HT, Asphalt Pavement	1,200.000	TON	108.00		
0410	403-A015	9.5-mm, ST, Asphalt Pavement	1,860.000	TON	110.00		
0420	406-D001	Fine Milling of Bituminous Pavement, All Depths	23,178.000	SY	2.30		
0430	407-A001	Asphalt for Tack Coat	5,284.000	GAL	2.30		
0440	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	514.000	LF	5.75		
0450	423-A001	Rumble Strips, Ground In	3.000	MI	300.00		
0460	501-K001	Transverse Grooving	48.000	SY	2.50		
0470	502-A001	Reinforced Cement Concrete Bridge End Pavement	329.000	SY	240.00		
0480	503-C010	Saw Cut, Full Depth	2,715.000	LF	15.50		
0490	601-B001	Class "B" Structural Concrete, Minor Structures	10.000	CY	1,560.00		
0500	602-A001	Reinforcing Steel	317.000	LBS	2.15		
0510	603-A012	24" Steel Pipe, Jacked or Bored, Wall Thickness 0.375"	192.000	LF	375.00		
0520	603-ALT003	18" Type A Alternate Pipe	16.000	LF	35.00		

Bridge Replacements on SR 198 near Columbia, (Bridge Nos. 119.0 & 119.3), known as Federal Aid Project No. CHBP-0046-01(013) / 102471301 in Marion County.					T. L. Wallace Construction, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$9,398,510.53					\$8,871,455.76		
Ref#	Item	Item Description	Item Qty	Units	1		
0530	603-CA026	24" Reinforced Concrete Pipe, Class III	520.000	LF	52.00		
0540	603-CB004	24" Reinforced Concrete End Section	9.000	EA	800.00		
0550	603-CE002	22" x 13" Concrete Arch Pipe, Class A III	40.000	LF	49.00		
0560	603-CF002	22" x 13" Concrete Arch Pipe End Section	2.000	EA	720.00		
0570	604-B001	Gratings	627.000	LBS	3.10		
0580	605-AA001	Geotextile for Subsurface Drainage, Type III	115.000	SY	3.15		
0590	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	207.000	LF	15.00		
0600	605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	10.000	LF	15.00		
0610	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	8.000	CY	100.00		
0620	606-B001	Guard Rail, Class A, Type 1	300.000	LF	22.00		
0630	606-D022	Guard Rail, Bridge End Section, Type 1	8.000	EA	2,900.00		
0640	606-E005	Guard Rail, Terminal End Section, Flared	6.000	EA	3,200.00		
0650	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	1,447.000	LF	25.00		
0660	615-A024	Concrete Bridge End Barrier, 37.5"	96.000	LF	55.00		
0670	616-A001	Concrete Median and/or Island Pavement, 10-inch	28.000	SY	130.00		
0680	616-A004	Concrete Median and/or Island Pavement, 4-inch	791.000	SY	63.00		
0690	617-A001	Right-of-Way Marker	4.000	EA	300.00		
0700	618-A001	Maintenance of Traffic	1.000	LS	80,000.00		
0710	619-A1003	Temporary Traffic Stripe, Continuous White, Paint	25,408.000	LF	0.28		
0720	619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	24,838.000	LF	0.28		
0730	619-A3004	Temporary Traffic Stripe, Skip White, Paint	9,680.000	LF	0.28		
0740	619-A5002	Temporary Traffic Stripe, Detail, Paint	9,176.000	LF	0.28		
0750	619-A6002	Temporary Traffic Stripe, Legend	1,020.000	LF	0.55		
0760	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	32.000	SF	9.15		
0770	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	677.000	SF	9.15		
0780	619-G4001	Barricades, Type III, Double Faced	114.000	LF	21.00		

Bridge Replacements on SR 198 near Columbia, (Bridge Nos. 119.0 & 119.3), known as Federal Aid Project No. CHBP-0046-01(013) / 102471301 in Marion County.					T. L. Wallace Construction, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$9,398,510.53					\$8,871,455.76		
Ref#	Item	Item Description	Item Qty	Units	1		
0790	619-G4007	Barricades, Type III, Single Faced, Permanent, Red/White	24.000	LF	44.00		
0800	619-G5001	Free Standing Plastic Drums	100.000	EA	55.00		
0810	619-G7001	Warning Lights, Type "B"	16.000	EA	229.00		
0820	620-A001	Mobilization	1.000	LS	734,000.00		
0830	626-A002	6" Thermoplastic Double Drop Traffic Stripe, Skip White	4,840.000	LF	1.10		
0840	626-B001	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	779.000	LF	1.10		
0850	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	9,834.000	LF	1.10		
0860	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	6,363.000	LF	1.10		
0870	626-F002	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	3,965.000	LF	1.10		
0880	626-G004	Thermoplastic Double Drop Detail Stripe, White	3,579.000	LF	2.20		
0890	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	1,009.000	LF	2.20		
0900	626-H001	Thermoplastic Double Drop Legend, White	323.000	SF	11.00		
0910	626-H002	Thermoplastic Double Drop Legend, White	510.000	LF	2.20		
0920	627-J001	Two-Way Clear Reflective High Performance Raised Markers	15.000	EA	10.75		
0930	627-K001	Red-Clear Reflective High Performance Raised Markers	153.000	EA	10.75		
0940	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	97.000	EA	10.75		
0950	629-A003	Vehicular Impact Attenuator, 55 MPH	2.000	EA	42,500.00		
0960	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	168.000	SF	20.00		
0970	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	110.000	SF	22.00		
0980	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	77.000	SF	24.00		
0990	630-C002	Steel U-Section Posts, 2.0 lb/ft	21.000	LF	10.00		
1000	630-C003	Steel U-Section Posts, 3.0 lb/ft	567.000	LF	11.50		
1010	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	120.000	LBS	2.95		
1020	630-F003	Delineators, Flexible Post Mounted, Crossover, Type II	4.000	EA	72.00		
1030	630-F006	Delineators, Guard Rail, White	33.000	EA	20.00		
1040	630-K002	Welded & Seamless Steel Pipe Posts, 3"	45.000	LF	50.00		

Bridge Replacements on SR 198 near Columbia, (Bridge Nos. 119.0 & 119.3), known as Federal Aid Project No. CHBP-0046-01(013) / 102471301 in Marion County.					T. L. Wallace Construction, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$9,398,510.53					\$8,871,455.76		
Ref#	Item	Item Description	Item Qty	Units	1		
1050	630-K003	Welded & Seamless Steel Pipe Posts, 4"	45.000	LF	60.00		
1060	699-A001	Roadway Construction Stakes	1.000	LS	115,000.00		
1070	815-F002	Sediment Control Stone	200.000	TON	70.00		
1080	907-619-E3001	Changeable Message Sign	3.000	EA	17,000.00		
1090	907-630-O006	Remove and Reset Signs, Ground Mounted	2.000	EA	825.00		
1100	907-906001	Trainees	1,040.000	HRS	5.00		
1110	304-F001	3/4" and Down Crushed Stone Base	7,200.000	TON			
1120	304-F002	Size 610 Crushed Stone Base	7,200.000	TON	64.05		
1130	304-F003	Size 825B Crushed Stone Base	7,200.000	TON			
1140	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	94.000	CY	76.50		
1150	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	94.000	CY			
1160	907-624-B002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White	2,090.000	LF			
1170	907-624-D002	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow	2,090.000	LF			
1180	628-H001	6" High Performance Cold Plastic Traffic Stripe, Continuous White	2,090.000	LF	7.75		
1190	628-J001	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow	2,090.000	LF	7.75		
1200	501-K001	Transverse Grooving	3,731.000	SY	2.50		
1210	803-P001	24" Steel Pipe Piling, Wall Thickness 0.500"	6,535.000	LF	116.55		
1220	804-C188	80' Prestressed Concrete Beam, Type FIB-36	1,435.000	LF	221.00		
1230	804-C199	70' Prestressed Concrete Beam, Type FIB-36	418.000	LF	220.00		
1240	804-C200	75' Prestressed Concrete Beam, Type FIB-36	2,688.000	LF	220.00		
1250	804-C201	95' Prestressed Concrete Beam, Type FIB-36	1,704.000	LF	220.00		
1260	805-A001	Reinforcement	314,047.000	LBS	1.25		
1270	805-C001	Reinforcement, Corrosion Resistant	13,340.000	LBS	2.20		
1280	813-A004	Concrete Railing, 36"	2,108.000	LF	55.00		
1290	815-A007	Loose Riprap, Size 300	8,011.000	TON	71.50		
1300	815-E001	Geotextile under Riprap	5,064.000	SY	1.85		

Bridge Replacements on SR 198 near Columbia, (Bridge Nos. 119.0 & 119.3), known as Federal Aid Project No. CHBP-0046-01(013) / 102471301 in Marion County.					T. L. Wallace Construction, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$9,398,510.53					\$8,871,455.76		
Ref#	Item	Item Description	Item Qty	Units	1		
1310	907-803-B001	Conventional Static Pile Load Test	2.000	EA	5,000.00		
1320	907-803-I004	PDA Test Pile, Steel Pipe Pile	7.000	EA	19,000.00		
1330	907-803-J001	Pile Restrike	4.000	EA	1,100.00		
1340	907-804-A001	Bridge Concrete, Class BDX	1,143.000	CY	950.00		
1350	907-804-A002	Bridge Concrete, Class AA	311.000	CY	1,025.00		

Letting Date: 5/27/2020

Call Number: 02

Page 6 of 6