

**Call 01 Bridge Repairs on SR 21 over North Canal and Tuscolameta Creek (Bridge Nos. 13.2 & 13.7), known as Federal Aid Project No. STP-0045-01(016) / 108423301 in Scott County.**

Q1. Silt fence and any erosion control items aren't included in the pay items. Are they intentionally missed out or is MDOT planning to include it after the project is awarded?

A1. No, any additional erosion control necessary to prevent sediment runoff into the waterway shall be absorbed in other items bid. It shall be the Contractor's responsibility to establish vegetation in disturbed areas as stated under "Disturbance Notes" on Working Number 1 of 7, Sheet Number 8002.

Q2. Will fiberglass reinforced stay-in-place encasement forms be allowed?

A2. No.

Q3. **1.)** Bridge 12.2: Bents 2 & 3 steel piles are in the creek with about 2' of water. Will a sheet pile coffer cell be required to perform the painting and encasement in the dry? **2.)** Bridge 12.7: Will Bents 4 & 5 piles be required to be excavated 3' below the creek bottom for the painting and the encasements?

A3. **1.)** Yes. **2.)** No, only 3' below ground at the location of the pile.