

Call 08 Mill & Overlay approximately 11 miles of SR 21 from Dixon to SR 15, known as State Project No. SP-5021-50(020) / 108569301 in Neshoba County.

Q1. Will the existing thermoplastic stripe need to be removed prior to placing the scrub seal?

A1. Yes, as stated in the Scope of Work, as well as Special Provision 907-414-1, all existing thermoplastic stripe shall be removed prior to the scrub seal operations.