BRIDGE STRUCTURES REQ'D.

NONE

BOX BRIDGES REQ'D. NONE

STATE OF MISSISSIPPI

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE OF PROPOSED STATE HIGHWAY FEDERAL AID PROJECT NO. ER-0006-03(043)

> MM#115.9 & 116 WESTBOUND MM#114.5 EASTBOUND MM#115 EASTBOUND


> > 1 IN. = 100 FT. **LAYOUT** 1 IN. = 3000 FT.

FMS CON:108056/301000

108057/301000

108058/301000

MM#115 EASTBOUND MM#114.5 EASTBOUND MM#115.9 & 116 WESTBOUND



EQUATIONS

NONE

EXCEPTIONS

NONE


COUNTY LINE

CONVENTIONAL SYMBOLS

TOWN CORPORATION LINE ... SECTION LINE EXISTING ROAD OR TRAVELED WAY PROPOSED ROAD OR TRAVELED WAY RAILROAD.. SURVEY LINE BRIDGES

LENGTH DATA

LENGTH OF ROADWAY LENGTH OF BRIDGES LENGTH OF PROJECT (NET) LENGTH OF EXCEPTIONS LENGTH OF PROJECT (GROSS)



ER-0006-03(043)

ITAWAMBA COUNTY

PROJECT NUMBER

ER-0006-03(043)

STATE MAP INDICATES APPROXIMATE LOCATION OF PROJECT. LAT. 34.219054 LONG. -88.224455 (APPROX. MIDDLE OF PROJECT)

> PERMITS ACQUIRED BY MDOT NATIONWIDE (OTHER)* **GENERAL*** INDIVIDUAL (404)* STORMWATER PERMIT

> > REQUIRED, SCNOI TO BE SUBMITTED BY CONTRACTOR (1 TO 4.99 ACRES)

NO STORMWATER PERMIT REQUIRED (<1 ACRE)


DESIGN CONTROL

STATE	PROJECT NO.
MISS.	ER-0006-03(043)


SH. NO.

DESCRIPTION OF SHEET	WKG. NO.	SH. NO.
TITLE SHEET (1)	TS-1	1
DETAILED INDEX & GENERAL NOTES (2)		
DETAILED INDEX GENERAL NOTES	DI-1 GN-1	2 3
CENEIVAL NOTES		
SUMMARY OF QUANTITIES (5)	000.4	
SUMMARY OF QUANTITIES - PROJ. NO. ER-0006-03(043)	SQS-1 SQS-2	5
SUMMARY OF QUANTITIES - PROJ. NO. ER-0006-03(042)	SQS-3	6
SUMMARY OF QUANTITIES - PROJ. NO. ER-0006-03(041)	SQS-4	7
SUMMARY OF QUANTITIES - PROJECT TOTALS SUMMARY OF QUANTITIES - PROJECT TOTALS	SQS-5	8
ESTIMATED QUANTITIES (2)		
ESTIMATED QUANTITIES - SUMMARY OF TRAFFIC CONTROL	EQ-1	9
ESTIMATED QUANTITIES - SUMMARY OF TRAFFIC CONTROL ESTIMATED QUANTITIES - TRAFFIC CONTROL SIGNS	EQ-1	10
PLAN PROFILE SHEETS (32)		
CONSTRUCTION SEQUENCE - MM 114.5 SLIDE SITE	WK-1	11
STABILIZATION PILE SCHEDULE - MM 114.5 SLIDE SITE	WK-2	12
EXISTING CONDITIONS - MM 114.5 & MM 115 SLIDE SITES STABILIZATION PILE PLAN - MM 114.5 SLIDE SITE (SHEET 1 OF 2)	WK-3 WK-4	13 14
STABILIZATION FILE FLAN - MM 114.5 SLIDE SITE (SHEET 2 F 2)	WK-5	15
PROPOSED CONDITIONS (SECTION A-A) - MM 114.5 SLIDE SITE	WK-6	16
PROPOSED CONDITIONS (SECTION B-B) - MM 114.5 SLIDE SITE	WK-7	17
DETAIL - MM 114.5 SLIDE SITE (SHEET 1 OF 2)	WK-8	18
DETAIL - MM 114.5 SLIDE SITE (SHEET 2 OF 2) EXISTING CONDITIONS (SECTION A-A) - MM 114.5 SLIDE SITE	WK-9 WK-10	19
EXISTING CONDITIONS (SECTION A-A) - MM 114.5 SLIDE SITE	WK-10	21
BORING LOGS - MM 114.5 SLIDE SITE	WK-12	22
CONSTRUCTION SEQUENCE - MM 115 SLIDE SITE	WK-13	23
FINAL GRADING - MM 115 SLIDE SITE	WK-14	24
PROPOSED CONDITIONS (SECTION C-C) - MM 115 SLIDE SITE	WK-15	25
DETAIL - MM 115 SLIDE SITE	WK-16	26
DETAIL - MM 115 SLIDE SITE EXISTING CONDITIONS (SECTION C-C) - MM 115 SLIDE SITE	WK-17	27
BORING LOGS - MM 115 SLIDE SITE	WK-18 WK-19	29
CONSTRUCTION SEQUENCE - MM 116 SLIDE SITE	WK-20	30
EXISTING CONDITIONS - MM 116 SLIDE SITES	WK-21	31
FINAL GRADING - MM 116 SLIDE SITE	WK-22	32
PROPOSED CONDITIONS (SECTION D-D) - MM 116 SLIDE SITE PROPOSED CONDITIONS (SECTION E-E) - MM 116 SLIDE SITE	WK-23 WK-24	33
DETAIL - MM 116 SLIDE SITE	WK-25	35
DETAIL - MM 116 SLIDE SITE	WK-26	36
EXISTING CONDITIONS (SECTION D-D) - MM 116 SLIDE SITE	WK-27	37
EXISTING CONDITIONS (SECTION E-E) - MM 116 SLIDE SITE BORING LOGS - MM 116 SLIDE SITE	WK-28 WK-29	38 39
	VVI-23	J J J
SPECIAL DESIGN SHEETS (3)		10
CONSTRUCTION SIGNING VEGETATION SCHEDULE	CS-1 VS-1	40
EDGE DRAIN DETAIL	EDD-1	41
CROSS SECTIONS (11)		
		40.00
MAINLIN I-22 (EASTBOUND) MM 114.5 & MM 115 MAINLIN I-22 (WESTBOUND) MM 116		43 - 49 50- 53
INIMITALITY IF22 (VVESTECUIND) IVIIVI TTO		30- 33

STANDARD DRAWINGS - ROADWAY SHEETS (21) AUG. 1, 2017 VERSION		
TYPICAL TEMPORARY EROSION CONTROL / SEDIMENT CONTROL APPLICATIONS	ECD-1	6101
DETAILS OF SEDIMENT BARRIER APPLICATIONS	ECD-2	6102
DETAILS OF SILT FENCE INSTALLATION	ECD-3	6103
DITCH CHECK STRUCTURES, TYPICAL APPLICATIONS AND DETAILS	ECD-4	6104
TEMPORARY EROSION, SEDIMENT, AND WATER POLLUTION CONTROL MEASURES	ECD-5	6105
(SILT FENCE AND HAY BALE DITCH CHECKS)	ECD-6	6106
DETAILS OF EROSION CONTROL WATTLE DITCH CHECKS	ECD-7	6107
DETAILS OF EROSION CONTROL SILT DIKE DITCH CHECK	ECD-8	6108
ROCK DITCH CHECK	ECD-9	6109
ROCK FILTER DAM	ECD-10	6110
ROCK DITCH CHECK WITH SUMP EXCAVATION	ECD-11	6111
STADILIZIED CONSTRUCTION ENTRANCE	ECD-16	6116
STABILIZIED CONSTRUCTION ENTRANCE	EGD-10	0110
DETAILS OF EROSION CONTROL SANDBAG DITCH CHECK	ECD-21	6121
SEDIMENT RETENTION BARRIER	ECD-22	6122
DETAILS OF TYPICAL DITCH TREATMENTS	DT-1	6123
		0.20
TRAFFIC CONTROL PLAN FOR POSTED SPEED LIMIT OF 65 OR 70 MPH (INTERSTATE AND OTHER		
4-LANE DIVIDED HIGHWAYS) (MEDIAN LANE OR OUTSIDE LANE CLOSURE) (EXTENDED PERIOD)	TCP-4	6354
TRAFFIC CONTROL PLAN FOR POSTED SPEED LIMIT OF 65 OR 70 MPH (INTERSTATE AND OTHER		
4-LANE DIVIDED HIGHWAYS) (MEDIAN LANE OR OUTSIDE LANE CLOSURE) (WORK DAY ONLY)	TCP-5	6355
HIGHWAY SIGN AND BARRICADE DETAILS FOR CONSTRUCTION PROJECTS	TCP-8	6358
LOCATION OF R16-3 SIGNS (SPEEDING FILES DOUBLED)	TCP-15	6364
TRAFFIC CONTROL DETAILS DRUM PLACEMENT AND SHOULDER CLOSURE	TCP-16	6365
TYPICAL GRADING TRANSITION BETWEEN CUTS & FILLS	GT-1	6404



TOTAL SHEETS (77)



PROJ. NO.: ER-0006-03(043) COUNTY: ITAWAMBA

ILE NAME: DI.DGN

DI-1
SHEET NUMBER
2

WORKING NUMBER

- 1 the location and spacing of signs, shown on the traffic control plans, are approximate and may be adjusted AS NECESSARY TO FIT FIELD CONDITIONS.
- 2) ALL TRAFFIC CONTROL DEVICES ON THIS PROJECT SHALL COMPLY WITH PART VI OF THE MUTCD (LATEST EDITION).
- 3 ALL PLASTIC DRUMS SHALL HAVE A BALLASTING COLLAR MADE FROM RECYCLED TRUCK TIRES OR OTHER SUITABLE MATERIAL.
- 4 a soil profile has been prepared for this project using samples taken from holes at the locations indicated IN THE TEST REPORTS. THIS SOIL PROFILE IS ON FILE IN THE DISTRICT AND CENTRAL CONSTRUCTION OFFICES AND IS AVAILABLE FOR EXAMINATION. THE DEPARTMENT DOES NOT GUARANTEE THAT THE MATERIALS AS SHOWN IN THE REPORTS ARE NECESSARILY TO BE FOUND OUTSIDE THE TEST HOLES.
- (5) 25% SHRINKAGE FACTOR USED IN THE EARTHWORK CALCULATIONS IS FOR DESIGN ESTIMATING PURPOSES ONLY.
- 6 THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING EXISTING STRUCTURES SUCH AS, BUT NOT LIMITED TO, PIPES, INLETS, APRONS, AND BRIDGES FROM DAMAGE WHICH MIGHT OCCUR DURING CONSTRUCTION. THE CONTRACTOR SHALL REPLACE OR REPAIR, AS DIRECTED BY THE ENGINEER, ANY STRUCTURES DAMAGED DURING THE LIFE OF THE CONTRACT. NO PAYMENT WILL BE MADE FOR REPLACEMENT OR REPAIR OF DAMAGED ITEMS.
- \bigcirc all pipe joints are to be wrapped in 24-inch wide type v geotextile fabric. All pickup holes shall be plugged AND COVERED WITH TYPE V GEOTEXTILE FABRIC, THE COST OF WHICH SHALL BE ABSORBED IN OTHER BID ITEMS.
- 8 VOIDS CREATED BY THE REMOVAL OF, BUT NOT LIMITED TO, POSTS, CONCRETE ANCHORS, AND FOOTINGS SHALL BE BACKFILLED AND TAMPED IN ACCORDANCE WITH SECTION 203 OF THE MISSISSIPPI STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION. THE COST OF WHICH WILL BE ABSORBED IN OTHER ITEMS BID.
- JTILITIES ON THE DRAWINGS ARE SHOWN IN THEIR ORIGINAL LOCATION BASED UPON THE BEST INFORMATION AVAILABLE TO THE ENGINEER. UTILITIES THAT WERE FOUND TO BE IN CONFLICT WITH CONSTRUCTION HAVE BEEN RELOCATED. PERMITS ARE ON FILE WITH THE DEPARTMENT SHOWING THE APPROXIMATE LOCATION OF UTILITIES RELOCATED WITHIN THE RIGHT-OF-WAY. THE ENGINEER CAN NOT AND DOES NOT WARRANT THAT THIS INFORMATION IS COMPLETE OR ACCURATE. THE CONTRACTOR MUST COORDINATE DIRECTLY WITH THE INVOLVED UTILITY OWNERS TO HAVE UNDERGROUND UTILITY LINES FIELD LOCATED IN ADVANCE OF CONSTRUCTION.
- 10 work on structures for this project requires excavation in the immediate vicinity of traffic and adjacent PROPERTIES. THEREFORE, THE RISK OF A FAILURE OCCURRING DURING EXCAVATION REQUIRES THAT EXTREME CAUTION BE EXERCISED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PLACING WHAT BRACING. SHORING. OR GROUND SUPPORT SYSTEM THAT IS DEEMED NECESSARY TO PREVENT A FAILURE AND PROTECT THE PERSONS WORKING NEAR THE EXCAVATION, THE PUBLIC THAT MAY BE ABOVE THE EXCAVATION OR ANY STRUCTURES ADJACENT TO THE EXCAVATION. ALL COSTS FOR DESIGNING, DRAWING, AND CONSTRUCTING THE FACILITY SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.
- 11) wire fence backing will be required for all silt fence. (see wk. no. ecd-3)
- 12) storage of flammable materials will not be allowed under any bridge structures.
- 13 FLUORESCENT ORANGE SHEETING SHALL BE USED ON ALL CONSTRUCTION AND TRAFFIC CONTROL SIGNS EXCEPT FOR THOSE DESIGNATED ON THE PLANS TO BE BLACK LEGEND AND BORDER ON WHITE BACKGROUND.
- (14) SMALL AMOUNTS OF EXCAVATION MAY BE NECESSARY AT SOME OF THE SITES. THIS MATERIAL MAY BE USED AS E.S.F.E. MATERIAL AND WILL BE PAID FOR BORROW. NO E.S.F.E. MATERIAL SHALL BE REMOVED FROM THE PROJECT WITHOUT THE APPROVAL OF THE ENGINEER.
- (15) ROADWAY SIGNS THAT ARE IN CONFLICT WITH CONSTRUCTION OF THIS PROJECT SHALL BE REMOVED AND RELOCATED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER, THE COST OF WHICH SHALL BE ABSORBED IN OTHER ITEMS BID.
- 16) THE EROSION CONTROL DEVICES REFERENCED IN THESE PLANS ARE A MINIMUM REQUIREMENT. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT SILT DOES NOT LEAVE THE RIGHT OF WAY OR CONTAMINATE WATERS OF THE U.S. DURING CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT AN EROSION CONTROL PLAN PRIOR TO COMMENCEMENT OF WORK AND MAINTAIN THE PLAN DURING CONSTRUCTION. ANY ADDITIONAL SILT BASINS NOT SHOWN IN THE PLANS SHALL BE INCLUDED IN THE CONTRACTOR'S EROSION CONTROL PLAN PRIOR TO SUBMITTING FOR APPROVAL.
- $rac{1}{2}$ prior to earthwork operations, the existing top 4" topsoil is to be stripped and stockpiled. After the GRADING OPERATIONS ARE COMPLETED, SAID TOPSOIL SHALL BE PLACED ON ALL AREAS THAT ARE NOT TO BE PAVED OR OTHERWISE PROTECTED. IN ACCORDANCE WITH SECTION 211 OF THE SPECIFICATIONS. OR THE VEGETATION SCHEDULE (SEE WK.SH.VS-1). EXISTING TOPSOIL AND ALL COSTS ASSOCIATED WITH STRIPPING, HAULING, STOCKPILING, AND PLACEMENT OF THE EXISTING TOPSOIL IS TO BE ABSORBED IN OTHER EARTHWORK ITEMS.
- (18) ALL ITEMS OF WORK ASSOCIATED WITH THE INSTALLATION OF A CONSTRUCTION ENTRANCE SHALL BE ABSORBED IN OTHER ITEMS OF WORK.
- 19 if colors are used on plan/profile sheets, they are intended to visually ease the location of elements for USERS OF THESE DRAWINGS. ALTHOUGH THE INTENT IS TO CATEGORIZE EVERYTHING AS EITHER EXISTING OR PROPOSED, IT IS THE END USERS RESPONSIBILITY TO ENSURE ALL ELEMENTS ARE INTERPRETED CORRECTLY REGARDLESS OF COLOR.
- 20all addenda to these plans will be posted to www.mdot.ms.gov under the proposal addenda column. BIDDERS ARE ADVISED THAT HARD COPIES OF ANY ADDENDA FOR THIS PROJECT WILL NOT BE MAILED. IT IS THE BIDDER'S RESPONSIBILITY TO CHECK AND SEE IF ANY ADDENDA HAVE BEEN POSTED FOR THIS PROJECT.

GENERAL NOTES (CONT.)

PROJECT NO. STATE ER-0006-03(043) MISS.


2) VEGETATIVE MATERIAL WILL BE REMOVED PRIOR TO PLACEMENT OF GRANULAR MATERIAL. THE COST OF WHICH SHALL BE ABSORBED IN OTHER ITEMS BID.

22 THE CONTRACTOR SHALL REPAIR ANY DAMAMGE TO THE SURFACE TREATED SHOULDERS THAT MIGHT OCCURE DURING CONSTRUCTION. ANY REPAIR TO SHOULDER WILL BE IN ACCORDANCE WITH SECTION 410 OF THE MISSISSIPPI STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION. NO PAYMENT WILL BE MADE FOR REPAIR OF DAMAGED SHOULDER.

(23) THE CONTRACTOR SHALL COVER ANY TEMPORARY TRAFFIC CONTROL SIGNGS SHOWN IN THE TRAFFIC CONTROL PLAN THAT DO NOT APPLY TO THE CURRENT PHASE.

THE RETROREFLECTIVE SIGN SHEETING ON RIGID .TEMPORARY TRAFFIC CONTROL (ORANGE)SIGNS SHALL BE MINIMUM IX.

25 LIST OF PUBLIC UTILITIES A. TENNESSEE VALLEY AUTHORITY




	SUMMARY OF QUANTITIES (SHEET 1)	<u> </u>		
PAY ITEM NO.	PAY ITEM	UNIT	ITAWAMBA: 108056	_
			Prelim	Final
	EARTHWORK			
201-B001	Clearing and Grubbing	ACRE	2	
202-B116	Removal of Debris, LVM	CY	50	1
203-EX021	Borrow Excavation, AH, FME, Class B9-6	CY	5,630	
203-G002	Excess Excavation, LVM, AH	CY	910	
206-A001	Structure Excavation	CY	40	
	ROADSIDE DEVELOPMENT			
211-B001	Topsoil for Slope Treatment, Contractor Furnished	CY	538	
213-C001	Superphosphate	TON	1	
216-A001	Solid Sodding	SY	2,400	
219-A001	Watering	KGAL	48	2
220-A001	Insect Pest Control	ACRE	1	
221-A001	Concrete Paved Ditch	CY	1	
223-A001	Mowing	ACRE	2	
225-A001	Grassing	ACRE	1	
225-B001	Agricultural Limestone	TON	2	
225-C001	Mulch, Vegetative Mulch	TON	2	
226-A001	Temporary Grassing	ACRE	1	
907-228-A002	Erosion Control Blanket, Type II	SY	2,400	
234-A001	Temporary Silt Fence	LF	535	
237-A002	Wattles, 20"	LF	505	
246-B001	Rockbags	EA	15	
249-A001	Riprap for Erosion Control	TON	10	
	DRAINAGE			
605-AA003	Geotextile for Subsurface Drainage, Type V, Non-Woven	SY	320	
605-O004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	LF	480	
605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	LF	10	
605-X002	Filter Material for Filter Beds, Type A	CY	40	
605-X003	Filter Material for Filter Beds, Type B	CY	670	
605-Z002	Underdrain Appurtenances, Elbows, Couplings, etc.	LS	1	
605-Z003	Underdrain Appurtenances, Sign	EA	1	
605-Z006	Underdrain Appurtenances, Small Animal Guard	EA	1	
	INCIDENTAL CONSTRUCTION			
618-A001	Maintenance of Traffic	LS	1	
619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	SF	16	
619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	SF	228	
619-G4005	Barricades, Type III, Single Faced	LF	24	
620-A001	Mobilization	LS	1	
699-A001	Roadway Construction Stakes	LS	1	

STATE PROJECT NO.

MISS ER-0006-03(043)/ER-0006-03(043)/ER-0006-03
(043)


- 1 REMOVAL OF DEBRIS INCLUDES THE REMOVAL OF ACCUMULATED DEBRIS AND SEDIMENT FROM THE PAVED DITCH.
- ② ESTIMATED 20 GALLONS PER SQ. YD. OF SOLID SOD.



	SUMMARY OF QUANTITIES (SHEET 2)				
PAY ITEM NO.	PAY ITEM	UNIT	ITAWAMBA : 108	3057-301000	
PATTILITINO.		OIVII	Prelim	Final	
	EARTHWORK				-
201-B001	Clearing and Grubbing	ACRE	2		
202-B116	Removal of Debris, LVM	CY	100		2
203-EX041	Borrow Excavation, AH, LVM, Class B9-6	CY	180		Ĭ
203-G002	Excess Excavation, LVM, AH	CY	180		
203-I002	Site Grading	SY	6,250		
211-B001	Topsoil for Slope Treatment, Contractor Furnished	CY	1,076		_
	ROADSIDE DEVELOPMENT				-
213-C001	Superphosphate	TON	1		
216-A001	Solid Sodding	SY	4,500		
219-A001	Watering	KGAL	90		(3
220-A001	Insect Pest Control	ACRE	2		
221-A001	Concrete Paved Ditch	CY	2		
223-A001	Mowing	ACRE	4		
225-A001	Grassing	ACRE	2		
225-B001	Agricultural Limestone	TON	4		
225-C001	Mulch, Vegetative Mulch	TON	4		
226-A001	Temporary Grassing	ACRE	2		
907-228-A002	Erosion Control Blanket, Type II	SY	4,500		
234-A001	Temporary Silt Fence	LF	690		
237-A002	Wattles, 20"	LF	715		
246-B001	Rockbags	EA	8		
249-A001	Riprap for Erosion Control	TON	10		_
	INCIDENTAL CONSTRUCTION				<u> </u> -
618-A001	Maintenance of Traffic	LS	1		
619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	SF	16		
619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	SF	228		
619-G4005	Barricades, Type III, Single Faced	LF	24		
620-A001	Mobilization	LS	1		
699-A001	Roadway Construction Stakes	LS	1		
803-D006	HP 14 x 73 Steel Piling	LF	6,105		(1

STATE PROJECT NO.		PROJECT NO.
	MISS	ER-0006-03(043)/ER-0006-03(043)/ER-0006-03
	1,1122	(043)


- 1 ALL HP 14X73 PILES SHALL BE EQUIPPED WITH COMPATIBLE BITE POINT OR PILE SHOE SHALL ABSORBED PER 803.04.3 AND 803.05.4.
- 2 REMOVAL OF DEBRIS INCLUDES THE REMOVAL OF ACCUMULATED DEBRIS AND SEDIMENT FROM THE PAVED DITCH.
- ③ ESTIMATED 20 GALLONS PER SQ. YD. OF SOLID SOD.



	SUMMARY OF QUANTITIES (SHEET		ITAWAMBA: 108	058-301000
PAY ITEM NO.	PAY ITEM	UNIT	Prelim	Final
	EARTHWORK			
201-B001	Clearing and Grubbing	ACRE	1	
202-B116	Removal of Debris, LVM	CY	50	
203-EX041	Borrow Excavation, AH, LVM, Class B9-6	CY	500	
203-G002	Excess Excavation, LVM, AH	CY	500	
203-I002	Site Grading	SY	520	
206-A001	Structure Excavation	CY	65	
	ROADSIDE DEVELOPMENT			
213-C001	Superphosphate	TON	1	
216-A001	Solid Sodding	SY	1,200	
219-A001	Watering	KGAL	24	(
220-A001	Insect Pest Control	ACRE	1	
221-A001	Concrete Paved Ditch	CY	1	
223-A001	Mowing	ACRE	2	
225-A001	Grassing	ACRE	1	
225-B001	Agricultural Limestone	TON	2	
225-C001	Mulch, Vegetative Mulch	TON	2	
226-A001	Temporary Grassing	ACRE	1	
907-228-A002	Erosion Control Blanket, Type II	SY	1,200	
234-A001	Temporary Silt Fence	LF	215	
246-B001	Rockbags	EA	2	
249-A001	Riprap for Erosion Control	TON	10	
	DRAINAGE			
605-AA003	Geotextile for Subsurface Drainage, Type V, Non-Woven	SY	160	
605-0004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	LF	180	
605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	LF	25	
605-X002	Filter Material for Filter Beds, Type A	CY	15	
605-X003	Filter Material for Filter Beds, Type B	CY	535	
605-Z002	Underdrain Appurtenances, Elbows, Couplings, etc.	LS	1	
605-Z003	Underdrain Appurtenances, Sign	EA	2	
605-Z006	Underdrain Appurtenances, Small Animal Guard	EA	2	
	INCIDENTAL CONSTRUCTION			
618-A001	Maintenance of Traffic	LS	1	
907-619-E3001	Changeable Message Sign	EA	1	(
620-A001	Mobilization	LS	1	
699-A001	Roadway Construction Stakes	LS	1	
815-A002	Loose Riprap, Size 100	TON	740	
815-E001	Geotextile under Riprap	SY	1,500	(

STATE		PROJECT NO.
	MISS	ER-0006-03(043)/ER-0006-03(043)/ER-0006-03
	1,1122	(043)


- 1 MAY BE USED AT ALL WORK SITES.
- ② ESTIMATED 20 GALLONS PER SQ. YD. OF SOLID SOD.
- 3 QUANTITY TO BE PLACED UNDER SIZE 100 RIPRAP.



	SUMMARY OF QUANTITIES (SHEET 4)	1 1		
PAY ITEM NO.	PAY ITEM	UNIT	Total Amo	
			Prelim	Final
	EARTHWORK			
201-B001	Clearing and Grubbing	ACRE	5	
202-B116	Removal of Debris, LVM	CY	200	(
203-EX021	Borrow Excavation, AH, FME, Class B9-6	CY	5,630	
203-EX041	Borrow Excavation, AH, LVM, Class B9-6	CY	680	
203-G002	Excess Excavation, LVM, AH	CY	1,590	
203-I002	Site Grading	SY	6,770	
206-A001	Structure Excavation	CY	105	
211-B001	Topsoil for Slope Treatment, Contractor Furnished	CY	1,076	
	ROADSIDE DEVELOPMENT			
211-B001	Topsoil for Slope Treatment, Contractor Furnished	CY	538	
213-C001	Superphosphate	TON	3	
216-A001	Solid Sodding	SY	8,100	
219-A001	Watering	KGAL	162	(
220-A001	Insect Pest Control	ACRE	4	
221-A001	Concrete Paved Ditch	CY	4	
223-A001	Mowing	ACRE	8	
225-A001	Grassing	ACRE	4	
225-B001	Agricultural Limestone	TON	8	
225-C001	Mulch, Vegetative Mulch	TON	8	
226-A001	Temporary Grassing	ACRE	4	
907-228-A002	Erosion Control Blanket, Type II	SY	8,100	
234-A001	Temporary Silt Fence	LF	1,440	
237-A002	Wattles, 20"	LF	1,220	
246-B001	Rockbags	EA	25	
249-A001	Riprap for Erosion Control	TON	30	
	DRAINAGE			
605-AA003	Geotextile for Subsurface Drainage, Type V, Non-Woven	SY	480	
605-0004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	LF	660	
605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	LF	35	
605-X002	Filter Material for Filter Beds, Type A	CY	55	
605-X003	Filter Material for Filter Beds, Type B	CY	1,205	
605-Z002	Underdrain Appurtenances, Elbows, Couplings, etc.	LS	1	
605-Z003	Underdrain Appurtenances, Sign	EA	3	
605-Z006	Underdrain Appurtenances, Small Animal Guard	EA	3	
	INCIDENTAL CONSTRUCTION			
618-A001	Maintenance of Traffic	LS	1	
619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	SF	32	
619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	SF	456	
907-619-E3001	Changeable Message Sign	EA	1	(

STATE	PROJECT NO.
MISS	ER-0006-03(043)/ER-0006-03(043)/ER-0006-03
1,1122	(043)

- 1 REMOVAL OF DEBRIS INCLUDES THE REMOVAL OF ACCUMULATED DEBRIS AND SEDIMENT FROM THE PAVED DITCH.
- ② MAY BE USED AT ALL WORK SITES.
- ③ ESTIMATED 20 GALLONS PER SQ. YD. OF SOLID SOD.



	SUMMARY OF QUANTITIES (SHEET	5)		
DAY ITEM NO	DAY ITEM	LINIT	Total Amo	ount
PAY ITEM NO.	PAY ITEM	UNIT	Prelim	Final
619-G4005	Barricades, Type III, Single Faced	LF	48	
620-A001	Mobilization	LS	1	
699-A001	Roadway Construction Stakes	LS	1	
803-D006	HP 14 x 73 Steel Piling	LF	6,105	
815-A002	Loose Riprap, Size 100	TON	740	
815-E001	Geotextile under Riprap	SY	1,500	

STATE	PROJECT NO.
MISS	ER-0006-03(043)/ER-0006-03(043)/ER-0006-03
	(043)

- 1 ALL HP 14X73 PILES SHALL BE EQUIPPED WITH COMPATIBLE BITE POINT OR PILE SHOE SHALL ABSORBED PER 803.04.3 AND 803.05.4.
- ② QUANTITY TO BE PLACED UNDER SIZE 100 RIPRAP.

