

Slide Repairs on I-22 near Mile Marker 116 in the Fill Slope of the Westbound Lane, near Mile Marker 114.5 in the Backslope of the Eastbound Lane, and Mile Marker 115 in the Backslope of the Eastbound Lane, known as Federal Aid Project Nos. ER-0006-03(043) / 108056301, ER-0006-03(043) / 108057301 & ER-0006-03(043) / 108058301 in Itawamba County.					Century Construction Group, Inc.	Phillips Contracting Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,093,288.40					\$1,060,566.20	\$1,154,649.50	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	201-B001	Clearing and Grubbing	5.000	ACRE	5,000.00	7,000.00	
0020	202-B116	Removal of Debris, LVM	200.000	CY	60.40	30.00	
0030	203-EX021	Borrow Excavation, AH, FME, Class B9-6	5,630.000	CY	23.90	23.00	
0040	203-EX041	Borrow Excavation, AH, LVM, Class B9-6	680.000	CY	27.80	19.00	
0050	203-G002	Excess Excavation, LVM, AH	1,590.000	CY	14.00	15.00	
0060	203-I002	Site Grading	6,770.000	SY	0.99	5.00	
0070	206-A001	Structure Excavation	105.000	CY	19.80	25.00	
0080	211-B001	Topsoil for Slope Treatment, Contractor Furnished	1,614.000	CY	23.90	23.00	
0090	213-C001	Superphosphate	3.000	TON	1,176.00	1,200.00	
0100	216-A001	Solid Sodding	8,100.000	SY	4.70	5.00	
0110	219-A001	Watering	162.000	KGAL	20.00	20.00	
0120	220-A001	Insect Pest Control	4.000	ACRE	30.00	30.00	
0130	221-A001	Concrete Paved Ditch	4.000	CY	1,048.00	1,000.00	
0140	223-A001	Mowing	8.000	ACRE	50.00	50.00	
0150	225-A001	Grassing	4.000	ACRE	2,941.00	3,125.00	
0160	225-B001	Agricultural Limestone	8.000	TON	294.00	312.50	
0170	225-C001	Mulch, Vegetative Mulch	8.000	TON	294.00	312.50	
0180	226-A001	Temporary Grassing	4.000	ACRE	1,765.00	1,875.00	
0190	234-A001	Temporary Silt Fence	2,178.000	LF	5.90	6.25	
0194	234-D001	Inlet Siltation Guard	2.000	EA	882.00	1,000.00	
0200	237-A002	Wattles, 20"	1,220.000	LF	9.40	10.00	
0202	239-A001	Temporary Slope Drains	2,145.000	LF	15.30	15.00	
0210	246-B001	Rockbags	55.000	EA	17.60	50.00	
0220	249-A001	Riprap for Erosion Control	30.000	TON	73.60	55.00	
0230	605-AA003	Geotextile for Subsurface Drainage, Type V, Non-Woven	480.000	SY	3.80	5.00	
0240	605-O004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	660.000	LF	19.80	50.00	

Slide Repairs on I-22 near Mile Marker 116 in the Fill Slope of the Westbound Lane, near Mile Marker 114.5 in the Backslope of the Eastbound Lane, and Mile Marker 115 in the Backslope of the Eastbound Lane, known as Federal Aid Project Nos. ER-0006-03(043) / 108056301, ER-0006-03(043) / 108057301 & ER-0006-03(043) / 108058301 in Itawamba County.					Century Construction Group, Inc.	Phillips Contracting Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,093,288.40					\$1,060,566.20	\$1,154,649.50	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0250	605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	35.000	LF	39.10	50.00	
0260	605-X002	Filter Material for Filter Beds, Type A	55.000	CY	113.00	50.00	
0270	605-X003	Filter Material for Filter Beds, Type B	1,205.000	CY	44.40	35.00	
0280	605-Z002	Underdrain Appurtenances, Elbows, Couplings, etc.	1.000	LS	4,964.00	2,000.00	
0290	605-Z003	Underdrain Appurtenances, Sign	3.000	EA	218.00	250.00	
0300	605-Z006	Underdrain Appurtenances, Small Animal Guard	3.000	EA	95.70	250.00	
0310	618-A001	Maintenance of Traffic	1.000	LS	23,774.00	35,000.00	
0320	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	32.000	SF	11.80	12.50	
0330	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	456.000	SF	11.80	12.50	
0340	619-G4005	Barricades, Type III, Single Faced	48.000	LF	28.20	30.00	
0350	620-A001	Mobilization	1.000	LS	105,000.00	80,000.00	
0360	699-A001	Roadway Construction Stakes	1.000	LS	14,300.00	15,000.00	
0380	815-A002	Loose Riprap, Size 100	740.000	TON	40.70	52.00	
0390	815-E001	Geotextile under Riprap	1,500.000	SY	2.70	3.50	
0400	907-228-A002	Erosion Control Blanket, Type II	8,100.000	SY	2.95	3.50	
0410	907-619-E3001	Changeable Message Sign	1.000	EA	8,823.00	10,000.00	
0420	803-D006	HP 14 x 73 Steel Piling	6,105.000	LF	60.00	70.00	