

Call 07 Bridge Replacement on SR 19 (Bridge No. 57.6), known as Federal Aid Project No. BR-0026-01(079) / 106114302 in Neshoba County.

Q1. Where is the 12.5-mm leveling going to be? The proposal indicates 700 tons, and our takeoff based on plan typical sections indicate less than 200 tons.

A1. The 12.5-mm asphalt leveling pay item is listed as 1.5" & variable depth. The existing roadway will be overlaid from BOP to EOP, except in the area of the box culvert, with variable depth asphalt to meet the vertical profile shown on WK 3 (Sheet 16) of the plans. The approximate depth of leveling asphalt may be ascertained from the comparison of existing and proposed profile grades.