

**Call 09 Mill & Overlay approximately 5.4 miles of SR 25 from 2 miles South of Calvery Road to the SR 15 Interchange and approximately 0.5 miles of SR 15 from approximately 0.25 miles South of the SR 25/SR 15 Interchange to just North of the Interchange, known as Federal Aid Project Nos. NH-0056-01(100) / 107930301 & 302 in Winston County.**

Q1. 98 working days is going to be hard to achieve with the many scopes of work / sequence of operations. Could that be looked at and reassessed?

A1. See addendum.

Q2. **1.)** On sheet 22 of the plans (failed areas), the quantity for asphalt given only gives enough quantity for around 2" based on the 2,100 SY but the typical states 1' max. What is the intended thickness for base repairs? Please clarify the quantity for base repairs. **2.)** What is the required curing period for the road bed reclamation?

A2. **1.)** The estimated quantities have been increased by addendum to reflect up to one foot of asphalt in areas with base repair. Determinations will be made in the field by the Project Engineer as to whether the max of one foot is needed. **2.)** See addendum.