

STATE	PROJECT NO.
MISS.	NHPP-0010-01(169)

DESCRIPTION OF SHEET

WKG. NO. SH. NO.

DESCRIPTION OF SHEET

WKG. NO. SH. NO.

TITLE SHEET (1)

TITLE

1 1

STANDARD DRAWING SHEETS (7)

PAVEMENT MARKING DETAILS FOR 2-LANE AND 4-LANE DIVIDED ROADWAYS

PM-1 6051

CONCRETE MEDIAN BARRIER (PRECAST) (32")

CMB-3 6226

TRAFFIC CONTROL PLAN FOR POSTED SPEED LIMIT OF 65 OR 70 MPH (INTERSTATES AND OTHER 4-LANE DIVIDED HIGHWAYS)(MEDIAN LANE OR OUTSIDE LANE CLOSURE) (EXTENDED PERIOD)

TCP-4 6354

TRAFFIC CONTROL PLAN FOR POSTED SPEED LIMIT OF 65 OR 70 MPH (INTERSTATES AND OTHER 4-LANE DIVIDED HIGHWAYS)(MEDIAN LANE OR OUTSIDE LANE CLOSURE) (WORK DAY ONLY)

TCP-5 6355

TEMPORARY STRIPING FOR TRAFFIC CONTROL 2-LANE AND 4-LANE DIVIDED HIGHWAYS

TCP-13 6363

LOCATION OF R16-3 SIGNS (SPEEDING FINES DOUBLED)

TCP-15 6365

TRAFFIC CONTROL DETAILS DRUM PLACEMENT AND SHOULDER CLOSURE

TCP-16 6366

DETAILED INDEX & GENERAL NOTES (2)

DETAILED INDEX
GENERAL NOTES
SEE BRIDGE PLANS FOR BRIDGE DETAILED INDEX

DI-1 2
GN-1 3

QUANTITY SHEETS (3)

SUMMARY OF QUANTITIES
ESTIMATED QUANTITIES - SUMMARY OF TRAFFIC CONTROL ITEMS, SUMMARY OF PAVEMENT MARKINGS
ESTIMATED QUANTITIES - ALTERNATIVE 1 - SUMMARY OF TRAFFIC CONTROL SIGNS
SEE BRIDGE PLANS FOR BRIDGE ESTIMATED QUANTITIES

SQ-1 4
EQ-1 5
TCPQ-1 6

DETAILED CONSTRUCTION SIGNING SHEET (2)

DETAIL OF CONSTRUCTION SIGNING - ALTERNATIVE 1 - LANE SHIFT AND SHOULDER CLOSURE
DETAIL OF CONSTRUCTION SIGNING - ALTERNATIVE 2 - WORK FROM BARGE

DCS-1 7
DCS-2 8

TOTAL SHEETS (17)

TRAFFIC CONTROL DETAIL SHEETS (1)

TRAFFIC CONTROL PLAN - ALTERNATIVE 1 - LANE SHIFT AND SHOULDER CLOSURE

TC-1 9

PAVEMENT MARKING DETAIL SHEETS (1)


PAVEMENT MARKING DETAIL - ALTERNATIVE 1 - LANE SHIFT AND SHOULDER CLOSURE

PMD-1 10

1/6/2021 10:36 AM DI.DGN

PS & E PLANS-DATE 1/8/21		
FMS CON. # 108043/302000		
REVISIONS		
DATE	SHEET NO.	BY



REVISION	MISSISSIPPI DEPARTMENT OF TRANSPORTATION DETAILED INDEX	
	PROJ. NO.: NHP-0010-01(169) COUNTY: JACKSON	 WORKING NUMBER DI-1
DATE	FILENAME: DI.dgn	SHEET NUMBER
DESIGN TEAM	VOLKERT	CHECKED
		DATE
		2

STATE	PROJECT NO.
MISS.	NHPP-0010-01(169)

GENERAL NOTES

- (1) THE LOCATION AND SPACING OF SIGNS, SHOWN ON THE TRAFFIC CONTROL PLANS, ARE APPROXIMATE AND MAY BE ADJUSTED AS NECESSARY TO FIT FIELD CONDITIONS.
- (2) ALL TRAFFIC CONTROL DEVICES ON THIS PROJECT SHALL COMPLY WITH PART VI OF THE **MUTCD** (LATEST EDITION).
- (3) FLUORESCENT ORANGE SHEETING SHALL BE USED ON ALL CONSTRUCTION AND TRAFFIC CONTROL SIGNS EXCEPT FOR THOSE DESIGNATED ON THE PLANS TO BE BLACK LEGEND AND BORDER ON WHITE BACKGROUND.
- (4) THE CONTRACTOR SHALL COORDINATE WITH THE CONTRACTOR FROM ADJACENT PROJECT(S) IN IMPLEMENTING THE TRAFFIC CONTROL PLAN AS DIRECTED BY THE ENGINEER. ALL CONFLICTING SIGNS SHALL BE COVERED OR REMOVED AS DIRECTED BY THE ENGINEER.
- (5) THE CONTRACTOR SHALL COVER ANY TEMPORARY TRAFFIC CONTROL SIGNS SHOWN IN THE TRAFFIC CONTROL PLAN THAT DO NOT APPLY TO THE CURRENT PHASE.
- (6) REMOVAL OF RAISED PAVEMENT MARKERS THAT ARE IN CONFLICT WITH REQUIRED CONSTRUCTION IS NOT CONSIDERED A SEPARATE PAY ITEM. COST TO BE ABSORBED IN OTHER ITEMS BID.
- (7) TEMPORARY STRIPING SHALL CONFORM TO FINISHED STRIPE SPECIFICATIONS FOR ALIGNMENT, NEATNESS, AND STRAIGHTNESS.
- (8) ALL ADDENDA TO THESE PLANS WILL BE POSTED TO WWW.MDOT.MS.GOV UNDER THE PROPOSAL ADDENDA COLUMN. BIDDERS ARE ADVISED THAT HARD COPIES OF ANY ADDENDA FOR THIS PROJECT WILL NOT BE MAILED. IT IS THE BIDDER'S RESPONSIBILITY TO CHECK AND SEE IF ANY ADDENDA HAVE BEEN POSTED FOR THIS PROJECT.
- (9) STORAGE OF FLAMMABLE MATERIALS WILL NOT BE ALLOWED UNDER ANY BRIDGE STRUCTURES WITHOUT WRITTEN APPROVAL FROM THE PROJECT ENGINEER. SEE NOTICE TO BIDDERS ENTITLED "MATERIAL STORAGE UNDER BRIDGES" FOR MORE INFORMATION.
- (10) THE RETROREFLECTIVE SIGN SHEETING ON RIGID, TEMPORARY TRAFFIC CONTROL (ORANGE) SIGNS SHALL BE MINIMUM TYPE IX.
- (11) ALL TRAFFIC CONTROL ITEMS ABSORBED IN MAINTENANCE OF TRAFFIC. THIS INCLUDES BUT IS NOT LIMITED TO : PERMANENT AND TEMPORARY PAVEMENT MARKING, REMOVAL OF TRAFFIC STRIPE, REMOVAL OF PAVEMENT MARKERS, TRAFFIC CONTROL SIGNS, BARRICADES, WARNING LIGHTS, CONCRETE MEDIAN BARRIER, REFLECTIVE MARKERS, AND ANY OTHER ITEMS ASSOCIATED WITH TRAFFIC CONTROL.
- (12) ALL WORK REQUIRING A LANE CLOSURE SHALL BE RESTRICTED TO SUNDAY THROUGH THURSDAY NIGHTS BETWEEN THE HOURS OF 9 P.M. AND 5 A.M. CHANGES OR VARIANCES FROM THESE RESTRICTIONS SHALL BE SUBMITTED TO THE PROJECT ENGINEER FOR REVIEW AND WRITTEN APPROVAL. A LANE RENTAL FEE OF \$1,500.00 PER FULL OR PARTIAL 5 MINUTES SHALL BE ASSESSED FOR CLOSURES OR OBSTRUCTIONS THAT EXTEND BEYOND THE TIMES MENTIONED ABOVE. NO EXPOSED SIGNS SHALL BE VIEWABLE TO THE TRAVELING PUBLIC PRIOR TO OR AFTER THE ABOVE-MENTIONED TIMES. NO PART OF A CLOSURE, INCLUDING DRUMS OR CONES, SHALL BE IN THE ROADWAY PRIOR TO OR AFTER THE ABOVE-MENTIONED TIMES. WORK REQUIRING A LANE CLOSURE SHALL BEGIN WITHIN ONE (1) HOUR OF THE COMPLETION OF THE CLOSURE SETUP. LANE CLOSURES WILL BE ALLOWED ONLY AT TIMES WHEN WORK REQUIRING A LANE CLOSURE IS UNDERWAY. FAILURE TO BEGIN WORKING WITHIN THIS 1-HOUR PERIOD AND/OR FAILURE TO REMOVE THE LANE CLOSURE UPON COMPLETION OF WORK WILL RESULT IN THE CONTRACTOR BEING ASSESSED A LANE RENTAL FEE OF \$1,500.00 FOR EACH FULL OR PARTIAL FIVE-MINUTE PERIOD BEYOND THE ALLOWABLE TIMES.
- (13) CONTRACTOR SHALL PROVIDE PROJECT ENGINEER 48 HOURS NOTICE PRIOR TO ANY LANE CLOSURE.
- (14) THREE TRAFFIC CONTROL ALTERNATIVES ARE PROVIDED FOR THE CONTRACTOR :
 - (1) LANE SHIFT AND SHOULDER CLOSURE
 - (2) WORK FROM BARGE
 - (3) NIGHT-TIME LANE CLOSURE

GENERAL NOTES (CONT.)

12/9/2020 3:42 PM GN-1.DGN



REVISION		BY		MISSISSIPPI DEPARTMENT OF TRANSPORTATION GENERAL NOTES	
DATE		DESIGN TEAM		PROJ. NO.: NHPP-0010-01(169) COUNTY: JACKSON WORKING NUMBER GN-1	
FILENAME: GN-1.DGN		CHECKED		SHEET NUMBER 3	
DESIGN TEAM		VOLKERT		DATE	

