

Call 01 Overlay approximately 7 miles on US 90 from SR 57 to the West Pascagoula River Bridge, known as State Project No. SP-0003-01(203) / 108278301 in Jackson County.

Q1. With the lack of milling projects on the Coast area over the last several years would MDOT Maintenance consider retaining a smaller percentage of RAP on this project?

A1. See addendum.

Q2. The scope of work listed in the project specifications under drainage items lists removal of debris and sand from 24" and 36" pipes under US 90 between Shaw Drive and Guillotte Drive, video inspection, and installation of Cured-In-Place Pipe. During our visit to the site, we noticed several pipes on the north side of US 90, but a lesser number on the south side. Are we to clean and inspect all of the pipes running under US 90 whether they start or stop at curb inlets, box inlets, or flared end sections? Will the final determination of the pipes to be lined be made after review of the video inspection?

A2. Only the two pipes (24" and 36" cross drains) listed in the Scope are to be cleaned and lined.

Q3. Scope of Work states, "All work requiring a lane closure within the limits of SR57 and the West Pascagoula Bridge shall be restricted to Sunday through Thursday between the hours of 5:00 PM to 4:30 AM. Changes or variances from these restrictions shall be submitted to the Project Engineer for review and written approval. Can a request for this to be changed to a day time hour project be accepted?

A3. All requests will be considered. However, Bidders are advised to bid as per the contract documents.