

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					R & J Construction Company, Inc.	Dunn Roadbuilders, LLC	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75					\$4,165,667.25	\$4,335,522.00	\$5,268,883.71
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS	51,000.00	85,000.00	150,000.00
0020	202-B004	Removal of Asphalt Driveways, All Depths	844.000	SY	2.25	7.00	6.00
0030	202-B007	Removal of Asphalt Pavement, All Depths	13,779.000	SY	2.25	3.00	6.00
0040	202-B059	Removal of Concrete Median & Island Pavement, All Depths	263.000	SY	18.00	5.00	19.00
0050	202-B063	Removal of Concrete Paved Ditch	68.000	SY	18.00	18.00	20.00
0060	202-B088	Removal of Curb & Gutter, All Types	796.000	LF	3.50	6.00	15.00
0070	202-B165	Removal of Inlets, All Sizes	1.000	EA	500.00	705.00	900.00
0080	202-B170	Removal of Junction Box	1.000	EA	500.00	705.00	900.00
0090	202-B191	Removal of Pipe, 8" And Above	515.000	LF	25.00	14.00	20.00
0100	202-B206	Removal of Right-Of-Way Marker	9.000	EA	100.00	47.00	300.00
0110	202-B215	Removal of Sign Including Post & Footing	45.000	EA	75.00	114.00	100.00
0120	203-A001	Unclassified Excavation, FM, AH	38,705.000	CY	3.45	5.00	6.08
0130	203-EX018	Borrow Excavation, AH, FME, Class B7-6	40,034.000	CY	10.15	11.00	10.80
0140	203-G001	Excess Excavation, FM, AH	24,459.000	CY	6.35	3.65	5.00
0150	206-A001	Structure Excavation	2,100.000	CY	8.00	11.00	19.00
0160	206-B001	Select Material for Undercuts, Contractor Furnished, FM	165.000	CY	34.25	75.00	63.00
0170	209-A005	Geotextile Stabilization, Type V, Non-Woven	27,420.000	SY	0.25	2.25	2.80
0180	211-B001	Topsoil for Slope Treatment, Contractor Furnished	2,000.000	CY	12.00	0.01	2.35
0190	213-C001	Superphosphate	8.000	TON	776.25	432.00	860.00
0200	216-A001	Solid Sodding	276.000	SY	5.25	10.00	5.75
0210	217-A001	Ditch Liner	440.000	SY	2.25	2.00	2.30
0220	219-A001	Watering	6.000	KGAL	20.00	20.00	20.00
0230	221-A001	Concrete Paved Ditch	26.000	CY	362.25	864.00	990.00
0240	223-A001	Mowing	45.000	ACRE	50.00	50.00	50.00
0250	224-A001	Soil Reinforcing Mat	1,081.000	SY	2.25	4.30	2.30
0260	225-A001	Grassing	15.000	ACRE	828.00	2,000.00	900.00

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					R & J Construction Company, Inc.	Dunn Roadbuilders, LLC	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75					\$4,165,667.25	\$4,335,522.00	\$5,268,883.71
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	225-B001	Agricultural Limestone	8.000	TON	98.50	108.00	110.00
0280	225-C001	Mulch, Vegetative Mulch	30.000	TON	196.75	270.00	220.00
0290	226-A001	Temporary Grassing	15.000	ACRE	828.00	1,070.00	900.00
0300	234-A001	Temporary Silt Fence	19,015.000	LF	1.55	3.00	1.75
0310	235-A001	Temporary Erosion Checks	200.000	EA	10.50	11.00	3.00
0320	236-A008	Silt Basin, Type D	5.000	EA	5,000.00	4,100.00	2,600.00
0330	236-B004	Maintenance and Removal of Existing Silt Basins, Type D	5.000	EA	3,000.00	4,100.00	1,100.00
0340	237-A002	Wattles, 20"	900.000	LF	5.25	12.00	7.70
0350	246-A001	Sandbags	30.000	LF	20.75	12.00	11.00
0360	249-A001	Riprap for Erosion Control	2,409.000	TON	67.00	77.00	80.00
0370	403-A001	12.5-mm, HT, Asphalt Pavement	476.000	TON	100.50	99.00	111.00
0380	403-A003	12.5-mm, ST, Asphalt Pavement	1,699.000	TON	98.50	97.00	110.00
0390	403-A004	19-mm, HT, Asphalt Pavement	655.000	TON	98.50	97.00	110.00
0400	403-A006	19-mm, ST, Asphalt Pavement	2,402.000	TON	91.25	90.00	102.00
0410	403-A013	9.5-mm, HT, Asphalt Pavement	1,646.000	TON	103.50	103.00	115.00
0420	403-A015	9.5-mm, ST, Asphalt Pavement	1,528.000	TON	108.75	107.00	121.00
0430	403-B003	12.5-mm, ST, Asphalt Pavement, Leveling	872.000	TON	100.50	99.00	111.00
0440	406-D001	Fine Milling of Bituminous Pavement, All Depths	16,174.000	SY	1.00	3.00	3.45
0450	407-A001	Asphalt for Tack Coat	4,301.000	GAL	2.25	2.25	2.30
0460	423-A001	Rumble Strips, Ground In	3.000	MI	310.50	324.00	345.00
0470	503-C010	Saw Cut, Full Depth	2,775.000	LF	7.25	9.00	8.00
0480	601-B001	Class "B" Structural Concrete, Minor Structures	25.000	CY	1,323.00	1,842.00	2,000.00
0490	602-A001	Reinforcing Steel	489.000	LBS	3.25	1.00	2.00
0500	603-ALT003	18" Type A Alternate Pipe	80.000	LF	46.75	62.00	45.00
0510	603-ALT013	36" x 23" Type A Alternate Pipe	80.000	LF	71.25	108.00	78.00
0520	603-CA012	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	392.000	LF	36.25	62.00	50.00

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					R & J Construction Company, Inc.	Dunn Roadbuilders, LLC	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75					\$4,165,667.25	\$4,335,522.00	\$5,268,883.71
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0530	603-CA027	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	360.000	LF	47.00	74.00	64.00
0540	603-CA071	42" Reinforced Concrete Pipe, Class IV, Rubber Type Gaskets	480.000	LF	101.25	140.00	150.00
0550	603-CA112	66" Reinforced Concrete Pipe, Class III, Rubber Type Gasket	96.000	LF	220.25	378.00	340.00
0560	603-CA116	66" Reinforced Concrete Pipe, Class IV, Rubber Type Gaskets	72.000	LF	242.25	432.00	360.00
0570	603-CB003	18" Reinforced Concrete End Section	3.000	EA	625.00	864.00	850.00
0580	603-CB004	24" Reinforced Concrete End Section	10.000	EA	725.00	864.00	850.00
0590	603-CB007	42" Reinforced Concrete End Section	4.000	EA	1,550.00	1,890.00	2,600.00
0600	603-CB011	66" Reinforced Concrete End Section	2.000	EA	2,700.00	3,672.00	4,000.00
0610	603-CE003	22" x 13" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	296.000	LF	45.25	75.00	64.00
0620	603-CF002	22" x 13" Concrete Arch Pipe End Section	1.000	EA	650.00	756.00	1,200.00
0630	604-B001	Gratings	1,500.000	LBS	4.50	6.50	3.85
0640	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	960.000	LF	23.50	19.50	25.85
0650	609-D008	Combination Concrete Curb and Gutter Type 3A	986.000	LF	27.50	19.50	30.45
0660	612-B001	Flowable Fill, Non-Excavatable	10.000	CY	456.50	540.00	400.00
0670	616-A001	Concrete Median and/or Island Pavement, 10-inch	34.000	SY	124.25	108.00	138.00
0680	616-A004	Concrete Median and/or Island Pavement, 4-inch	487.000	SY	46.75	59.00	51.70
0690	617-A001	Right-of-Way Marker	38.000	EA	269.25	226.00	300.00
0700	618-A001	Maintenance of Traffic	1.000	LS	33,411.00	40,000.00	80,000.00
0710	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	5.000	MI	1,035.00	1,080.00	1,149.00
0720	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	4.000	MI	1,035.00	1,080.00	1,149.00
0730	619-A3001	Temporary Traffic Stripe, Skip White	2.000	MI	1,035.00	1,080.00	1,149.00
0740	619-A5002	Temporary Traffic Stripe, Detail, Paint	28,521.000	LF	0.20	0.10	0.11
0750	619-A6003	Temporary Traffic Stripe, Legend, Paint	357.000	SF	1.05	1.00	1.15
0760	619-A6004	Temporary Traffic Stripe, Legend, Paint	753.000	LF	1.05	1.00	1.15
0770	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	242.000	EA	7.25	8.00	8.05
0780	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	160.000	SF	8.50	16.00	6.90

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					R & J Construction Company, Inc.	Dunn Roadbuilders, LLC	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75					\$4,165,667.25	\$4,335,522.00	\$5,268,883.71
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0790	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	736.000	SF	8.50	16.00	6.90
0800	619-G4001	Barricades, Type III, Double Faced	48.000	LF	26.00	38.00	19.55
0810	619-G4005	Barricades, Type III, Single Faced	156.000	LF	26.00	32.00	16.10
0820	619-G5001	Free Standing Plastic Drums	200.000	EA	58.00	59.00	40.25
0830	619-G7001	Warning Lights, Type "B"	6.000	EA	196.75	162.00	144.00
0840	620-A001	Mobilization	1.000	LS	362,967.00	91,000.00	365,000.00
0850	626-A004	6" Thermoplastic Traffic Stripe, Skip White	1.000	MI	2,070.00	2,160.00	2,298.00
0860	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	2.000	MI	4,140.00	4,320.00	4,595.00
0870	626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	2.000	MI	4,140.00	4,320.00	4,595.00
0880	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	1.000	MI	4,140.00	4,320.00	4,595.00
0890	626-G002	Thermoplastic Detail Stripe, White	12,492.000	LF	2.10	2.00	2.30
0900	626-G003	Thermoplastic Detail Stripe, Yellow	1,246.000	LF	2.10	2.00	2.30
0910	626-H004	Thermoplastic Legend, White	356.000	SF	7.25	8.00	8.05
0920	626-H005	Thermoplastic Legend, White	893.000	LF	2.75	3.00	2.90
0930	627-J001	Two-Way Clear Reflective High Performance Raised Markers	137.000	EA	8.50	9.00	9.20
0940	627-K001	Red-Clear Reflective High Performance Raised Markers	247.000	EA	8.50	9.00	9.20
0950	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	136.000	EA	8.50	9.00	9.20
0960	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	92.000	SF	23.00	22.00	23.00
0970	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	107.000	SF	24.00	24.00	25.30
0980	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	136.000	SF	23.50	23.00	24.15
0990	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	192.000	SF	28.00	30.00	32.15
1000	630-C002	Steel U-Section Posts, 2.0 lb/ft	9.000	LF	12.00	9.00	8.85
1010	630-C003	Steel U-Section Posts, 3.0 lb/ft	362.000	LF	12.50	10.00	10.35
1020	630-D008	Structural Steel Beams, W6 x 9	156.000	LF	96.50	60.00	63.20
1030	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	123.000	LBS	4.50	3.00	2.90
1040	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	208.000	LBS	4.75	3.00	2.90

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					R & J Construction Company, Inc.	Dunn Roadbuilders, LLC	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75					\$4,165,667.25	\$4,335,522.00	\$5,268,883.71
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1050	630-K003	Welded & Seamless Steel Pipe Posts, 4"	182.000	LF	58.00	54.00	57.45
1060	635-A059	Traffic Signal Head, Type 1	5.000	EA	911.00	898.00	1,011.00
1070	635-A065	Traffic Signal Head, Type 2 FYA	2.000	EA	1,594.00	1,462.00	1,769.00
1080	635-A070	Traffic Signal Head, Type 3	2.000	EA	1,304.25	1,412.00	1,448.00
1090	635-A073	Traffic Signal Head, Type 4	1.000	EA	1,335.25	1,349.00	1,482.00
1100	638-A006	Flasher Assembly, Prepare To Stop	4.000	EA	3,943.50	3,867.00	4,377.00
1110	647-A001	Removal of Existing Traffic Signal Equipment	1.000	LS	10,433.00	3,670.00	12,428.00
1120	699-A001	Roadway Construction Stakes	1.000	LS	58,000.00	42,000.00	70,000.00
1130	815-A002	Loose Riprap, Size 100	258.000	TON	67.00	88.00	80.00
1140	815-E001	Geotextile under Riprap	598.000	SY	2.75	2.00	3.95
1150	815-F002	Sediment Control Stone	324.000	TON	59.00	69.00	80.00
1160	907-240-A001	Interlocking Flexible Block Erosion Control System	2,116.000	SY	77.75	81.00	85.00
1170	907-253-A001	Coir Fiber Baffle	934.000	LF	10.50	6.00	12.00
1180	907-632-A007	Solid State Traffic Cabinet Assembly, Type III Cabinet, Type 1 Controller	1.000	EA	29,012.00	19,026.00	32,000.00
1190	907-632-J001	Power Service Pedestal	1.000	EA	6,521.00	4,206.00	7,237.00
1200	907-634-A107	Traffic Signal Equipment Pole, Type II, 22' Shaft, 40' Arm	1.000	EA	10,433.00	10,586.00	11,578.00
1210	907-634-A109	Traffic Signal Equipment Pole, Type II, 22' Shaft, 50' Arm	1.000	EA	11,572.00	11,799.00	12,842.00
1220	907-634-A117	Traffic Signal Equipment Pole, Type II, 22' Shaft, 90' Arm	2.000	EA	27,774.50	27,607.00	30,000.00
1230	907-634-C001	Pole Foundations, Class "B" Concrete	35.000	CY	101.00	898.00	1.10
1240	907-636-B006	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 12, 4 Conductor	2,500.000	LF	2.00	2.00	2.20
1250	907-636-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 8 Conductor	795.000	LF	2.50	3.00	2.65
1260	907-636-B053	Electric Cable, Underground in Conduit, THHN, AWG #6, 3 Conductor	20.000	LF	6.25	8.00	6.65
1270	907-636-D003	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 12, 4 Conductor	96.000	LF	2.00	4.00	2.10
1280	907-636-D008	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 14, 8 Conductor	343.000	LF	2.50	5.00	2.65
1290	907-636-D020	Electric Cable, Aerial Supported in Conduit, THHN, AWG #6, 3 Conductor	40.000	LF	6.25	7.00	6.90
1300	907-637-A002	Pullbox Enclosure, Type 2	9.000	EA	983.25	847.00	1,092.00

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					R & J Construction Company, Inc.	Dunn Roadbuilders, LLC	T. L. Wallace Construction, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75					\$4,165,667.25	\$4,335,522.00	\$5,268,883.71
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1310	907-637-A003	Pullbox Enclosure, Type 3	2.000	EA	1,226.50	1,293.00	1,362.00
1320	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	140.000	LF	8.50	9.00	9.20
1330	907-637-C030	Traffic Signal Conduit, Underground, Type 4, 3"	20.000	LF	12.50	13.00	13.80
1340	907-637-D002	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 2"	2,010.000	LF	10.00	16.00	10.95
1350	907-637-D003	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3"	510.000	LF	15.75	20.00	17.30
1360	907-639-J001	Type 3 Intersection Device	1.000	EA	6,195.00	6,430.00	6,875.00
1370	907-641-A002	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2	4.000	EA	7,158.00	7,255.00	7,943.00
1380	907-641-B002	Signal Advanced Radar Vehicle Detection Sensor, Type 2	2.000	EA	7,520.00	7,684.00	8,345.00
1390	907-641-D001	Radar Vehicle Detection Cable	1,686.000	LF	2.50	3.00	2.80
1400	907-653-B001	Street Name Sign	47.000	SF	83.00	74.00	91.90
1410	304-F001	3/4" and Down Crushed Stone Base	17,577.000	TON			
1420	304-F002	Size 610 Crushed Stone Base	17,577.000	TON			
1430	304-F003	Size 825B Crushed Stone Base	17,577.000	TON	38.00	43.00	60.00

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					Walters Construction Co., Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75					\$5,342,284.94		
Ref#	Item	Item Description	Item Qty	Units	4		
0010	201-A001	Clearing and Grubbing	1.000	LS	202,000.00		
0020	202-B004	Removal of Asphalt Driveways, All Depths	844.000	SY	14.00		
0030	202-B007	Removal of Asphalt Pavement, All Depths	13,779.000	SY	4.60		
0040	202-B059	Removal of Concrete Median & Island Pavement, All Depths	263.000	SY	30.00		
0050	202-B063	Removal of Concrete Paved Ditch	68.000	SY	72.00		
0060	202-B088	Removal of Curb & Gutter, All Types	796.000	LF	11.00		
0070	202-B165	Removal of Inlets, All Sizes	1.000	EA	702.00		
0080	202-B170	Removal of Junction Box	1.000	EA	702.00		
0090	202-B191	Removal of Pipe, 8" And Above	515.000	LF	9.00		
0100	202-B206	Removal of Right-Of-Way Marker	9.000	EA	371.00		
0110	202-B215	Removal of Sign Including Post & Footing	45.000	EA	100.00		
0120	203-A001	Unclassified Excavation, FM, AH	38,705.000	CY	6.80		
0130	203-EX018	Borrow Excavation, AH, FME, Class B7-6	40,034.000	CY	12.70		
0140	203-G001	Excess Excavation, FM, AH	24,459.000	CY	9.20		
0150	206-A001	Structure Excavation	2,100.000	CY	12.55		
0160	206-B001	Select Material for Undercuts, Contractor Furnished, FM	165.000	CY	37.70		
0170	209-A005	Geotextile Stabilization, Type V, Non-Woven	27,420.000	SY	2.00		
0180	211-B001	Topsoil for Slope Treatment, Contractor Furnished	2,000.000	CY	4.45		
0190	213-C001	Superphosphate	8.000	TON	883.00		
0200	216-A001	Solid Sodding	276.000	SY	5.80		
0210	217-A001	Ditch Liner	440.000	SY	2.40		
0220	219-A001	Watering	6.000	KGAL	20.00		
0230	221-A001	Concrete Paved Ditch	26.000	CY	1,100.00		
0240	223-A001	Mowing	45.000	ACRE	50.00		
0250	224-A001	Soil Reinforcing Mat	1,081.000	SY	2.40		
0260	225-A001	Grassing	15.000	ACRE	942.00		

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					Walters Construction Co., Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75						\$5,342,284.94	
Ref#	Item	Item Description	Item Qty	Units		4	
0270	225-B001	Agricultural Limestone	8.000	TON		112.00	
0280	225-C001	Mulch, Vegetative Mulch	30.000	TON		224.00	
0290	226-A001	Temporary Grassing	15.000	ACRE		942.00	
0300	234-A001	Temporary Silt Fence	19,015.000	LF		2.00	
0310	235-A001	Temporary Erosion Checks	200.000	EA		11.77	
0320	236-A008	Silt Basin, Type D	5.000	EA		932.00	
0330	236-B004	Maintenance and Removal of Existing Silt Basins, Type D	5.000	EA		4,500.00	
0340	237-A002	Wattles, 20"	900.000	LF		5.90	
0350	246-A001	Sandbags	30.000	LF		23.55	
0360	249-A001	Riprap for Erosion Control	2,409.000	TON		102.00	
0370	403-A001	12.5-mm, HT, Asphalt Pavement	476.000	TON		106.50	
0380	403-A003	12.5-mm, ST, Asphalt Pavement	1,699.000	TON		101.00	
0390	403-A004	19-mm, HT, Asphalt Pavement	655.000	TON		115.00	
0400	403-A006	19-mm, ST, Asphalt Pavement	2,402.000	TON		99.00	
0410	403-A013	9.5-mm, HT, Asphalt Pavement	1,646.000	TON		107.00	
0420	403-A015	9.5-mm, ST, Asphalt Pavement	1,528.000	TON		104.00	
0430	403-B003	12.5-mm, ST, Asphalt Pavement, Leveling	872.000	TON		101.00	
0440	406-D001	Fine Milling of Bituminous Pavement, All Depths	16,174.000	SY		5.75	
0450	407-A001	Asphalt for Tack Coat	4,301.000	GAL		3.00	
0460	423-A001	Rumble Strips, Ground In	3.000	MI		350.00	
0470	503-C010	Saw Cut, Full Depth	2,775.000	LF		8.25	
0480	601-B001	Class "B" Structural Concrete, Minor Structures	25.000	CY		2,000.00	
0490	602-A001	Reinforcing Steel	489.000	LBS		1.60	
0500	603-ALT003	18" Type A Alternate Pipe	80.000	LF		40.00	
0510	603-ALT013	36" x 23" Type A Alternate Pipe	80.000	LF		40.00	
0520	603-CA012	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	392.000	LF		46.72	

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					Walters Construction Co., Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75						\$5,342,284.94	
Ref#	Item	Item Description	Item Qty	Units	4		
0530	603-CA027	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	360.000	LF		93.50	
0540	603-CA071	42" Reinforced Concrete Pipe, Class IV, Rubber Type Gaskets	480.000	LF		128.00	
0550	603-CA112	66" Reinforced Concrete Pipe, Class III, Rubber Type Gasket	96.000	LF		238.00	
0560	603-CA116	66" Reinforced Concrete Pipe, Class IV, Rubber Type Gaskets	72.000	LF		288.00	
0570	603-CB003	18" Reinforced Concrete End Section	3.000	EA		1,200.00	
0580	603-CB004	24" Reinforced Concrete End Section	10.000	EA		1,250.00	
0590	603-CB007	42" Reinforced Concrete End Section	4.000	EA		2,000.00	
0600	603-CB011	66" Reinforced Concrete End Section	2.000	EA		5,200.00	
0610	603-CE003	22" x 13" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	296.000	LF		96.50	
0620	603-CF002	22" x 13" Concrete Arch Pipe End Section	1.000	EA		1,200.00	
0630	604-B001	Gratings	1,500.000	LBS		2.65	
0640	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	960.000	LF		26.50	
0650	609-D008	Combination Concrete Curb and Gutter Type 3A	986.000	LF		31.20	
0660	612-B001	Flowable Fill, Non-Excavatable	10.000	CY		400.00	
0670	616-A001	Concrete Median and/or Island Pavement, 10-inch	34.000	SY		140.00	
0680	616-A004	Concrete Median and/or Island Pavement, 4-inch	487.000	SY		53.00	
0690	617-A001	Right-of-Way Marker	38.000	EA		235.00	
0700	618-A001	Maintenance of Traffic	1.000	LS		29,000.00	
0710	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	5.000	MI		1,177.00	
0720	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	4.000	MI		1,177.00	
0730	619-A3001	Temporary Traffic Stripe, Skip White	2.000	MI		1,177.00	
0740	619-A5002	Temporary Traffic Stripe, Detail, Paint	28,521.000	LF		0.13	
0750	619-A6003	Temporary Traffic Stripe, Legend, Paint	357.000	SF		1.18	
0760	619-A6004	Temporary Traffic Stripe, Legend, Paint	753.000	LF		1.18	
0770	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	242.000	EA		8.24	
0780	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	160.000	SF		17.66	

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					Walters Construction Co., Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75					\$5,342,284.94		
Ref#	Item	Item Description	Item Qty	Units	4		
0790	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	736.000	SF		17.66	
0800	619-G4001	Barricades, Type III, Double Faced	48.000	LF		41.20	
0810	619-G4005	Barricades, Type III, Single Faced	156.000	LF		35.35	
0820	619-G5001	Free Standing Plastic Drums	200.000	EA		64.75	
0830	619-G7001	Warning Lights, Type "B"	6.000	EA		176.00	
0840	620-A001	Mobilization	1.000	LS		430,000.00	
0850	626-A004	6" Thermoplastic Traffic Stripe, Skip White	1.000	MI		2,350.00	
0860	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	2.000	MI		4,700.00	
0870	626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	2.000	MI		4,700.00	
0880	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	1.000	MI		4,700.00	
0890	626-G002	Thermoplastic Detail Stripe, White	12,492.000	LF		2.36	
0900	626-G003	Thermoplastic Detail Stripe, Yellow	1,246.000	LF		2.36	
0910	626-H004	Thermoplastic Legend, White	356.000	SF		8.24	
0920	626-H005	Thermoplastic Legend, White	893.000	LF		2.95	
0930	627-J001	Two-Way Clear Reflective High Performance Raised Markers	137.000	EA		9.45	
0940	627-K001	Red-Clear Reflective High Performance Raised Markers	247.000	EA		9.45	
0950	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	136.000	EA		9.45	
0960	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	92.000	SF		23.50	
0970	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	107.000	SF		26.00	
0980	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	136.000	SF		25.00	
0990	630-B002	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted	192.000	SF		33.00	
1000	630-C002	Steel U-Section Posts, 2.0 lb/ft	9.000	LF		9.00	
1010	630-C003	Steel U-Section Posts, 3.0 lb/ft	362.000	LF		10.60	
1020	630-D008	Structural Steel Beams, W6 x 9	156.000	LF		64.75	
1030	630-E002	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	123.000	LBS		2.94	
1040	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	208.000	LBS		2.94	

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					Walters Construction Co., Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75						\$5,342,284.94	
Ref#	Item	Item Description	Item Qty	Units		4	
1050	630-K003	Welded & Seamless Steel Pipe Posts, 4"	182.000	LF		58.80	
1060	635-A059	Traffic Signal Head, Type 1	5.000	EA		1,000.00	
1070	635-A065	Traffic Signal Head, Type 2 FYA	2.000	EA		1,800.00	
1080	635-A070	Traffic Signal Head, Type 3	2.000	EA		1,500.00	
1090	635-A073	Traffic Signal Head, Type 4	1.000	EA		1,500.00	
1100	638-A006	Flasher Assembly, Prepare To Stop	4.000	EA		4,500.00	
1110	647-A001	Removal of Existing Traffic Signal Equipment	1.000	LS		13,000.00	
1120	699-A001	Roadway Construction Stakes	1.000	LS		53,000.00	
1130	815-A002	Loose Riprap, Size 100	258.000	TON		133.50	
1140	815-E001	Geotextile under Riprap	598.000	SY		2.00	
1150	815-F002	Sediment Control Stone	324.000	TON		84.60	
1160	907-240-A001	Interlocking Flexible Block Erosion Control System	2,116.000	SY		88.30	
1170	907-253-A001	Coir Fiber Baffle	934.000	LF		12.00	
1180	907-632-A007	Solid State Traffic Cabinet Assembly, Type III Cabinet, Type 1 Controller	1.000	EA		33,000.00	
1190	907-632-J001	Power Service Pedestal	1.000	EA		7,500.00	
1200	907-634-A107	Traffic Signal Equipment Pole, Type II, 22' Shaft, 40' Arm	1.000	EA		12,000.00	
1210	907-634-A109	Traffic Signal Equipment Pole, Type II, 22' Shaft, 50' Arm	1.000	EA		13,000.00	
1220	907-634-A117	Traffic Signal Equipment Pole, Type II, 22' Shaft, 90' Arm	2.000	EA		31,500.00	
1230	907-634-C001	Pole Foundations, Class "B" Concrete	35.000	CY		1.12	
1240	907-636-B006	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 12, 4 Conductor	2,500.000	LF		2.25	
1250	907-636-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 8 Conductor	795.000	LF		2.70	
1260	907-636-B053	Electric Cable, Underground in Conduit, THHN, AWG #6, 3 Conductor	20.000	LF		6.70	
1270	907-636-D003	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 12, 4 Conductor	96.000	LF		2.12	
1280	907-636-D008	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 14, 8 Conductor	343.000	LF		2.71	
1290	907-636-D020	Electric Cable, Aerial Supported in Conduit, THHN, AWG #6, 3 Conductor	40.000	LF		7.07	
1300	907-637-A002	Pullbox Enclosure, Type 2	9.000	EA		1,100.00	

Intersection Improvements on US 84 at Reservoir Road / Magnolia Hill Road & SR 184, known as Federal Aid Project No. HSIP-0015-03 (011) / 107249301 in Wayne County.					Walters Construction Co., Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,523,416.75					\$5,342,284.94		
Ref#	Item	Item Description	Item Qty	Units	4		
1310	907-637-A003	Pullbox Enclosure, Type 3	2.000	EA	1,400.00		
1320	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	140.000	LF	9.40		
1330	907-637-C030	Traffic Signal Conduit, Underground, Type 4, 3"	20.000	LF	14.00		
1340	907-637-D002	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 2"	2,010.000	LF	11.18		
1350	907-637-D003	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3"	510.000	LF	17.75		
1360	907-639-J001	Type 3 Intersection Device	1.000	EA	7,000.00		
1370	907-641-A002	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2	4.000	EA	8,100.00		
1380	907-641-B002	Signal Advanced Radar Vehicle Detection Sensor, Type 2	2.000	EA	8,500.00		
1390	907-641-D001	Radar Vehicle Detection Cable	1,686.000	LF	2.82		
1400	907-653-B001	Street Name Sign	47.000	SF	94.00		
1410	304-F001	3/4" and Down Crushed Stone Base	17,577.000	TON			
1420	304-F002	Size 610 Crushed Stone Base	17,577.000	TON			
1430	304-F003	Size 825B Crushed Stone Base	17,577.000	TON	47.50		