

Intersection Improvements on US 61 at SR 533, known as Federal Aid Project No. HSIP-0009-01(148) / 108425301 in Jefferson County.					G. Rayborn Contracting	T. L. Wallace Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,542,142.59					\$2,665,895.50	\$2,727,750.34	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	201-B001	Clearing and Grubbing	6.000	ACRE	5,000.00	1,125.00	
0020	202-A001	Removal of Obstructions	1.000	LS	15,000.00	4,000.00	
0030	202-B007	Removal of Asphalt Pavement, All Depths	654.000	SY	10.00	14.70	
0040	202-B050	Removal of Concrete Combination Curb & Gutter	145.000	LF	10.00	13.05	
0050	202-B059	Removal of Concrete Median & Island Pavement, All Depths	100.000	SY	10.00	50.15	
0060	202-B063	Removal of Concrete Paved Ditch	20.000	SY	20.00	54.55	
0070	202-B129	Removal of Flared End Section, All Sizes	1.000	EA	100.00	425.70	
0080	202-B165	Removal of Inlets, All Sizes	1.000	EA	1,000.00	1,703.00	
0090	202-B191	Removal of Pipe, 8" And Above	8.000	LF	10.00	26.15	
0100	202-B240	Removal of Traffic Stripe	13,800.000	LF	3.50	3.45	
0110	203-A001	Unclassified Excavation, FM, AH	626.000	CY	10.00	14.95	
0120	203-EX020	Borrow Excavation, AH, FME, Class B9	6,469.000	CY	15.00	17.65	
0130	203-G001	Excess Excavation, FM, AH	250.000	CY	15.00	14.40	
0140	206-A001	Structure Excavation	7.000	CY	30.00	73.35	
0150	209-A005	Geotextile Stabilization, Type V, Non-Woven	9,777.000	SY	4.00	2.90	
0160	213-C001	Superphosphate	3.000	TON	900.00	863.05	
0170	215-A001	Vegetative Materials for Mulch	12.000	TON	325.00	224.40	
0180	216-A001	Solid Sodding	307.000	SY	7.00	5.75	
0190	217-A001	Ditch Liner	889.000	SY	3.25	2.20	
0200	219-A001	Watering	6.000	KGAL	20.00	20.00	
0210	220-A001	Insect Pest Control	3.000	ACRE	30.00	30.00	
0220	221-A001	Concrete Paved Ditch	42.000	CY	800.00	969.25	
0230	223-A001	Mowing	12.000	ACRE	50.00	50.00	
0240	225-A001	Grassing	6.000	ACRE	1,550.00	920.55	
0250	225-B001	Agricultural Limestone	3.000	TON	300.00	109.35	
0260	226-A001	Temporary Grassing	3.000	ACRE	1,200.00	920.55	

Intersection Improvements on US 61 at SR 533, known as Federal Aid Project No. HSIP-0009-01(148) / 108425301 in Jefferson County.					G. Rayborn Contracting	T. L. Wallace Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,542,142.59					\$2,665,895.50	\$2,727,750.34	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	234-A001	Temporary Silt Fence	2,500.000	LF	3.50	3.45	
0280	234-D001	Inlet Siltation Guard	4.000	EA	550.00	575.35	
0290	237-A002	Wattles, 20"	200.000	LF	10.00	7.85	
0300	246-B002	Rockbags	150.000	LF	12.00	11.30	
0310	249-A001	Riprap for Erosion Control	100.000	TON	100.00	65.45	
0320	304-B004	Granular Material, Class 5, Group D	5,893.000	TON	25.00	35.00	
0330	403-A002	12.5-mm, MT, Asphalt Pavement	1,004.000	TON	135.00	139.85	
0340	403-A005	19-mm, MT, Asphalt Pavement	1,254.000	TON	125.00	129.10	
0350	403-A006	19-mm, ST, Asphalt Pavement	1,601.000	TON	115.00	109.75	
0360	403-A014	9.5-mm, MT, Asphalt Pavement	2,795.000	TON	120.00	116.20	
0370	406-A002	Cold Milling of Bituminous Pavement, All Depths	7,157.000	SY	6.00	6.75	
0380	407-A001	Asphalt for Tack Coat	4,141.000	GAL	5.50	4.30	
0390	423-A001	Rumble Strips, Ground In	3.000	MI	1,500.00	322.20	
0400	503-C010	Saw Cut, Full Depth	745.000	LF	20.00	21.10	
0410	601-B001	Class "B" Structural Concrete, Minor Structures	3.000	CY	1,500.00	2,000.00	
0420	602-A001	Reinforcing Steel	95.000	LBS	10.00	1.70	
0430	603-CA011	18" Reinforced Concrete Pipe, Class III	8.000	LF	65.00	64.10	
0440	603-CE002	22" x 13" Concrete Arch Pipe, Class A III	40.000	LF	75.00	60.60	
0450	603-CF002	22" x 13" Concrete Arch Pipe End Section	1.000	EA	1,000.00	908.20	
0460	609-D003	Combination Concrete Curb and Gutter Type 2	5,200.000	LF	24.00	26.00	
0470	612-B001	Flowable Fill, Non-Excavatable	2.000	CY	1,000.00	1,414.00	
0480	616-A001	Concrete Median and/or Island Pavement, 10-inch	467.000	SY	90.00	105.00	
0490	618-A001	Maintenance of Traffic	1.000	LS	60,000.00	100,000.00	
0500	619-A1002	Temporary Traffic Stripe, Continuous White	15,534.000	LF	1.75	1.55	
0510	619-A2002	Temporary Traffic Stripe, Continuous Yellow	11,500.000	LF	1.75	1.55	
0520	619-A3002	Temporary Traffic Stripe, Skip White	16,080.000	LF	1.75	1.55	

Intersection Improvements on US 61 at SR 533, known as Federal Aid Project No. HSIP-0009-01(148) / 108425301 in Jefferson County.					G. Rayborn Contracting	T. L. Wallace Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,542,142.59					\$2,665,895.50	\$2,727,750.34	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0530	619-A5001	Temporary Traffic Stripe, Detail	6,770.000	LF	1.75	1.55	
0540	619-A6001	Temporary Traffic Stripe, Legend	180.000	SF	3.00	2.30	
0550	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	205.000	SF	10.00	9.20	
0560	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	749.000	SF	10.00	9.20	
0570	619-F1001	Concrete Median Barrier, Precast	4,050.000	LF	42.00	25.00	
0580	619-F2001	Remove and Reset Concrete Median Barrier, Precast	4,450.000	LF	15.00	20.00	
0590	619-G4005	Barricades, Type III, Single Faced	144.000	LF	22.00	20.75	
0600	619-G5001	Free Standing Plastic Drums	142.000	EA	55.00	55.25	
0610	619-G7001	Warning Lights, Type "B"	8.000	EA	200.00	208.00	
0620	620-A001	Mobilization	1.000	LS	250,000.00	260,000.00	
0630	626-A002	6" Thermoplastic Double Drop Traffic Stripe, Skip White	8,040.000	LF	1.50	1.15	
0640	626-B001	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	1,502.000	LF	1.75	1.45	
0650	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	6,505.000	LF	1.75	1.45	
0660	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	880.000	LF	1.75	1.45	
0670	626-F002	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	4,870.000	LF	1.75	1.45	
0680	626-G002	Thermoplastic Detail Stripe, White	7,540.000	LF	3.00	2.90	
0690	626-G003	Thermoplastic Detail Stripe, Yellow	5,759.000	LF	3.00	2.90	
0700	626-H004	Thermoplastic Legend, White	715.000	SF	10.00	9.20	
0710	627-K001	Red-Clear Reflective High Performance Raised Markers	438.000	EA	10.00	8.65	
0720	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	200.000	EA	10.00	8.65	
0730	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	12.000	SF	30.00	23.05	
0740	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	89.000	SF	30.00	24.20	
0750	630-C001	Square Tube Posts, 4.0 lb/ft	709.000	LF	40.00	41.45	
0760	630-C002	Steel U-Section Posts, 2.0 lb/ft	54.000	LF	15.00	10.35	
0770	630-E005	Structural Steel Angles & Bars, Aluminum Unistrut	66.000	LBS	5.00	4.05	
0780	630-K002	Welded & Seamless Steel Pipe Posts, 3"	96.000	LF	65.00	63.30	

Intersection Improvements on US 61 at SR 533, known as Federal Aid Project No. HSIP-0009-01(148) / 108425301 in Jefferson County.					G. Rayborn Contracting	T. L. Wallace Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,542,142.59					\$2,665,895.50	\$2,727,750.34	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0790	699-A001	Roadway Construction Stakes	1.000	LS	10,000.00	27,000.00	
0800	907-630-PP002	Roadside Directional Signs, Sheet Aluminum, 0.125" Thickness, Ground Mounted	93.000	SF	30.00	25.35	
0810	304-F001	3/4" and Down Crushed Stone Base	5,638.000	TON			
0820	304-F002	Size 610 Crushed Stone Base	5,638.000	TON	55.00	58.08	
0830	304-F003	Size 825B Crushed Stone Base	5,638.000	TON			

Letting Date: 6/22/2021

Call Number: 01

Page 4 of 4