

Mill & Overlay approximately 8.5 miles on SR 32 from the end of the 4-lane section in Charleston to US 51, known as State Project Nos. MP-2032-68(009) / 307473301 & MP-2032-81(007) / 307473302 in Tallahatchie & Yalobusha Counties.					Lehman-Roberts Company		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,676,505.35					\$4,088,536.00		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-B007	Removal of Asphalt Pavement, All Depths	1,500.000	SY	115.00		
0020	203-G001	Excess Excavation, FM, AH	230.000	CY	5.75		
0030	304-B002	Granular Material, Class 3, Group D	2,400.000	TON	37.00		
0040	403-A006	19-mm, ST, Asphalt Pavement	950.000	TON	130.00		
0050	403-A015	9.5-mm, ST, Asphalt Pavement	14,610.000	TON	109.00		
0060	403-B012	9.5-mm, ST, Asphalt Pavement, Leveling	6,975.000	TON	109.00		
0070	406-D001	Fine Milling of Bituminous Pavement, All Depths	79,650.000	SY	2.65		
0080	407-A001	Asphalt for Tack Coat	7,700.000	GAL	3.25		
0090	423-A001	Rumble Strips, Ground In	20.000	MI	450.00		
0100	503-C010	Saw Cut, Full Depth	1,500.000	LF	11.00		
0110	618-A001	Maintenance of Traffic	1.000	LS	185,000.00		
0120	618-B001	Additional Construction Signs	2.000	SF	10.00		
0130	619-A1001	Temporary Traffic Stripe, Continuous White	58.000	MI	1,500.00		
0140	619-A2001	Temporary Traffic Stripe, Continuous Yellow	51.000	MI	1,500.00		
0150	619-A4002	Temporary Traffic Stripe, Skip Yellow	23.000	MI	1,500.00		
0160	619-A5001	Temporary Traffic Stripe, Detail	21,700.000	LF	0.22		
0170	619-A6002	Temporary Traffic Stripe, Legend	7,175.000	LF	1.50		
0180	620-A001	Mobilization	1.000	LS	200,000.00		
0190	626-C004	6" Thermoplastic Edge Stripe, Continuous White	20.000	MI	4,650.00		
0200	626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	9.000	MI	2,600.00		
0210	626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	7.000	MI	4,650.00		
0220	626-G002	Thermoplastic Detail Stripe, White	5,290.000	LF	2.30		
0230	626-G003	Thermoplastic Detail Stripe, Yellow	1,915.000	LF	2.30		
0240	626-H005	Thermoplastic Legend, White	2,400.000	LF	4.00		
0250	627-J001	Two-Way Clear Reflective High Performance Raised Markers	832.000	EA	9.00		
0260	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	824.000	EA	9.00		

Mill & Overlay approximately 8.5 miles on SR 32 from the end of the 4-lane section in Charleston to US 51, known as State Project Nos. MP-2032-68(009) / 307473301 & MP-2032-81(007) / 307473302 in Tallahatchie & Yalobusha Counties.					Lehman-Roberts Company		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,676,505.35					\$4,088,536.00		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	138.000	SF	22.75		
0280	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	378.000	SF	26.75		
0290	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	108.000	SF	24.75		
0300	907-414-A001	Scrub Seal	93,700.000	SY	2.85		
0310	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	250.00		

Letting Date: 6/22/2021

Call Number: 23

Page 2 of 2