

Emergency Slide Repair on I-20 EB at Ellis Avenue Interchange, known as Federal Aid Project No. ER-0020-01(258) / 108473301 in Hinds County.					Dozer, LLC	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$369,522.35					\$899,156.60	\$943,140.85	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	202-B006	Removal of Asphalt Paved Shoulders, All Depths	71.000	SY	25.00	35.00	
0020	202-B061	Removal of Concrete Median Barrier, Precast	120.000	LF	35.00	35.00	
0030	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	140.000	LF	16.80	20.00	
0040	202-B251	Removal of Underground Electric Wire	750.000	LF	3.60	2.00	
0050	203-EX008	Borrow Excavation, AH, FME, Class B15	100.000	CY	50.00	65.00	
0060	203-EX020	Borrow Excavation, AH, FME, Class B9	2,676.000	CY	32.75	40.00	
0070	203-G001	Excess Excavation, FM, AH	3,002.000	CY	15.00	30.00	
0080	206-A001	Structure Excavation	17.000	CY	50.00	79.25	
0090	206-B001	Select Material for Undercuts, Contractor Furnished, FM	50.000	CY	100.00	112.75	
0100	209-A005	Geotextile Stabilization, Type V, Non-Woven	30.000	SY	10.00	6.75	
0110	211-B001	Topsoil for Slope Treatment, Contractor Furnished	193.000	CY	35.00	52.50	
0120	213-C001	Superphosphate	1.000	TON	1,200.00	1,150.00	
0130	220-A001	Insect Pest Control	1.000	ACRE	30.00	30.00	
0140	225-A001	Grassing	1.000	ACRE	4,200.00	3,150.00	
0150	225-B001	Agricultural Limestone	2.000	TON	300.00	435.00	
0160	225-C001	Mulch, Vegetative Mulch	1.000	TON	600.00	505.00	
0170	226-A001	Temporary Grassing	1.000	ACRE	4,200.00	2,500.00	
0180	229-A001	Erosion Mat	882.000	SY	100.00	92.50	
0190	234-A001	Temporary Silt Fence	625.000	LF	8.00	7.50	
0200	237-A002	Wattles, 20"	625.000	LF	10.00	10.00	
0210	246-B001	Rockbags	176.000	EA	25.00	15.00	
0220	249-A001	Riprap for Erosion Control	25.000	TON	120.00	125.00	
0230	249-B001	Remove and Reset Riprap	20.000	CY	50.00	68.25	
0240	304-D004	Granular Material, Size 57	40.000	TON	150.00	125.00	
0250	403-A003	12.5-mm, ST, Asphalt Pavement	16.000	TON	420.00	450.00	
0260	407-A001	Asphalt for Tack Coat	6.000	GAL	13.20	25.00	

Emergency Slide Repair on I-20 EB at Ellis Avenue Interchange, known as Federal Aid Project No. ER-0020-01(258) / 108473301 in Hinds County.					Dozer, LLC	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$369,522.35					\$899,156.60	\$943,140.85	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	503-C010	Saw Cut, Full Depth	110.000	LF	35.00	50.00	
0280	601-B001	Class "B" Structural Concrete, Minor Structures	12.000	CY	5,000.00	3,825.00	
0290	602-A001	Reinforcing Steel	631.000	LBS	3.00	2.85	
0300	603-CA076	48" Reinforced Concrete Pipe, Class III	32.000	LF	240.00	295.00	
0310	605-AA001	Geotextile for Subsurface Drainage, Type III	407.000	SY	5.00	5.25	
0320	605-O004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	178.000	LF	30.00	55.00	
0330	605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	240.000	LF	30.00	55.00	
0340	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	18.000	CY	100.00	128.25	
0350	605-Z001	Underdrain Appurtenances, Concrete Apron, Precast or Cast-In-Place	1.000	EA	2,500.00	4,825.00	
0360	605-Z002	Underdrain Appurtenances, Elbows, Couplings, etc.	1.000	LS	2,500.00	3,250.00	
0370	605-Z005	Underdrain Appurtenances, Small Animal Guard	1.000	LS	50.00	215.00	
0380	606-B001	Guard Rail, Class A, Type 1	75.000	LF	33.60	40.00	
0390	606-D012	Guard Rail, Bridge End Section, Type D Modified	1.000	EA	3,420.00	4,125.00	
0400	606-E005	Guard Rail, Terminal End Section, Flared	1.000	EA	4,140.00	4,975.00	
0410	618-A001	Maintenance of Traffic	1.000	LS	227,154.00	72,500.00	
0420	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	19.000	SF	11.40	10.00	
0430	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	360.000	SF	11.40	10.00	
0440	619-G4005	Barricades, Type III, Single Faced	42.000	LF	37.80	20.00	
0450	619-G5001	Free Standing Plastic Drums	20.000	EA	74.40	55.50	
0460	619-G7001	Warning Lights, Type "B"	2.000	EA	189.60	150.00	
0470	620-A001	Mobilization	1.000	LS	204,130.00	329,050.00	
0480	630-F006	Delineators, Guard Rail, White	5.000	EA	26.40	30.00	
0490	630-G004	Type 3 Object Markers, OM-3R or OM-3L	1.000	EA	102.00	125.00	
0500	682-B005	Underground Branch Circuit, Jacked or Bored, AWG 1/0, 3 Conductor	750.000	LF	41.10	55.00	
0510	699-A001	Roadway Construction Stakes	1.000	LS	25,000.00	17,500.00	
0520	907-619-E3001	Changeable Message Sign	3.000	EA	1,260.00	4,325.00	

Emergency Slide Repair on I-20 EB at Ellis Avenue Interchange, known as Federal Aid Project No. ER-0020-01(258) / 108473301 in Hinds County.					Dozer, LLC	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$369,522.35					\$899,156.60	\$943,140.85	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0530	304-F001	3/4" and Down Crushed Stone Base	5.000	TON			
0540	304-F002	Size 610 Crushed Stone Base	5.000	TON	450.00	195.00	
0550	304-F003	Size 825B Crushed Stone Base	5.000	TON			

Letting Date: 9/22/2021

Call Number: 01

Page 3 of 3