

Call 05 Bridge Replacements on SR 493 (Bridge Nos. 6.2 & 6.4), known as Federal Project No. BR-0447-00(022) / 100589304 in Lauderdale County.

- Q1. Working Sheet 3, Sheet No. 20, in the Contract Plans refers to cross-sections, but we were unable to locate them. Can these cross-sections be provided?
- A1. See Addendum.
- Q2. The project plans and proposal list the borrow excavation as B17; however, Note 7 of General Notes states that the design soil shall be a A-6(10) and the backfill of any undercut shall be B15. The proposal does not include a pay item for B15 borrow and B17 borrow does not meet A-6(10) specifications. Please advise which borrow specification is required.
- A2. See Addendum.
- Q3. Will asphalt be required under guardrails?
- A3. Yes.
- Q4. Can we request to change the Borrow Excavation specifications to B15 to meet A-6(10) specifications? B17 sample collected for project use exhibit a wide range of P.I. 15-31 and sandy soil conditions.
- A4. No. Borrow Excavation shall be B17. Please refer to Addendum 1 for more details.
- Q5. Is Sheet Number 6009 incorrect as it shows a 33.5" bridge end pavement rail and the pay items and Sheet Number 39 show 37.5"?
- A5. Sheet Number 6009 (Working Number BER-1) was included by error and shall be disregarded.
- Q6. On sheet 39, the plans show the 37.5" Bridge End Pavement Rail using the bracket that is 1'-3". Could the ends be worked up using the 8" bracket that has been used in other jobs?
- A6. Yes. A 2nd Order Revision will be issued to reflect this change.