

Overlay approximately 7 miles on SR 7 from the Humphreys County Line to 2 miles south of Morgan City, known as State Project No. MP-2007-42(009) / 307475301 in Leflore County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,213,817.15					\$3,135,375.80		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-B007	Removal of Asphalt Pavement, All Depths	1,306.000	SY	75.00		
0020	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	229.000	SY	271.70		
0030	202-B240	Removal of Traffic Stripe	675.000	LF	4.00		
0040	203-G001	Excess Excavation, FM, AH	340.000	CY	30.00		
0050	304-B002	Granular Material, Class 3, Group D	5,100.000	TON	38.00		
0060	403-A006	19-mm, ST, Asphalt Pavement	1,011.000	TON	125.00		
0070	403-A015	9.5-mm, ST, Asphalt Pavement	10,900.000	TON	116.00		
0080	403-B012	9.5-mm, ST, Asphalt Pavement, Leveling	775.000	TON	140.00		
0090	403-C003	19-mm, ST, Asphalt Pavement, Trench Widening	2,784.000	TON	125.00		
0100	406-D001	Fine Milling of Bituminous Pavement, All Depths	110,000.000	SY	2.25		
0110	407-A001	Asphalt for Tack Coat	9,540.000	GAL	4.00		
0120	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	18,200.000	LF	3.00		
0130	423-A001	Rumble Strips, Ground In	16.000	MI	425.00		
0140	503-C010	Saw Cut, Full Depth	2,094.000	LF	11.50		
0190	618-A001	Maintenance of Traffic	1.000	LS	200,000.00		
0200	618-B001	Additional Construction Signs	10.000	SF	10.00		
0210	619-A1001	Temporary Traffic Stripe, Continuous White	30.000	MI	1,500.00		
0220	619-A4002	Temporary Traffic Stripe, Skip Yellow	16.000	MI	1,500.00		
0230	619-A5001	Temporary Traffic Stripe, Detail	540.000	LF	0.50		
0240	619-A6002	Temporary Traffic Stripe, Legend	675.000	LF	2.00		
0250	620-A001	Mobilization	1.000	LS	150,000.00		
0260	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	540.000	LF	2.00		
0270	626-C004	6" Thermoplastic Edge Stripe, Continuous White	16.000	MI	4,800.00		
0280	626-D002	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	294.000	LF	2.00		
0290	626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	8.000	MI	2,400.00		
0300	626-G002	Thermoplastic Detail Stripe, White	540.000	LF	2.00		

Overlay approximately 7 miles on SR 7 from the Humphreys County Line to 2 miles south of Morgan City, known as State Project No. MP-2007-42(009) / 307475301 in Leflore County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,213,817.15					\$3,135,375.80		
Ref#	Item	Item Description	Item Qty	Units	1		
0310	626-H005	Thermoplastic Legend, White	450.000	LF	4.00		
0320	627-J001	Two-Way Clear Reflective High Performance Raised Markers	89.000	EA	8.50		
0330	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	518.000	EA	8.50		
0340	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	51.000	SF	20.00		
0350	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	170.000	SF	22.00		
0360	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	8.000	SF	21.00		
0362	630-C005	Square Tube Posts, 2.0 lb/ft	525.000	LF	25.00		
0380	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	85.00		