

Bridge Replacements on SR 6 through Marks (Bridge Nos. 31.3, 32.1, 33.2 & 33.5), known as Federal Aid Project No. BR-0070-02(015) / 102624303 in Quitman County.					W. G. Yates & Sons Construction Company	Manhattan Road & Bridge Company	Eutaw Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$28,894,390.65					\$29,770,439.45	IRREGULAR \$31,293,653.00	\$39,959,704.58
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS	170,000.00	450,000.00	1,667,000.00
0020	201-B001	Clearing and Grubbing	5.000	ACRE	6,000.00	15,000.00	6,000.00
0030	202-A001	Removal of Obstructions	1.000	LS	650,000.00	450,000.00	465,000.00
0040	202-B019	Removal of Box Culvert	53.000	LF	250.00	400.00	651.61
0050	202-B037	Removal of Bridge Railing	124.000	LF	55.00	60.00	125.56
0060	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	24,153.000	SY	8.50	7.00	32.53
0070	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	2,576.000	LF	8.00	7.20	9.09
0080	202-B165	Removal of Inlets, All Sizes	1.000	EA	700.00	960.00	819.55
0090	202-B191	Removal of Pipe, 8" And Above	399.000	LF	25.00	28.00	11.71
0100	202-B240	Removal of Traffic Stripe	4,453.000	LF	4.00	4.25	4.54
0110	203-A001	Unclassified Excavation, FM, AH	59,207.000	CY	8.00	9.00	13.75
0120	203-EX020	Borrow Excavation, AH, FME, Class B9	163,420.000	CY	15.00	16.00	28.00
0130	203-G001	Excess Excavation, FM, AH	86,747.000	CY	6.00	8.50	6.35
0140	206-A001	Structure Excavation	1,234.000	CY	30.00	15.00	11.83
0150	206-B001	Select Material for Undercuts, Contractor Furnished, FM	537.000	CY	120.00	60.00	62.48
0160	209-A005	Geotextile Stabilization, Type V, Non-Woven	55,107.000	SY	4.00	2.75	2.19
0170	211-B001	Topsoil for Slope Treatment, Contractor Furnished	8,346.000	CY	5.00	11.00	1.00
0180	213-C001	Superphosphate	16.000	TON	900.00	900.00	1,022.33
0190	216-A001	Solid Sodding	1,452.000	SY	10.00	6.25	11.36
0200	217-A001	Ditch Liner	358.000	SY	5.00	5.25	5.68
0210	219-A001	Watering	29.000	KGAL	20.00	20.00	20.00
0220	220-A001	Insect Pest Control	31.000	ACRE	30.00	30.00	30.00
0230	221-A001	Concrete Paved Ditch	247.000	CY	450.00	750.00	823.99
0240	223-A001	Mowing	62.000	ACRE	50.00	50.00	50.00
0250	224-A001	Soil Reinforcing Mat	1,069.000	SY	5.00	5.25	5.68
0260	225-A001	Grassing	31.000	ACRE	1,750.00	835.00	1,987.87

Bridge Replacements on SR 6 through Marks (Bridge Nos. 31.3, 32.1, 33.2 & 33.5), known as Federal Aid Project No. BR-0070-02(015) / 102624303 in Quitman County.					W. G. Yates & Sons Construction Company	Manhattan Road & Bridge Company	Eutaw Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$28,894,390.65						IRREGULAR	
					\$29,770,439.45	\$31,293,653.00	\$39,959,704.58
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	225-B001	Agricultural Limestone	93.000	TON	50.00	105.00	56.80
0280	225-C001	Mulch, Vegetative Mulch	62.000	TON	200.00	210.00	227.19
0290	226-A001	Temporary Grassing	31.000	ACRE	1,050.00	835.00	1,192.72
0300	234-A001	Temporary Silt Fence	23,200.000	LF	3.50	3.20	5.73
0310	234-C001	Super Silt Fence	8,100.000	LF	10.50	12.00	14.26
0320	234-D001	Inlet Siltation Guard	1.000	EA	750.00	785.04	851.95
0330	234-E001	Reset Inlet Siltation Guard	1.000	EA	750.00	525.00	851.95
0340	234-F001	Turbidity Barrier	1,030.000	LF	20.00	34.00	22.72
0350	236-A008	Silt Basin, Type D	1.000	EA	7,000.00	7,200.00	1,567.59
0360	237-A002	Wattles, 20"	31,800.000	LF	5.00	4.20	5.68
0370	239-A001	Temporary Slope Drains	4,520.000	LF	15.00	19.50	20.05
0380	245-A001	Silt Dike	200.000	LF	8.00	19.50	9.09
0390	246-B001	Rockbags	900.000	EA	12.00	7.85	17.66
0400	247-A001	Temporary Stream Diversion	3.000	EA	13,000.00	15,500.00	24,000.00
0410	249-A001	Riprap for Erosion Control	4,420.000	TON	80.00	77.00	68.00
0420	249-B001	Remove and Reset Riprap	2,940.000	CY	40.00	36.00	40.73
0430	304-B002	Granular Material, Class 3, Group D	15,150.000	TON	28.00	46.00	39.71
0440	403-A002	12.5-mm, MT, Asphalt Pavement	2,535.000	TON	137.00	141.00	160.52
0445	403-A003	12.5-mm, ST, Asphalt Pavement	252.000	TON	162.00	167.00	190.24
0450	403-A005	19-mm, MT, Asphalt Pavement	2,852.000	TON	127.00	131.00	148.63
0460	403-A006	19-mm, ST, Asphalt Pavement	3,644.000	TON	127.00	131.00	148.63
0470	403-A014	9.5-mm, MT, Asphalt Pavement	3,732.000	TON	142.00	146.00	166.46
0480	403-A015	9.5-mm, ST, Asphalt Pavement	476.000	TON	203.00	209.00	237.80
0490	403-B002	12.5-mm, MT, Asphalt Pavement, Leveling	158.000	TON	223.00	230.00	261.58
0500	403-C003	19-mm, ST, Asphalt Pavement, Trench Widening	32.000	TON	610.00	627.00	713.41
0510	406-D001	Fine Milling of Bituminous Pavement, All Depths	21,765.000	SY	5.00	3.00	1.42

Bridge Replacements on SR 6 through Marks (Bridge Nos. 31.3, 32.1, 33.2 & 33.5), known as Federal Aid Project No. BR-0070-02(015) / 102624303 in Quitman County.					W. G. Yates & Sons Construction Company	Manhattan Road & Bridge Company	Eutaw Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$28,894,390.65					\$29,770,439.45	IRREGULAR \$31,293,653.00	\$39,959,704.58
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0520	407-A001	Asphalt for Tack Coat	8,722.000	GAL	3.60	3.65	4.16
0530	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	188.000	LF	10.00	10.50	11.47
0540	423-A001	Rumble Strips, Ground In	5.000	MI	500.00	795.00	309.14
0550	502-A001	Reinforced Cement Concrete Bridge End Pavement	404.000	SY	295.00	400.00	416.50
0560	503-C010	Saw Cut, Full Depth	120.000	LF	4.00	16.00	9.42
0570	601-A001	Class "B" Structural Concrete	782.000	CY	750.00	875.00	1,000.00
0580	601-B001	Class "B" Structural Concrete, Minor Structures	3.000	CY	2,500.00	5,500.00	3,102.44
0590	602-A001	Reinforcing Steel	141,093.000	LBS	1.75	1.20	1.14
0600	603-ALT003	18" Type A Alternate Pipe	292.000	LF	60.00	72.00	48.66
0610	603-ALT006	24" Type A Alternate Pipe	144.000	LF	80.00	91.00	62.88
0620	603-ALT008	29" x 18" Type A Alternate Pipe	32.000	LF	100.00	133.00	66.32
0630	603-ALT009	30" Type A Alternate Pipe	72.000	LF	100.00	112.00	82.18
0640	603-ALT016	48" Type A Alternate Pipe	104.000	LF	150.00	200.00	134.15
0650	603-CA040	30" Reinforced Concrete Pipe, Class III	112.000	LF	100.00	118.00	82.41
0660	603-CB004	24" Reinforced Concrete End Section	2.000	EA	1,325.00	2,130.00	1,121.54
0670	603-CB005	30" Reinforced Concrete End Section	4.000	EA	1,500.00	2,400.00	2,693.13
0680	603-CB008	48" Reinforced Concrete End Section	2.000	EA	3,100.00	3,300.00	2,172.65
0690	603-CF003	29" x 18" Concrete Arch Pipe End Section	2.000	EA	1,400.00	2,150.00	1,152.46
0700	604-B001	Gratings	250.000	LBS	6.00	7.50	2.71
0710	605-AA001	Geotextile for Subsurface Drainage, Type III	107.000	SY	6.00	12.00	3.71
0720	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	192.000	LF	20.00	40.00	21.72
0730	605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	24.000	LF	30.00	55.00	21.73
0740	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	7.000	CY	200.00	170.00	85.55
0742	605-X005	Filter Material for Filter Beds, Type C	3,700.000	CY	22.00	100.00	18.75
0750	606-B001	Guard Rail, Class A, Type 1	650.000	LF	24.00	25.00	27.26
0760	606-D022	Guard Rail, Bridge End Section, Type I	8.000	EA	3,150.00	3,300.00	3,578.17

Bridge Replacements on SR 6 through Marks (Bridge Nos. 31.3, 32.1, 33.2 & 33.5), known as Federal Aid Project No. BR-0070-02(015) / 102624303 in Quitman County.					W. G. Yates & Sons Construction Company	Manhattan Road & Bridge Company	Eutaw Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$28,894,390.65					\$29,770,439.45	IRREGULAR \$31,293,653.00	\$39,959,704.58
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0770	606-E005	Guard Rail, Terminal End Section, Flared	8.000	EA	3,350.00	3,500.00	3,805.36
0780	609-D003	Combination Concrete Curb and Gutter Type 2	337.000	LF	38.50	60.00	35.38
0790	612-A001	Flowable Fill, Excavatable	254.000	CY	350.00	405.00	425.97
0800	614-A003	Concrete Driveway, Without Reinforcement, 6-inch Thickness	128.000	SY	91.00	110.00	146.88
0810	615-A004	Concrete Bridge End Barrier, 43.5"	80.000	LF	91.00	96.00	105.00
0820	617-A001	Right-of-Way Marker	44.000	EA	260.00	380.00	1,241.83
0830	618-A001	Maintenance of Traffic	1.000	LS	175,000.00	8,500.00	450,000.00
0840	619-A1001	Temporary Traffic Stripe, Continuous White	9.000	MI	2,000.00	2,100.00	2,271.85
0850	619-A1005	Temporary Traffic Stripe, Continuous White, Type 1 Tape	2,660.000	LF	3.50	3.65	3.98
0860	619-A2001	Temporary Traffic Stripe, Continuous Yellow	9.000	MI	2,000.00	2,100.00	2,271.85
0870	619-A2006	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	1,160.000	LF	3.50	3.65	3.98
0880	619-A4002	Temporary Traffic Stripe, Skip Yellow	2.000	MI	2,000.00	2,100.00	2,271.86
0890	619-A5001	Temporary Traffic Stripe, Detail	4,757.000	LF	0.30	0.32	0.34
0900	619-A6002	Temporary Traffic Stripe, Legend	484.000	LF	1.50	1.60	1.70
0910	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	96.000	SF	10.00	10.50	11.36
0920	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	887.000	SF	10.00	10.50	11.36
0930	619-G4001	Barricades, Type III, Double Faced	24.000	LF	24.00	25.00	27.26
0940	619-G4005	Barricades, Type III, Single Faced	384.000	LF	20.00	21.00	22.72
0950	619-G5001	Free Standing Plastic Drums	74.000	EA	75.00	78.00	85.19
0960	619-G7001	Warning Lights, Type "B"	16.000	EA	200.00	210.00	227.19
0970	620-A001	Mobilization	1.000	LS	2,750,000.00	1,500,000.00	3,990,000.00
0980	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	5.000	MI	6,500.00	6,800.00	6,701.97
0990	626-D001	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	2.000	MI	3,000.00	3,150.00	3,407.78
1000	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	2.000	MI	6,500.00	6,800.00	6,701.97
1010	626-G002	Thermoplastic Detail Stripe, White	4,346.000	LF	3.00	3.20	3.41
1020	626-H004	Thermoplastic Legend, White	167.000	SF	10.00	10.50	11.36

Bridge Replacements on SR 6 through Marks (Bridge Nos. 31.3, 32.1, 33.2 & 33.5), known as Federal Aid Project No. BR-0070-02(015) / 102624303 in Quitman County.					W. G. Yates & Sons Construction Company	Manhattan Road & Bridge Company	Eutaw Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$28,894,390.65						IRREGULAR	
Ref#	Item	Item Description	Item Qty	Units	1	2	3
					\$29,770,439.45	\$31,293,653.00	\$39,959,704.58
1030	626-H005	Thermoplastic Legend, White	292.000	LF	4.00	4.20	4.54
1040	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	283.000	EA	10.00	10.50	11.36
1050	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	218.000	SF	22.00	23.00	24.99
1060	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	398.000	SF	24.00	25.00	27.26
1070	630-C001	Square Tube Posts, 4.0 lb/ft	885.000	LF	48.00	50.00	54.52
1080	630-C1001	Square Post Inner Sleeve	40.000	LF	78.00	81.50	88.60
1090	630-E005	Structural Steel Angles & Bars, Aluminum Unistrut	190.000	LBS	5.00	5.25	5.68
1100	630-F006	Delineators, Guard Rail, White	44.000	EA	22.00	23.00	24.99
1110	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	4.000	EA	85.00	90.00	96.55
1120	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	4.000	EA	85.00	90.00	96.55
1130	699-A001	Roadway Construction Stakes	1.000	LS	250,000.00	250,000.00	575,000.00
1140	815-A007	Loose Riprap, Size 300	1,017.000	TON	70.00	80.00	68.00
1150	815-E001	Geotextile under Riprap	1,322.000	SY	5.00	7.50	2.61
1160	815-F002	Sediment Control Stone	593.000	TON	75.00	75.00	59.10
1170	907-207-A001	Settlement Plate	2.000	EA	5,000.00	5,500.00	4,196.58
1180	907-253-A001	Coir Fiber Baffle	175.000	LF	25.00	15.50	28.40
1190	907-832-PP003	Concrete Mat	18,728.000	SY	85.00	101.00	102.33
1200	907-899-A001	Railway-Highway Provisions	1.000	LS	40,000.00	27,000.00	100,000.00
1210	907-906001	Trainees	1,040.000	HRS	5.00	5.00	5.00
1220	304-F001	3/4" and Down Crushed Stone Base	17,800.000	TON			
1230	304-F002	Size 610 Crushed Stone Base	17,800.000	TON	50.00	55.00	54.00
1240	304-F003	Size 825B Crushed Stone Base	17,800.000	TON			
1250	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	97.000	CY			14.26
1260	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	97.000	CY	80.00	125.00	
1270	501-K001	Transverse Grooving	5,891.000	SY	3.00	2.45	2.64
1280	803-K014	Drilled Shaft, 84" Diameter	520.000	LF	1,550.00	1,750.00	2,200.00

Bridge Replacements on SR 6 through Marks (Bridge Nos. 31.3, 32.1, 33.2 & 33.5), known as Federal Aid Project No. BR-0070-02(015) / 102624303 in Quitman County.					W. G. Yates & Sons Construction Company	Manhattan Road & Bridge Company	Eutaw Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$28,894,390.65						IRREGULAR	
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1290	803-L009	Test Shaft, 84" Diameter	1.000	EA	370,000.00	395,000.00	450,000.00
1300	803-M012	Trial Shaft, 84" Diameter	145.000	LF	1,500.00	1,700.00	1,850.00
1310	803-N001	Exploration	40.000	LF	1.00	130.00	588.56
1320	803-O028	Temporary Casing, 84" Diameter	100.000	LF	950.00	960.00	1,099.84
1330	803-P001	24" Steel Pipe Piling, Wall Thickness 0.500"	3,715.000	LF	255.00	253.00	270.00
1340	803-P009	30" Steel Pipe Piling, Wall Thickness 0.625"	1,040.000	LF	345.00	407.00	360.00
1350	804-C186	110' Prestressed Concrete Beam, Type FIB-45	2,625.000	LF	325.00	381.00	350.00
1360	804-C196	140' Prestressed Concrete Beam, Type FIB-63	837.000	LF	425.00	385.00	420.00
1370	805-A001	Reinforcement	616,381.000	LBS	1.40	1.40	1.80
1380	805-C001	Reinforcement, Corrosion Resistant	3,390.000	LBS	3.25	4.10	4.56
1390	810-A007	Structural Steel, A 709, Grade 50W	1,130,893.000	LBS	2.25	2.89	2.80
1400	810-A008	Structural Steel, A 709, Grade HPS 70W	1,189,625.000	LBS	2.25	2.89	3.30
1410	811-D001	Disc Bearing Device	20.000	EA	8,500.00	13,925.00	9,380.00
1420	813-A003	Concrete Railing, 42"	2,674.000	LF	91.00	95.00	113.00
1430	815-A007	Loose Riprap, Size 300	1,161.000	TON	70.00	67.00	68.00
1440	815-E001	Geotextile under Riprap	1,995.000	SY	5.00	4.40	2.19
1450	907-803-B001	Conventional Static Pile Load Test	2.000	EA	5,000.00	5,000.00	5,000.00
1460	907-803-I004	PDA Test Pile, Steel Pipe Pile	6.000	EA	35,000.00	31,500.00	29,500.00
1470	907-803-J001	Pile Restrike	4.000	EA	1,000.00	1,100.00	1,223.49
1480	907-804-A001	Bridge Concrete, Class BDX	816.000	CY	1,200.00	950.00	1,150.00
1490	907-804-A002	Bridge Concrete, Class AA	580.000	CY	1,200.00	875.00	1,200.00
1500	907-804-A004	Bridge Concrete, Class BD	1,002.000	CY	1,100.00	900.00	1,050.00
1510	907-823-A001	Preformed Joint Seal, Type I	94.000	LF	25.00	25.00	27.54
1520	907-823-A002	Preformed Joint Seal, Type II	94.000	LF	30.00	28.00	30.98
1530	907-827-A002	7" Modular Bridge Joint System	94.000	LF	1,600.00	1,650.00	2,518.62