

Call 01 Bridge Repair on SR 16/149 over Whittington Auxiliary Channel (Bridge No. 211.1), known as State Project No. SP-0091-01(010) / 109070301 in Yazoo County.

Q1. Will temporary striping be required or will the road remain closed long enough until permanent stripe can be placed?

A1. Permanent stripe is to be done prior to reopening the road to traffic.

Q2. 1.) Due to the lack of availability of 4' milling machines equipped with fine milling drums, would it be acceptable by the Department to use a regular milling drum on a 4' machine?
2.) Would it be possible to use a 7' milling machine with a fine milling drum?

A2. 1.) No. 2.) No.

Q3. Will the hybrid polymer concrete overlay be required to be poured continuously? If not, is there a desired pour sequence that we need to accommodate?

A3. The Department does not have a preference on if it is poured continuously and has no desired pour sequence, but it must be poured as per the manufacturer's recommendations.