

Intersection Improvements on SR 826 at SR 14 & US 61, known as Federal Aid Project No. STBG-0009-02(087) / 106687301 in Sharkey County.					Simmons Erosion Control, Inc.	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,398,840.75					\$1,496,585.10	\$1,684,587.25	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	202-B008	Removal of Asphalt Pavement, All Depths, Including Soil Cement Base	2,208.000	SY	16.00	30.00	
0020	202-B089	Removal of Curb &/or Curb and Gutter, All Types	450.000	LF	15.00	15.00	
0030	202-B240	Removal of Traffic Stripe	500.000	LF	6.25	12.00	
0040	203-EX021	Borrow Excavation, AH, FME, Class B9-6	4,769.000	CY	41.00	45.00	
0050	203-G001	Excess Excavation, FM, AH	1,000.000	CY	15.00	32.00	
0060	203-H001	Surplus Excavation, FM, AH	1,500.000	CY	20.50	20.00	
0070	209-A005	Geotextile Stabilization, Type V, Non-Woven	4,419.000	SY	3.25	3.50	
0080	213-C001	Superphosphate	2.000	TON	850.00	250.00	
0090	220-A001	Insect Pest Control	4.000	ACRE	30.00	30.00	
0100	223-A001	Mowing	8.000	ACRE	50.00	50.00	
0110	225-A001	Grassing	4.000	ACRE	1,000.00	1,200.00	
0120	225-B001	Agricultural Limestone	2.000	TON	100.00	400.00	
0130	225-C001	Mulch, Vegetative Mulch	7.000	TON	200.00	400.00	
0140	226-A001	Temporary Grassing	4.000	ACRE	850.00	1,200.00	
0150	234-A001	Temporary Silt Fence	2,200.000	LF	4.00	3.50	
0160	237-A002	Wattles, 20"	500.000	LF	6.00	10.00	
0170	246-B002	Rockbags	200.000	LF	9.00	15.00	
0180	403-A002	12.5-mm, MT, Asphalt Pavement	821.000	TON	206.50	195.00	
0190	403-A005	19-mm, MT, Asphalt Pavement	484.000	TON	193.50	190.00	
0200	403-A014	9.5-mm, MT, Asphalt Pavement	984.000	TON	187.00	175.00	
0210	403-C002	19-mm, MT, Asphalt Pavement, Trench Widening	40.000	TON	600.00	350.00	
0220	406-D001	Fine Milling of Bituminous Pavement, All Depths	7,808.000	SY	5.00	7.00	
0230	407-A001	Asphalt for Tack Coat	771.000	GAL	4.25	4.00	
0240	503-C010	Saw Cut, Full Depth	2,047.000	LF	11.00	12.00	
0250	601-B001	Class "B" Structural Concrete, Minor Structures	1.000	CY	1,850.00	3,000.00	
0260	609-D004	Combination Concrete Curb and Gutter Type 2 Modified	453.000	LF	46.00	55.00	

Intersection Improvements on SR 826 at SR 14 & US 61, known as Federal Aid Project No. STBG-0009-02(087) / 106687301 in Sharkey County.					Simmons Erosion Control, Inc.	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,398,840.75					\$1,496,585.10	\$1,684,587.25	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	616-A001	Concrete Median and/or Island Pavement, 10-inch	90.000	SY	115.00	130.00	
0280	616-A004	Concrete Median and/or Island Pavement, 4-inch	278.000	SY	68.00	80.00	
0290	617-A001	Right-of-Way Marker	11.000	EA	165.00	300.00	
0300	618-A001	Maintenance of Traffic	1.000	LS	114,000.00	105,000.00	
0310	619-A1003	Temporary Traffic Stripe, Continuous White, Paint	4,986.000	LF	1.25	5.25	
0320	619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	2,253.000	LF	1.25	5.25	
0330	619-A4003	Temporary Traffic Stripe, Skip Yellow, Paint	2,100.000	LF	1.25	5.25	
0340	619-A5002	Temporary Traffic Stripe, Detail, Paint	2,106.000	LF	1.85	5.25	
0350	619-A6004	Temporary Traffic Stripe, Legend, Paint	188.000	LF	2.50	5.25	
0360	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	12.000	EA	12.50	60.00	
0370	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	56.000	SF	10.00	7.50	
0380	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	839.000	SF	10.00	7.50	
0390	619-D3001	Remove and Reset Signs, All Sizes	5.000	EA	1,500.00	120.00	
0400	619-G4001	Barricades, Type III, Double Faced	72.000	LF	22.25	15.00	
0410	619-G4005	Barricades, Type III, Single Faced	180.000	LF	20.00	15.00	
0420	619-G5001	Free Standing Plastic Drums	130.000	EA	51.50	30.00	
0430	619-G7001	Warning Lights, Type "B"	6.000	EA	130.00	100.00	
0440	620-A001	Mobilization	1.000	LS	135,000.00	190,000.00	
0450	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	1.000	MI	6,175.00	16,500.00	
0460	626-D001	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	1.000	MI	3,700.00	2,750.00	
0470	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	1.000	MI	6,175.00	5,500.00	
0480	626-G004	Thermoplastic Double Drop Detail Stripe, White	2,896.000	LF	4.00	5.50	
0490	626-H002	Thermoplastic Double Drop Legend, White	342.000	LF	10.00	16.50	
0500	627-J001	Two-Way Clear Reflective High Performance Raised Markers	162.000	EA	13.00	33.00	
0510	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	60.000	EA	13.00	33.00	
0520	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	75.000	SF	32.25	17.00	

Intersection Improvements on SR 826 at SR 14 & US 61, known as Federal Aid Project No. STBG-0009-02(087) / 106687301 in Sharkey County.					Simmons Erosion Control, Inc.	Hemphill Construction Company, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,398,840.75					\$1,496,585.10	\$1,684,587.25	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0530	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	16.000	SF	33.50	16.00	
0540	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	81.000	SF	37.00	18.00	
0550	630-C002	Steel U-Section Posts, 2.0 lb/ft	20.000	LF	22.25	13.00	
0560	630-C003	Steel U-Section Posts, 3.0 lb/ft	105.000	LF	25.00	14.00	
0570	630-K001	Welded & Seamless Steel Pipe Posts, 3 1/2"	45.000	LF	80.50	60.00	
0580	630-K003	Welded & Seamless Steel Pipe Posts, 4"	15.000	LF	93.00	66.00	
0590	699-A001	Roadway Construction Stakes	1.000	LS	52,000.00	10,000.00	
0600	907-626-Z003	Thermoplastic Legend, White, 6" Equivalent Length, 40-mil. min.	1,080.000	LF	1.95	11.00	
0610	304-F001	3/4" and Down Crushed Stone Base	2,842.000	TON			
0620	304-F002	Size 610 Crushed Stone Base	2,842.000	TON			
0630	304-F003	Size 825B Crushed Stone Base	2,842.000	TON	65.00	85.00	