

Call 07 Mill & Overlay approximately 6 miles of US 51 from Geeslin Corner to the Yalobusha County Line, known as Federal Aid Project No. NH-2901-00(038) / 108270301 in Grenada County.

Q1. What is the depth of the existing asphalt pavement over the concrete pavement?

A1. It is estimated that the existing asphalt thickness ranges from 3-4” and variable near the northern half of the project to 5-7.5” and variable near the southern half of the project.

Q2. Did MDOT take core samples of the existing road base? If so, what is the existing thickness of asphalt and concrete?

A2. See Answer No. 1 for asphalt thicknesses. It is estimated that the concrete thickness is 6”.

Q3. I am wondering if the saw cutting is for concrete or asphalt and how deep it is.

A3. See above answers.