

Call 11 Scrub Seal & Overlay approximately 6 miles of SR 14 from SR 35 to 0.75 miles west of SR 19, known as State Project No. MP-2014-04(008) / 307902301 in Attala County.

- Q1. Is there a leveling table or schedule that MDOT can provide that list locations and dimensions of areas MDOT will require 3/4" and variable 9.5mm, ST leveling? Proposal only states that approx. 50 tons per mile was included to perform this work.
- A1. There is no table. This asphalt is set up to be used as directed by the Engineer in areas where improvement in the ride quality is needed.