

Mill & Overlay approximately 6 miles of US 51 from Geeslin Corner to the Yalobusha County Line, known as Federal Aid Project No. NH-2901-00(038) / 108270301 in Grenada County.					Lehman-Roberts Company		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,532,762.00					\$4,221,464.50		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-B007	Removal of Asphalt Pavement, All Depths	1,026.000	SY	150.00		
0020	202-B069	Removal of Concrete Pavement w/ Variable Depth Overlay	1,234.000	SY	150.00		
0030	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	1,095.000	LF	12.00		
0040	202-B215	Removal of Sign Including Post & Footing	77.000	EA	115.00		
0050	203-G001	Excess Excavation, FM, AH	100.000	CY	4.00		
0060	304-B004	Granular Material, Class 5, Group D	2,750.000	TON	55.00		
0070	403-A006	19-mm, ST, Asphalt Pavement	1,475.000	TON	190.00		
0080	403-A015	9.5-mm, ST, Asphalt Pavement	8,700.000	TON	165.00		
0090	403-B012	9.5-mm, ST, Asphalt Pavement, Leveling	650.000	TON	180.00		
0100	403-C003	19-mm, ST, Asphalt Pavement, Trench Widening	1,100.000	TON	160.00		
0110	406-D001	Fine Milling of Bituminous Pavement, All Depths	98,600.000	SY	4.90		
0120	407-A001	Asphalt for Tack Coat	21,000.000	GAL	5.00		
0130	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	17,500.000	LF	3.50		
0140	423-A001	Rumble Strips, Ground In	12.000	MI	275.00		
0150	503-C010	Saw Cut, Full Depth	5,260.000	LF	5.75		
0160	606-B002	Guard Rail, Class A, Type 1, 'W' Beam	800.000	LF	59.00		
0170	606-E001	Guard Rail, Terminal End Section	8.000	EA	3,800.00		
0180	618-A001	Maintenance of Traffic	1.000	LS	300,000.00		
0190	618-B001	Additional Construction Signs	1.000	SF	10.00		
0200	619-A1001	Temporary Traffic Stripe, Continuous White	34.000	MI	1,900.00		
0210	619-A2001	Temporary Traffic Stripe, Continuous Yellow	12.000	MI	1,900.00		
0220	619-A4002	Temporary Traffic Stripe, Skip Yellow	15.000	MI	1,900.00		
0230	619-A5001	Temporary Traffic Stripe, Detail	3,400.000	LF	0.35		
0240	619-A6002	Temporary Traffic Stripe, Legend	1,375.000	LF	1.70		
0250	620-A001	Mobilization	1.000	LS	275,000.00		
0260	626-B002	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	12.000	MI	7,900.00		

Mill & Overlay approximately 6 miles of US 51 from Geeslin Corner to the Yalobusha County Line, known as Federal Aid Project No. NH-2901-00(038) / 108270301 in Grenada County.					Lehman-Roberts Company		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,532,762.00					\$4,221,464.50		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	626-D001	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	5.000	MI	4,200.00		
0280	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	4.000	MI	7,900.00		
0290	626-G004	Thermoplastic Double Drop Detail Stripe, White	2,400.000	LF	3.50		
0300	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	1,000.000	LF	3.50		
0310	626-H001	Thermoplastic Double Drop Legend, White	25.000	SF	17.00		
0320	626-H002	Thermoplastic Double Drop Legend, White	1,375.000	LF	5.00		
0330	627-J001	Two-Way Clear Reflective High Performance Raised Markers	250.000	EA	10.00		
0340	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	615.000	EA	10.00		
0350	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	107.000	SF	19.00		
0360	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	228.000	SF	21.00		
0370	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	148.000	SF	20.00		
0380	630-C001	Square Tube Posts, 4.0 lb/ft	90.000	LF	68.00		
0390	630-C005	Square Tube Posts, 2.0 lb/ft	1,011.000	LF	15.00		
0400	630-F006	Delineators, Guard Rail, White	54.000	EA	23.00		
0410	630-G004	Type 3 Object Markers, OM-3R or OM-3L	56.000	EA	89.00		
0420	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	305.00		
0430	304-F001	3/4" and Down Crushed Stone Base	175.000	TON	71.00		
0440	304-F002	Size 610 Crushed Stone Base	175.000	TON			
0450	304-F003	Size 825B Crushed Stone Base	175.000	TON			