

Mill & Overlay approximately 9 miles of SR 309 from the end of the 4-Lane section north of I-22 to the Tennessee State Line, known as State Project No. MP-2309-47(008) / 307901301 in Marshall County.					Standard Construction Company, Inc.	Lehman-Roberts Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,538,467.85					\$4,840,329.40	\$4,940,196.00	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	202-B007	Removal of Asphalt Pavement, All Depths	1,087.000	SY	74.40	33.00	
0020	202-B215	Removal of Sign Including Post & Footing	82.000	EA	55.00	52.75	
0030	203-G001	Excess Excavation, FM, AH	48.000	CY	105.00	50.00	
0040	304-B004	Granular Material, Class 5, Group D	4,900.000	TON	45.00	67.40	
0050	403-A005	19-mm, MT, Asphalt Pavement	750.000	TON	225.00	197.00	
0060	403-A014	9.5-mm, MT, Asphalt Pavement	13,000.000	TON	158.80	153.00	
0070	403-B011	9.5-mm, MT, Asphalt Pavement, Leveling	1,075.000	TON	175.00	195.50	
0080	406-D001	Fine Milling of Bituminous Pavement, All Depths	150,350.000	SY	3.55	5.00	
0090	407-A001	Asphalt for Tack Coat	34,850.000	GAL	5.00	5.25	
0100	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	56.000	LF	18.50	11.00	
0110	423-A001	Rumble Strips, Ground In	13.000	MI	1,400.00	675.00	
0120	503-C010	Saw Cut, Full Depth	3,200.000	LF	14.25	1.25	
0130	613-D005	Adjustment of Manhole	11.000	EA	750.00	250.00	
0140	618-A001	Maintenance of Traffic	1.000	LS	305,000.00	255,000.00	
0150	618-B001	Additional Construction Signs	1.000	SF	10.00	10.00	
0160	619-A1001	Temporary Traffic Stripe, Continuous White	31.000	MI	1,760.00	1,690.00	
0170	619-A2001	Temporary Traffic Stripe, Continuous Yellow	22.000	MI	1,760.00	1,690.00	
0180	619-A4002	Temporary Traffic Stripe, Skip Yellow	10.000	MI	1,760.00	1,690.00	
0190	619-A5001	Temporary Traffic Stripe, Detail	465.000	LF	0.40	1.00	
0200	619-A6002	Temporary Traffic Stripe, Legend	454.000	LF	1.70	2.00	
0210	620-A001	Mobilization	1.000	LS	400,000.00	430,000.00	
0220	626-B002	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	16.000	MI	7,480.00	7,200.00	
0230	626-D001	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	5.000	MI	3,740.00	3,600.00	
0240	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	11.000	MI	7,480.00	7,200.00	
0250	626-G004	Thermoplastic Double Drop Detail Stripe, White	158.000	LF	3.30	4.00	
0260	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	307.000	LF	3.30	4.00	

Mill & Overlay approximately 9 miles of SR 309 from the end of the 4-Lane section north of I-22 to the Tennessee State Line, known as State Project No. MP-2309-47(008) / 307901301 in Marshall County.					Standard Construction Company, Inc.	Lehman-Roberts Company	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,538,467.85					\$4,840,329.40	\$4,940,196.00	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	626-H001	Thermoplastic Double Drop Legend, White	213.000	SF	13.20	13.00	
0280	626-H002	Thermoplastic Double Drop Legend, White	454.000	LF	4.40	5.00	
0290	627-J001	Two-Way Clear Reflective High Performance Raised Markers	731.000	EA	9.90	9.50	
0300	627-K001	Red-Clear Reflective High Performance Raised Markers	53.000	EA	9.90	9.50	
0310	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,570.000	EA	9.90	9.50	
0320	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	220.000	SF	33.00	32.00	
0330	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	36.000	SF	37.00	36.00	
0340	630-A005	Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness	200.000	SF	35.00	34.00	
0350	630-C005	Square Tube Posts, 2.0 lb/ft	960.000	LF	31.00	30.00	
0360	630-G004	Type 3 Object Markers, OM-3R or OM-3L	35.000	EA	165.00	159.00	
0370	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	440.00	232.25	
0380	907-632-B001	Remove and Replace Existing Traffic Signal Cabinet Assembly, Type I Cabinet, Type 1 Controller	1.000	EA	19,550.00	18,750.00	
0390	907-632-C001	Modify Existing Traffic Signal Cabinet Assembly	1.000	EA	3,450.00	3,281.00	
0400	907-641-A002	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2	8.000	EA	10,925.00	10,387.25	
0410	907-641-B002	Signal Advanced Radar Vehicle Detection Sensor, Type 2	2.000	EA	10,925.00	10,500.00	
0420	907-641-D001	Radar Vehicle Detection Cable	1,600.000	LF	2.30	2.25	
0430	907-899-A001	Railway-Highway Provisions	1.000	LS	18,500.00	35,000.00	
0440	304-F001	3/4" and Down Crushed Stone Base	100.000	TON			
0450	304-F002	Size 610 Crushed Stone Base	100.000	TON	253.00	55.00	
0460	304-F003	Size 825B Crushed Stone Base	100.000	TON			