

**Call 04 Bridge Replacement on SR 18 over Dabbs Creek (Bridge No. 83.4), known as Federal Aid Project No. BR-0039-02(047) / 106979301 in Rankin County.**

- Q1. Sheet 8006 (plan view) calls for a LP1 bearing pad that is 1.8125" thick per Sheet 13. However, Sheet 13 (Sheet 8015) shows the LP1 bearing pad @ 1.875" thick. Please clarify.
- A1. The 1.8125" thickness shown on Sheet 8006 represents the compressed pad thickness, and the 1.875" thickness shown on Sheet 8015 represents the nominal pad thickness. See Neoprene Pad Thickness Table on Sheet 8012.
- Q2. Can we request for as built plans on existing bridge?
- A2. As-built plans can be downloaded at the following link: <https://file-exchange.mdot.state.ms.us/dl/?f=902961637ad36bf23674413c2bdb75dfd36eb1a1>