

| Interchange Improvements of SR 25 / I-22 from the beginning of the 4-Lane Section south of Fulton to just north of Country Club Road, known as Federal Aid Project No. NHPP-0040-02(038) / 107781302 in Itawamba County. | | | | | Cook & Son, LLC | Century Construction Group, Inc. | Phillips Contracting Co., Inc. |
|--|-----------|---|------------|-------|-----------------|----------------------------------|--------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,453,929.30 | | | | | \$6,543,529.80 | \$7,539,348.43 | \$8,653,764.35 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0010 | 201-B001 | Clearing and Grubbing | 2.000 | ACRE | 2,500.00 | 4,904.45 | 20,000.00 |
| 0020 | 202-B006 | Removal of Asphalt Paved Shoulders, All Depths For Ramp Shoulders | 667.000 | SY | 10.00 | 17.60 | 30.00 |
| 0030 | 202-B007 | Removal of Asphalt Pavement, All Depths | 2,740.000 | SY | 10.00 | 10.45 | 30.00 |
| 0040 | 202-B059 | Removal of Concrete Median & Island Pavement, All Depths | 1,565.000 | SY | 25.00 | 30.00 | 32.50 |
| 0050 | 202-B063 | Removal of Concrete Paved Ditch | 230.000 | SY | 10.00 | 30.00 | 32.50 |
| 0060 | 202-B092 | Removal of Curb, All Types | 2,570.000 | LF | 20.00 | 20.00 | 19.50 |
| 0070 | 202-B165 | Removal of Inlets, All Sizes | 5.000 | EA | 1,500.00 | 5,000.00 | 1,500.00 |
| 0080 | 202-B191 | Removal of Pipe, 8" And Above | 12.000 | LF | 20.00 | 75.00 | 50.00 |
| 0090 | 202-B217 | Removal of Sign Post and Footing | 21.000 | EA | 175.00 | 188.16 | 125.00 |
| 0100 | 202-B229 | Removal of Soil Cement, All Depths | 1,244.000 | SY | 20.00 | 18.88 | 15.00 |
| 0110 | 202-B239 | Removal of Traffic Signal | 3.000 | EA | 3,850.00 | 5,411.57 | 4,850.00 |
| 0120 | 202-B240 | Removal of Traffic Stripe | 10,000.000 | LF | 3.00 | 3.23 | 3.60 |
| 0130 | 203-EX020 | Borrow Excavation, AH, FME, Class B9 | 22,149.000 | CY | 14.00 | 20.46 | 23.40 |
| 0140 | 203-G001 | Excess Excavation, FM, AH | 5,000.000 | CY | 10.00 | 16.32 | 24.40 |
| 0150 | 206-A001 | Structure Excavation | 258.000 | CY | 25.00 | 12.81 | 25.00 |
| 0160 | 206-B001 | Select Material for Undercuts, Contractor Furnished, FM | 100.000 | CY | 25.00 | 44.86 | 23.40 |
| 0170 | 209-A005 | Geotextile Stabilization, Type V, Non-Woven | 16,720.000 | SY | 2.50 | 3.04 | 3.00 |
| 0180 | 211-B001 | Topsoil for Slope Treatment, Contractor Furnished | 1,000.000 | CY | 20.00 | 39.26 | 30.00 |
| 0190 | 213-C001 | Superphosphate | 5.000 | TON | 1,200.00 | 1,290.24 | 1,420.00 |
| 0200 | 216-A001 | Solid Sodding | 344.000 | SY | 10.00 | 10.75 | 12.00 |
| 0210 | 219-A001 | Watering | 7.000 | KGAL | 20.00 | 20.00 | 20.00 |
| 0220 | 220-A001 | Insect Pest Control | 10.000 | ACRE | 30.00 | 30.00 | 30.00 |
| 0230 | 221-A001 | Concrete Paved Ditch | 59.000 | CY | 800.00 | 1,000.00 | 765.00 |
| 0240 | 223-A001 | Mowing | 20.000 | ACRE | 50.00 | 50.00 | 50.00 |
| 0250 | 225-A001 | Grassing | 10.000 | ACRE | 2,500.00 | 2,688.00 | 2,960.00 |
| 0260 | 225-B001 | Agricultural Limestone | 5.000 | TON | 250.00 | 268.80 | 300.00 |

| Interchange Improvements of SR 25 / I-22 from the beginning of the 4-Lane Section south of Fulton to just north of Country Club Road, known as Federal Aid Project No. NHPP-0040-02(038) / 107781302 in Itawamba County. | | | | | Cook & Son, LLC | Century Construction Group, Inc. | Phillips Contracting Co., Inc. |
|--|------------|---|-----------|-------|-----------------|----------------------------------|--------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,453,929.30 | | | | | \$6,543,529.80 | \$7,539,348.43 | \$8,653,764.35 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0270 | 225-C001 | Mulch, Vegetative Mulch | 20.000 | TON | 250.00 | 268.80 | 300.00 |
| 0280 | 226-A001 | Temporary Grassing | 10.000 | ACRE | 1,500.00 | 1,612.80 | 1,800.00 |
| 0290 | 237-A002 | Wattles, 20" | 320.000 | LF | 8.00 | 8.60 | 9.50 |
| 0300 | 239-A001 | Temporary Slope Drains | 500.000 | LF | 16.00 | 18.49 | 20.00 |
| 0310 | 245-A001 | Silt Dike | 200.000 | LF | 10.00 | 10.75 | 12.00 |
| 0320 | 246-B002 | Rockbags | 200.000 | LF | 10.00 | 10.75 | 12.00 |
| 0330 | 249-A001 | Riprap for Erosion Control | 10.000 | TON | 100.00 | 104.44 | 75.00 |
| 0340 | 249-B001 | Remove and Reset Riprap | 30.000 | CY | 100.00 | 55.06 | 100.00 |
| 0350 | 304-B001 | Granular Material, Class 3, Group C | 5,254.000 | TON | 24.00 | 45.00 | 60.00 |
| 0360 | 403-A001 | 12.5-mm, HT, Asphalt Pavement | 708.000 | TON | 260.00 | 279.55 | 325.00 |
| 0370 | 403-A004 | 19-mm, HT, Asphalt Pavement | 1,063.000 | TON | 260.00 | 279.55 | 325.00 |
| 0380 | 403-A006 | 19-mm, ST, Asphalt Pavement | 1,640.000 | TON | 225.00 | 241.92 | 282.50 |
| 0390 | 403-A013 | 9.5-mm, HT, Asphalt Pavement | 4,414.000 | TON | 190.00 | 204.29 | 237.50 |
| 0400 | 406-B001 | Cold Milling of Concrete Pavement, All Depths Bridge End Pavement | 320.000 | SY | 6.00 | 6.81 | 87.00 |
| 0410 | 406-D001 | Fine Milling of Bituminous Pavement, All Depths | 5,500.000 | SY | 6.00 | 9.67 | 8.50 |
| 0420 | 407-A001 | Asphalt for Tack Coat | 4,770.000 | GAL | 5.00 | 5.38 | 6.25 |
| 0430 | 503-C010 | Saw Cut, Full Depth | 3,000.000 | LF | 10.00 | 5.38 | 7.00 |
| 0440 | 601-B001 | Class "B" Structural Concrete, Minor Structures | 30.000 | CY | 1,750.00 | 3,500.00 | 1,881.00 |
| 0450 | 602-A001 | Reinforcing Steel | 2,068.000 | LBS | 2.50 | 3.00 | 11.25 |
| 0460 | 603-ALT003 | 18" Type A Alternate Pipe | 500.000 | LF | 40.00 | 66.97 | 95.00 |
| 0470 | 603-CA011 | 18" Reinforced Concrete Pipe, Class III | 16.000 | LF | 125.00 | 152.53 | 250.00 |
| 0480 | 603-CA076 | 48" Reinforced Concrete Pipe, Class III | 8.000 | LF | 219.00 | 305.45 | 405.00 |
| 0490 | 603-CB003 | 18" Reinforced Concrete End Section | 2.000 | EA | 1,150.00 | 2,358.19 | 2,350.00 |
| 0500 | 603-CB008 | 48" Reinforced Concrete End Section | 1.000 | EA | 3,100.00 | 3,634.78 | 3,570.00 |
| 0510 | 603-CE002 | 22" x 13" Concrete Arch Pipe, Class A III | 8.000 | LF | 112.00 | 206.06 | 275.00 |
| 0520 | 604-A001 | Castings | 1,457.000 | LBS | 4.00 | 6.00 | 5.00 |

| Interchange Improvements of SR 25 / I-22 from the beginning of the 4-Lane Section south of Fulton to just north of Country Club Road, known as Federal Aid Project No. NHPP-0040-02(038) / 107781302 in Itawamba County. | | | | | Cook & Son, LLC | Century Construction Group, Inc. | Phillips Contracting Co., Inc. |
|--|-----------|--|------------|-------|-----------------|----------------------------------|--------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,453,929.30 | | | | | \$6,543,529.80 | \$7,539,348.43 | \$8,653,764.35 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0530 | 604-B001 | Gratings | 1,881.000 | LBS | 4.00 | 5.00 | 5.00 |
| 0540 | 609-D004 | Combination Concrete Curb and Gutter Type 2 Modified | 4,854.000 | LF | 26.00 | 29.08 | 33.90 |
| 0550 | 609-D012 | Combination Concrete Curb and Gutter Type 3A Modified | 3,918.000 | LF | 26.00 | 29.08 | 33.90 |
| 0560 | 616-A001 | Concrete Median and/or Island Pavement, 10-inch | 503.000 | SY | 120.00 | 155.00 | 153.80 |
| 0570 | 616-A004 | Concrete Median and/or Island Pavement, 4-inch | 3,171.000 | SY | 58.00 | 81.00 | 85.90 |
| 0580 | 618-A001 | Maintenance of Traffic | 1.000 | LS | 655,000.00 | 400,000.00 | 700,000.00 |
| 0590 | 619-A1002 | Temporary Traffic Stripe, Continuous White | 14,911.000 | LF | 1.00 | 1.08 | 1.20 |
| 0600 | 619-A1005 | Temporary Traffic Stripe, Continuous White, Type 1 Tape | 1,125.000 | LF | 3.00 | 3.23 | 3.60 |
| 0610 | 619-A2002 | Temporary Traffic Stripe, Continuous Yellow | 16,520.000 | LF | 1.00 | 1.08 | 1.20 |
| 0620 | 619-A2006 | Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape | 1,750.000 | LF | 3.00 | 3.23 | 3.60 |
| 0630 | 619-A5001 | Temporary Traffic Stripe, Detail | 46,810.000 | LF | 1.00 | 1.08 | 1.20 |
| 0640 | 619-A6001 | Temporary Traffic Stripe, Legend | 1,390.000 | SF | 2.50 | 2.69 | 3.00 |
| 0650 | 619-A6002 | Temporary Traffic Stripe, Legend | 2,864.000 | LF | 1.50 | 1.61 | 1.80 |
| 0660 | 619-C6001 | Red-Clear Reflective High Performance Raised Marker | 745.000 | EA | 8.00 | 8.60 | 9.50 |
| 0670 | 619-D1001 | Standard Roadside Construction Signs, Less than 10 Square Feet | 140.000 | SF | 10.00 | 10.75 | 10.00 |
| 0680 | 619-D2001 | Standard Roadside Construction Signs, 10 Square Feet or More | 1,010.000 | SF | 10.00 | 10.75 | 10.00 |
| 0690 | 619-F1001 | Concrete Median Barrier, Precast | 972.000 | LF | 65.00 | 75.00 | 100.00 |
| 0700 | 619-G4001 | Barricades, Type III, Double Faced | 48.000 | LF | 24.00 | 25.80 | 22.50 |
| 0710 | 619-G4005 | Barricades, Type III, Single Faced | 156.000 | LF | 24.00 | 25.80 | 20.00 |
| 0720 | 619-G5001 | Free Standing Plastic Drums | 475.000 | EA | 60.00 | 64.51 | 45.00 |
| 0730 | 619-G7001 | Warning Lights, Type "B" | 19.000 | EA | 200.00 | 215.04 | 160.00 |
| 0740 | 619-H1001 | Traffic Signals | 1.000 | LS | 51,780.00 | 66,847.33 | 11,900.00 |
| 0750 | 619-J1003 | Impact Attenuator, 50 MPH | 2.000 | EA | 6,500.00 | 6,988.80 | 11,900.00 |
| 0760 | 619-J2003 | Impact Attenuator, 50 MPH, Replacement Package | 2.000 | EA | 3,500.00 | 3,763.20 | 3,125.00 |
| 0770 | 620-A001 | Mobilization | 1.000 | LS | 764,045.90 | 750,000.00 | 800,000.00 |
| 0780 | 626-A002 | 6" Thermoplastic Double Drop Traffic Stripe, Skip White | 6,259.000 | LF | 1.00 | 1.08 | 1.20 |

| Interchange Improvements of SR 25 / I-22 from the beginning of the 4-Lane Section south of Fulton to just north of Country Club Road, known as Federal Aid Project No. NHPP-0040-02(038) / 107781302 in Itawamba County. | | | | | Cook & Son, LLC | Century Construction Group, Inc. | Phillips Contracting Co., Inc. |
|--|--------------|---|------------|-------|-----------------|----------------------------------|--------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,453,929.30 | | | | | \$6,543,529.80 | \$7,539,348.43 | \$8,653,764.35 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0790 | 626-C001 | 6" Thermoplastic Double Drop Edge Stripe, Continuous White | 6,274.000 | LF | 2.00 | 2.15 | 2.40 |
| 0800 | 626-D002 | 6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow | 80.000 | LF | 1.00 | 1.08 | 1.20 |
| 0810 | 626-E002 | 6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow | 2,394.000 | LF | 2.00 | 2.15 | 2.40 |
| 0820 | 626-F002 | 6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow | 4,629.000 | LF | 2.00 | 2.15 | 2.40 |
| 0830 | 626-G004 | Thermoplastic Double Drop Detail Stripe, White | 17,489.000 | LF | 3.00 | 3.23 | 3.60 |
| 0840 | 626-G005 | Thermoplastic Double Drop Detail Stripe, Yellow | 4,100.000 | LF | 3.00 | 3.23 | 3.60 |
| 0850 | 626-H001 | Thermoplastic Double Drop Legend, White | 1,302.000 | SF | 10.00 | 10.75 | 12.00 |
| 0860 | 626-H002 | Thermoplastic Double Drop Legend, White | 2,144.000 | LF | 4.00 | 4.30 | 4.80 |
| 0870 | 627-J001 | Two-Way Clear Reflective High Performance Raised Markers | 31.000 | EA | 9.00 | 9.68 | 10.70 |
| 0880 | 627-K001 | Red-Clear Reflective High Performance Raised Markers | 445.000 | EA | 9.00 | 9.68 | 10.70 |
| 0890 | 627-L001 | Two-Way Yellow Reflective High Performance Raised Markers | 95.000 | EA | 9.00 | 9.68 | 10.70 |
| 0900 | 630-A001 | Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness | 104.000 | SF | 19.00 | 20.43 | 22.50 |
| 0910 | 630-A003 | Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness | 407.000 | SF | 21.00 | 22.58 | 27.50 |
| 0920 | 630-A005 | Standard Roadside Signs, Sheet Aluminum, 0.1" Thickness | 33.000 | SF | 20.00 | 21.50 | 25.00 |
| 0930 | 630-B002 | Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted | 219.000 | SF | 36.00 | 38.71 | 40.00 |
| 0940 | 630-C001 | Square Tube Posts, 4.0 lb/ft | 282.000 | LF | 65.00 | 69.89 | 100.00 |
| 0950 | 630-C005 | Square Tube Posts, 2.0 lb/ft | 231.000 | LF | 14.00 | 15.05 | 75.00 |
| 0960 | 630-D008 | Structural Steel Beams, W6 x 9 | 178.000 | LF | 65.00 | 69.89 | 170.00 |
| 0970 | 635-A059 | Traffic Signal Head, Type 1 | 22.000 | EA | 1,070.00 | 1,150.46 | 1,340.00 |
| 0980 | 635-A061 | Traffic Signal Head, Type 2 | 2.000 | EA | 1,090.00 | 1,171.97 | 1,370.00 |
| 0990 | 635-A065 | Traffic Signal Head, Type 2 FYA | 6.000 | EA | 1,910.00 | 2,053.63 | 2,390.00 |
| 1000 | 635-A070 | Traffic Signal Head, Type 3 | 6.000 | EA | 1,565.00 | 1,682.69 | 1,960.00 |
| 1010 | 699-A001 | Roadway Construction Stakes | 1.000 | LS | 40,000.00 | 325,000.00 | 200,000.00 |
| 1020 | 815-F002 | Sediment Control Stone | 50.000 | TON | 125.00 | 87.40 | 100.00 |
| 1030 | 907-234-A001 | Temporary Silt Fence | 10,000.000 | LF | 4.00 | 4.30 | 4.75 |
| 1040 | 907-234-D001 | Inlet Siltation Guard | 10.000 | EA | 650.00 | 698.88 | 770.00 |

| Interchange Improvements of SR 25 / I-22 from the beginning of the 4-Lane Section south of Fulton to just north of Country Club Road, known as Federal Aid Project No. NHPP-0040-02(038) / 107781302 in Itawamba County. | | | | | Cook & Son, LLC | Century Construction Group, Inc. | Phillips Contracting Co., Inc. |
|--|---------------|--|-----------|-------|-----------------|----------------------------------|--------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,453,929.30 | | | | | \$6,543,529.80 | \$7,539,348.43 | \$8,653,764.35 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 1050 | 907-619-E3001 | Changeable Message Sign | 2.000 | EA | 10,000.00 | 10,752.00 | 12,000.00 |
| 1060 | 907-619-M1002 | Smart Work Zone, Portable Queue Trailer | 4.000 | EA | 2,818.75 | 3,030.72 | 20,420.00 |
| 1070 | 907-619-M1003 | Smart Work Zone, Portable Camera Trailer | 1.000 | EA | 4,510.00 | 4,849.15 | 28,775.00 |
| 1080 | 907-619-M1004 | Smart Work Zone, Portable Message Board Trailer | 3.000 | EA | 2,255.00 | 2,424.58 | 21,350.00 |
| 1090 | 907-619-M2001 | Smart Work Zone, Portable Queue Trailer, Operational Month | 8.000 | EA | 2,316.60 | 2,490.81 | 2,785.00 |
| 1100 | 907-619-M2002 | Smart Work Zone, Portable Camera Trailer, Operational Month | 8.000 | EA | 870.10 | 935.53 | 490.00 |
| 1110 | 907-619-M2003 | Smart Work Zone, Portable Message Board Trailer, Operational Month | 8.000 | EA | 3,382.50 | 3,636.86 | 1,750.00 |
| 1120 | 907-619-M3002 | Smart Work Zone, System Monitoring, Operational Month | 8.000 | EA | 1,980.00 | 2,128.90 | 3,715.00 |
| 1130 | 907-632-A010 | Solid State Traffic Cabinet Assembly, Type IV Cabinet, Type 1 Controller | 4.000 | EA | 24,725.00 | 26,584.32 | 31,000.00 |
| 1140 | 907-632-J001 | Power Service Pedestal | 4.000 | EA | 9,125.00 | 9,811.20 | 11,400.00 |
| 1150 | 907-633-A001 | Uninterruptable Power Supply | 4.000 | EA | 5,475.00 | 5,886.72 | 6,850.00 |
| 1160 | 907-634-A050 | Traffic Signal Equipment Pole, Type II(L), 30' Shaft, 70' Arm | 1.000 | EA | 30,260.00 | 32,535.55 | 37,900.00 |
| 1162 | 907-634-A052 | Traffic Signal Equipment Pole, Type II(L), 30' Shaft, 80' Arm | 1.000 | EA | 39,845.00 | 42,841.34 | 49,850.00 |
| 1180 | 907-634-A081 | Traffic Signal Equipment Pole, Type II, 17' Shaft, 35' Arm | 1.000 | EA | 14,460.00 | 15,547.39 | 18,075.00 |
| 1190 | 907-634-A083 | Traffic Signal Equipment Pole, Type II, 17' Shaft, 45' Arm | 3.000 | EA | 15,245.00 | 16,391.42 | 19,060.00 |
| 1200 | 907-634-A088 | Traffic Signal Equipment Pole, Type II, 17' Shaft, 60' Arm | 1.000 | EA | 23,235.00 | 24,982.27 | 29,050.00 |
| 1220 | 907-634-A090 | Traffic Signal Equipment Pole, Type II, 17' Shaft, 70' Arm | 2.000 | EA | 25,580.00 | 27,503.62 | 32,000.00 |
| 1222 | 907-634-A130 | Traffic Signal Equipment Pole, Type II, 30' Shaft, 65' Arm | 1.000 | EA | 31,650.00 | 34,030.08 | 39,570.00 |
| 1230 | 907-634-A257 | Traffic Signal Equipment Pole, Type III(L), 30' Shaft, 40' & 55' Arm | 1.000 | EA | 30,220.00 | 32,492.54 | 37,800.00 |
| 1240 | 907-634-A394 | Traffic Signal Equipment Pole, Type III, 17' Shaft, 45' & 65' Arm | 1.000 | EA | 30,890.00 | 33,212.93 | 38,625.00 |
| 1250 | 907-634-C001 | Pole Foundations, Class "B" Concrete | 34.000 | CY | 1,125.00 | 1,209.60 | 1,410.00 |
| 1260 | 907-634-D002 | Slip Casing, 30" Diameter | 20.000 | LF | 28.00 | 30.11 | 35.00 |
| 1270 | 907-634-D003 | Slip Casing, 36" Diameter | 24.000 | LF | 34.00 | 36.56 | 42.50 |
| 1280 | 907-636-B016 | Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 8 Conductor | 3,675.000 | LF | 3.60 | 3.87 | 4.50 |
| 1290 | 907-636-B027 | Electric Cable, Underground in Conduit, IMSA 20-1, AWG 8, 2 Conductor | 400.000 | LF | 3.60 | 3.87 | 4.50 |
| 1300 | 907-637-A002 | Pullbox Enclosure, Type 2 | 10.000 | EA | 1,410.00 | 1,516.03 | 1,770.00 |

| Interchange Improvements of SR 25 / I-22 from the beginning of the 4-Lane Section south of Fulton to just north of Country Club Road, known as Federal Aid Project No. NHPP-0040-02(038) / 107781302 in Itawamba County. | | | | | Cook & Son, LLC | Century Construction Group, Inc. | Phillips Contracting Co., Inc. |
|--|--------------|--|-----------|-------|-----------------|----------------------------------|--------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$7,453,929.30 | | | | | \$6,543,529.80 | \$7,539,348.43 | \$8,653,764.35 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 1310 | 907-637-A003 | Pullbox Enclosure, Type 3 | 6.000 | EA | 1,810.00 | 1,946.11 | 2,270.00 |
| 1320 | 907-637-C028 | Traffic Signal Conduit, Underground, Type 4, 2" | 388.000 | LF | 14.60 | 15.70 | 18.25 |
| 1330 | 907-637-C030 | Traffic Signal Conduit, Underground, Type 4, 3" | 192.000 | LF | 18.40 | 19.78 | 23.00 |
| 1340 | 907-637-D003 | Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3" | 1,030.000 | LF | 16.20 | 17.42 | 20.25 |
| 1350 | 907-639-B001 | Type 1 Optical Detector | 14.000 | EA | 1,020.00 | 1,096.70 | 1,275.00 |
| 1360 | 907-639-C001 | Type 1 Optical Detector Cable | 3,015.000 | LF | 2.35 | 2.53 | 3.00 |
| 1370 | 907-639-D001 | Multimode Phase Selector | 4.000 | EA | 3,525.00 | 3,790.08 | 4,410.00 |
| 1380 | 907-641-A002 | Signal Stop Bar Radar Vehicle Detection Sensor, Type 2 | 14.000 | EA | 8,700.00 | 9,354.24 | 10,875.00 |
| 1390 | 907-641-B002 | Signal Advanced Radar Vehicle Detection Sensor, Type 2 | 8.000 | EA | 9,165.00 | 9,854.21 | 11,460.00 |
| 1400 | 907-641-D001 | Radar Vehicle Detection Cable | 1,525.000 | LF | 15.00 | 16.13 | 18.75 |
| 1410 | 907-650-A002 | On Street Video Equipment, Fixed Type | 6.000 | EA | 2,990.00 | 3,214.85 | 3,740.00 |
| 1420 | 907-650-A003 | On Street Video Equipment, PTZ Type | 6.000 | EA | 5,015.00 | 5,392.13 | 6,270.00 |
| 1430 | 907-653-A001 | Traffic Sign | 60.000 | SF | 115.00 | 123.65 | 144.00 |
| 1440 | 907-662-D002 | Radio Interconnect, Broadband, Short Range | 4.000 | EA | 6,065.00 | 6,521.09 | 7,580.00 |
| 1450 | 907-663-A002 | Network Switch, Type B | 4.000 | EA | 2,725.00 | 2,929.92 | 3,410.00 |
| 1460 | 907-663-D001 | Category 6 Cable, Installed in Conduit | 1,499.000 | LF | 2.05 | 2.20 | 2.60 |
| 1470 | 304-F001 | 3/4" and Down Crushed Stone Base | 6,277.000 | TON | 42.50 | | 52.50 |
| 1480 | 304-F002 | Size 610 Crushed Stone Base | 6,277.000 | TON | | 65.00 | |
| 1490 | 304-F003 | Size 825B Crushed Stone Base | 6,277.000 | TON | | | |
| 1500 | 907-624-A002 | 6" Inverted Profile Thermoplastic Traffic Stripe, Skip White | 747.000 | LF | | | |
| 1510 | 907-624-B002 | 6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White | 747.000 | LF | | | |
| 1520 | 907-624-D002 | 6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow | 747.000 | LF | | | |
| 1530 | 628-G001 | 6" High Performance Cold Plastic Traffic Stripe, Skip White | 747.000 | LF | 9.00 | 9.68 | 10.70 |
| 1540 | 628-H001 | 6" High Performance Cold Plastic Traffic Stripe, Continuous White | 747.000 | LF | 9.00 | 9.68 | 10.70 |
| 1550 | 628-J001 | 6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow | 747.000 | LF | 9.00 | 9.68 | 10.70 |