

Traffic Signal Installation at the intersection of SR 15 and Broad Street, known as Federal Aid Project No. STBG-0022-02(071) / 108899301 in Newton County.					Webster Electric Co., LLC	Powell Construction Services, Inc.	Lewis Electric, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$210,622.20					\$198,577.30	\$215,567.00	\$222,209.00
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	618-A001	Maintenance of Traffic	1.000	LS	13,000.00	9,895.00	5,000.00
0020	620-A001	Mobilization	1.000	LS	18,100.00	29,875.00	21,000.00
0030	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	18.000	SF	59.50	85.00	15.00
0040	630-C001	Square Tube Posts, 4.0 lb/ft	26.000	LF	119.00	70.00	10.00
0050	635-A059	Traffic Signal Head, Type 1	8.000	EA	1,080.00	1,050.00	1,250.00
0060	635-A065	Traffic Signal Head, Type 2 FYA	1.000	EA	1,920.00	1,925.00	2,000.00
0070	647-A001	Removal of Existing Traffic Signal Equipment	1.000	LS	13,250.00	17,565.00	2,500.00
0080	907-632-A007	Solid State Traffic Cabinet Assembly, Type III Cabinet, Type 1 Controller	1.000	EA	22,220.00	22,125.00	26,750.00
0090	907-632-J001	Power Service Pedestal	1.000	EA	10,160.00	6,425.00	4,750.00
0100	907-634-A259	Traffic Signal Equipment Pole, Type III(L), 30' Shaft, 40' & 65' Arm	1.000	EA	33,610.00	34,850.00	52,350.00
0110	907-634-A272	Traffic Signal Equipment Pole, Type III(L), 30' Shaft, 50' & 65' Arm	1.000	EA	33,790.00	35,750.00	52,750.00
0120	907-634-C001	Pole Foundations, Class "B" Concrete	8.000	CY	1,105.00	1,685.00	1,750.00
0130	907-636-B003	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 10, 2 Conductor	200.000	LF	3.00	3.75	5.00
0140	907-636-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 8 Conductor	360.000	LF	3.60	3.50	4.50
0150	907-636-B025	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 6, 3 Conductor	80.000	LF	7.05	10.00	6.50
0160	907-636-D001	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 10, 2 Conductor	60.000	LF	3.00	4.25	5.00
0170	907-636-D008	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG 14, 8 Conductor	252.000	LF	3.60	5.50	4.50
0180	907-637-A002	Pullbox Enclosure, Type 2	1.000	EA	1,555.00	1,450.00	1,750.00
0190	907-637-A003	Pullbox Enclosure, Type 3	1.000	EA	1,830.00	1,985.00	2,150.00
0200	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	40.000	LF	19.00	12.00	10.00
0210	907-637-C030	Traffic Signal Conduit, Underground, Type 4, 3"	55.000	LF	21.50	15.00	12.00
0220	907-637-D003	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3"	330.000	LF	21.50	30.00	25.00
0230	907-641-D001	Radar Vehicle Detection Cable	424.000	LF	3.65	4.00	5.00
0240	907-653-B001	Street Name Sign	45.000	SF	97.00	80.00	125.00
0250	907-663-A001	Network Switch, Type A	1.000	EA	2,445.00	2,875.00	1,750.00
0260	907-663-C001	Cellular Modem	1.000	EA	1,675.00	865.00	1,000.00

Traffic Signal Installation at the intersection of SR 15 and Broad Street, known as Federal Aid Project No. STBG-0022-02(071) / 108899301 in Newton County.				Webster Electric Co., LLC	Powell Construction Services, Inc.	Lewis Electric, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$210,622.20				\$198,577.30	\$215,567.00	\$222,209.00	
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	907-672-A003	Remove and Reset Traffic Signal Equipment	4.000	EA	1,220.00	950.00	575.00

Letting Date: 1/25/2023

Call Number: 02

Page 2 of 2