

Call 06 Bridge Preventive Maintenance on US 45 over Porterville Road / KCS Railroad (Bridge Nos. 103.8A & 103.8B) & on I-59 over Toomsba Creek (Bridge No. 164.6B), known as Federal Aid Project No. STBG-9999-05(394) / 1087773050 & 3051 in Kemper & Lauderdale Counties.

Q1. Can we request the as-builts for this project?

A1. The as-builts can be downloaded from the following link: <https://file-exchange.mdot.state.ms.us/dl/?f=cbb778d78d244085cc2640745bae4b31d0d07623>

Q2. Can MDOT please provide more information regarding Line No. 140 - 907-824-PP007 scope of work? There are 3 CY of Elastomeric Concrete included in the bridge items, but no reference to what this is for. Please advise.

A2. The joints are armored. As per Special Provision 907-823-7, the armor and surrounding concrete should be removed and replaced with Elastomeric Concrete.