

Bridge Replacements on SR 182 at White Creek Canal (Bridge No. 122.1) & Little Black Creek (Bridge No. 122.4), known as Federal Aid Project No. BR-0730-00(003) / 106976301 in Webster County.					Ste-Bil Grading Inc.	Century Construction Group, Inc.	Key, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,813,849.00					\$4,695,105.60	\$5,786,471.00	\$5,909,880.60
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS	100,000.00	100,000.00	103,000.00
0020	202-A001	Removal of Obstructions	1.000	LS	120,000.00	240,000.00	190,000.00
0030	202-B007	Removal of Asphalt Pavement, All Depths	4,296.000	SY	6.00	6.00	5.00
0040	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	740.000	LF	5.00	4.30	3.90
0050	202-B190	Removal of Piling	36.000	EA	500.00	1,020.00	360.00
0060	202-B191	Removal of Pipe, 8" And Above	383.000	LF	12.00	30.00	44.00
0070	203-A001	Unclassified Excavation, FM, AH	7,321.000	CY	6.50	11.75	19.00
0080	203-EX020	Borrow Excavation, AH, FME, Class B9	4,008.000	CY	20.00	26.00	28.00
0090	203-F001	Channel Excavation, FM	850.000	CY	15.00	15.25	19.00
0100	203-G001	Excess Excavation, FM, AH	1,000.000	CY	10.00	14.25	15.00
0110	206-A001	Structure Excavation	1,319.000	CY	25.00	20.75	23.00
0120	206-B001	Select Material for Undercuts, Contractor Furnished, FM	257.000	CY	80.00	139.00	167.00
0130	209-A005	Geotextile Stabilization, Type V, Non-Woven	6,016.000	SY	3.00	3.30	5.00
0140	211-B001	Topsoil for Slope Treatment, Contractor Furnished	780.000	CY	0.01	16.25	1.00
0150	213-C001	Superphosphate	2.000	TON	850.00	1,030.00	944.00
0160	216-A001	Solid Sodding	850.000	SY	6.00	6.10	5.60
0170	217-A001	Ditch Liner	254.000	SY	3.50	3.70	3.40
0180	219-A001	Watering	17.000	KGAL	20.00	20.00	20.00
0190	220-A001	Insect Pest Control	3.000	ACRE	30.00	30.00	30.00
0200	221-A001	Concrete Paved Ditch	75.000	CY	800.00	869.00	1,420.00
0210	225-A001	Grassing	3.000	ACRE	1,250.00	1,060.00	972.00
0220	225-B001	Agricultural Limestone	9.000	TON	400.00	109.00	100.00
0230	225-C001	Mulch, Vegetative Mulch	6.000	TON	300.00	229.00	211.00
0240	226-A001	Temporary Grassing	3.000	ACRE	1,250.00	964.00	889.00
0250	236-A008	Silt Basin, Type D	1.000	EA	5,000.00	9,820.00	5,570.00
0260	237-A002	Wattles, 20"	5,200.000	LF	6.50	4.90	4.50

Bridge Replacements on SR 182 at White Creek Canal (Bridge No. 122.1) & Little Black Creek (Bridge No. 122.4), known as Federal Aid Project No. BR-0730-00(003) / 106976301 in Webster County.					Ste-Bil Grading Inc.	Century Construction Group, Inc.	Key, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,813,849.00					\$4,695,105.60	\$5,786,471.00	\$5,909,880.60
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	239-A001	Temporary Slope Drains	2,657.000	LF	12.00	15.75	5.90
0280	245-A001	Silt Dike	52.000	LF	10.00	24.25	23.00
0290	246-B001	Rockbags	198.000	EA	10.00	12.25	12.00
0300	247-A001	Temporary Stream Diversion	1.000	EA	35,000.00	111,000.00	75,000.00
0310	249-A001	Riprap for Erosion Control	40.000	TON	100.00	119.00	150.00
0320	249-B001	Remove and Reset Riprap	22.000	CY	100.00	77.25	150.00
0330	304-A002	Granular Material, LVM, Class 3, Group C	100.000	CY	55.00	157.00	170.00
0340	304-C001	Granular Material, AEA, Class 3, Group C	341.000	CY	100.00	116.00	133.00
0350	403-A003	12.5-mm, ST, Asphalt Pavement	619.000	TON	213.00	292.00	231.00
0360	403-A006	19-mm, ST, Asphalt Pavement	788.000	TON	220.00	246.00	225.00
0370	403-A015	9.5-mm, ST, Asphalt Pavement	559.000	TON	195.00	308.00	204.00
0380	406-D001	Fine Milling of Bituminous Pavement, All Depths	1,244.000	SY	9.00	12.50	7.50
0390	407-A001	Asphalt for Tack Coat	848.000	GAL	6.60	7.30	5.40
0400	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	78.000	LF	15.00	12.25	12.00
0410	423-A001	Rumble Strips, Ground In	1.000	MI	2,500.00	362.00	334.00
0420	501-K001	Transverse Grooving	24.000	SY	12.00	2.90	2.60
0430	502-A001	Reinforced Cement Concrete Bridge End Pavement	166.000	SY	350.00	386.00	512.00
0440	503-C010	Saw Cut, Full Depth	112.000	LF	15.00	6.10	17.00
0450	601-B001	Class "B" Structural Concrete, Minor Structures	1.000	CY	2,500.00	2,770.00	184.00
0460	603-ALT006	24" Type A Alternate Pipe	40.000	LF	60.00	79.25	74.00
0470	605-AA001	Geotextile for Subsurface Drainage, Type III	44.000	SY	3.00	9.40	1.90
0480	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	80.000	LF	40.00	23.50	25.00
0490	605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	12.000	LF	40.00	28.25	55.00
0500	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	3.000	CY	600.00	304.00	433.00
0510	606-B001	Guard Rail, Class A, Type 1	75.000	LF	33.00	40.00	37.00
0520	606-D022	Guard Rail, Bridge End Section, Type 1	4.000	EA	3,950.00	4,760.00	4,390.00

Bridge Replacements on SR 182 at White Creek Canal (Bridge No. 122.1) & Little Black Creek (Bridge No. 122.4), known as Federal Aid Project No. BR-0730-00(003) / 106976301 in Webster County.					Ste-Bil Grading Inc.	Century Construction Group, Inc.	Key, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,813,849.00					\$4,695,105.60	\$5,786,471.00	\$5,909,880.60
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0530	606-E005	Guard Rail, Terminal End Section, Flared	4.000	EA	3,800.00	4,580.00	4,220.00
0540	615-A024	Concrete Bridge End Barrier, 37.5"	40.000	LF	100.00	91.75	83.00
0550	617-A001	Right-of-Way Marker	19.000	EA	300.00	384.00	500.00
0560	618-A001	Maintenance of Traffic	1.000	LS	5,500.00	50,800.00	50,000.00
0570	619-A1002	Temporary Traffic Stripe, Continuous White	4,675.000	LF	2.00	2.50	2.30
0580	619-A2002	Temporary Traffic Stripe, Continuous Yellow	4,675.000	LF	2.00	2.50	2.30
0590	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	78.000	SF	10.00	9.30	8.50
0600	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	321.000	SF	10.00	9.30	8.50
0610	619-G4001	Barricades, Type III, Double Faced	24.000	LF	23.00	19.50	18.00
0620	619-G4005	Barricades, Type III, Single Faced	96.000	LF	21.00	18.25	17.00
0630	619-G5001	Free Standing Plastic Drums	25.000	EA	45.00	42.25	39.00
0640	619-G7001	Warning Lights, Type "B"	12.000	EA	150.00	151.00	139.00
0650	620-A001	Mobilization	1.000	LS	350,000.00	570,000.00	590,000.00
0660	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	4,675.000	LF	3.50	4.30	3.90
0670	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	4,675.000	LF	3.50	4.30	3.90
0680	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	29.000	EA	15.00	18.25	17.00
0690	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	10.000	SF	28.00	33.75	32.00
0700	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	44.000	SF	30.00	36.25	34.00
0710	630-C001	Square Tube Posts, 4.0 lb/ft	48.000	LF	68.00	82.00	76.00
0720	630-C005	Square Tube Posts, 2.0 lb/ft	83.000	LF	44.00	53.25	49.00
0730	630-F006	Delineators, Guard Rail, White	14.000	EA	25.00	30.25	28.00
0740	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	4.000	EA	100.00	115.00	106.00
0750	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	4.000	EA	100.00	115.00	106.00
0760	699-A001	Roadway Construction Stakes	1.000	LS	65,000.00	95,800.00	150,000.00
0770	815-A007	Loose Riprap, Size 300	271.000	TON	80.00	102.00	98.00
0780	815-E001	Geotextile under Riprap	239.000	SY	3.00	6.10	5.00

Bridge Replacements on SR 182 at White Creek Canal (Bridge No. 122.1) & Little Black Creek (Bridge No. 122.4), known as Federal Aid Project No. BR-0730-00(003) / 106976301 in Webster County.					Ste-Bil Grading Inc.	Century Construction Group, Inc.	Key, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,813,849.00					\$4,695,105.60	\$5,786,471.00	\$5,909,880.60
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0790	815-F002	Sediment Control Stone	38.000	TON	95.00	121.00	100.00
0800	907-234-A001	Temporary Silt Fence	4,400.000	LF	4.00	3.70	3.40
0810	907-234-C001	Super Silt Fence	650.000	LF	14.00	15.25	14.00
0820	907-253-A001	Coir Fiber Baffle	216.000	LF	12.00	15.25	14.00
0830	907-257-A001	Floating Skimmer System	1.000	EA	5,000.00	6,030.00	6,980.00
0840	907-619-E3001	Changeable Message Sign	2.000	EA	7,500.00	12,100.00	12,000.00
0850	304-G001	Size 3/4" and Down Crushed Stone Base, AEA	945.000	CY	120.00		
0860	304-G002	Size 610 Crushed Stone Base, AEA	945.000	CY		199.00	150.00
0870	304-G003	Size 825B Crushed Stone Base, AEA	945.000	CY			
0880	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	40.000	CY	80.00	98.75	
0890	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	40.000	CY			103.00
0900	206-A001	Structure Excavation	219.000	CY	20.00	29.75	35.00
0910	501-K001	Transverse Grooving	1,359.000	SY	5.00	2.90	2.70
0920	803-D006	HP 14 x 73 Steel Piling	1,235.000	LF	85.00	89.75	83.00
0930	803-D007	HP 14 x 89 Steel Piling	1,930.000	LF	95.00	114.00	95.00
0940	804-C188	80' Prestressed Concrete Beam, Type FIB-36	398.000	LF	400.00	357.00	326.00
0950	804-C192	100' Prestressed Concrete Beam, Type FIB-36	1,493.000	LF	400.00	355.00	326.00
0960	805-A001	Reinforcement	213,815.000	LBS	1.50	1.60	1.80
0970	805-C001	Reinforcement, Corrosion Resistant	4,653.000	LBS	3.00	3.50	2.90
0980	813-A004	Concrete Railing, 36"	764.000	LF	80.00	91.75	83.00
0990	815-A007	Loose Riprap, Size 300	1,198.000	TON	80.00	93.25	94.00
1000	815-E001	Geotextile under Riprap	958.000	SY	3.00	3.80	5.00
1010	907-803-B001	Conventional Static Pile Load Test	1.000	EA	5,000.00	5,000.00	5,000.00
1020	907-803-I003	PDA Test Pile, HP Steel Pile	3.000	EA	18,000.00	19,500.00	22,000.00
1030	907-803-J001	Pile Restrike	3.000	EA	500.00	757.00	287.00
1040	907-804-A001	Bridge Concrete, Class BDX	413.000	CY	1,200.00	1,440.00	1,540.00

Bridge Replacements on SR 182 at White Creek Canal (Bridge No. 122.1) & Little Black Creek (Bridge No. 122.4), known as Federal Aid Project No. BR-0730-00(003) / 106976301 in Webster County.					Ste-Bil Grading Inc.	Century Construction Group, Inc.	Key, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,813,849.00					\$4,695,105.60	\$5,786,471.00	\$5,909,880.60
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1050	907-804-A002	Bridge Concrete, Class AA	133.000	CY	1,200.00	1,240.00	2,560.00
1060	907-804-A003	Bridge Concrete, Class B	548.000	CY	850.00	1,010.00	1,130.00
1070	907-823-A001	Preformed Joint Seal, Type I	73.000	LF	30.00	31.50	29.00

Letting Date: 5/23/2023

Call Number: 06

Page 5 of 5

Bridge Replacements on SR 182 at White Creek Canal (Bridge No. 122.1) & Little Black Creek (Bridge No. 122.4), known as Federal Aid Project No. BR-0730-00(003) / 106976301 in Webster County.					Cotton Creek Transport, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,813,849.00					\$6,221,515.15		
Ref#	Item	Item Description	Item Qty	Units	4		
0010	201-A001	Clearing and Grubbing	1.000	LS	585,000.00		
0020	202-A001	Removal of Obstructions	1.000	LS	470,000.00		
0030	202-B007	Removal of Asphalt Pavement, All Depths	4,296.000	SY	8.00		
0040	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	740.000	LF	3.50		
0050	202-B190	Removal of Piling	36.000	EA	100.00		
0060	202-B191	Removal of Pipe, 8" And Above	383.000	LF	14.00		
0070	203-A001	Unclassified Excavation, FM, AH	7,321.000	CY	8.00		
0080	203-EX020	Borrow Excavation, AH, FME, Class B9	4,008.000	CY	29.00		
0090	203-F001	Channel Excavation, FM	850.000	CY	8.00		
0100	203-G001	Excess Excavation, FM, AH	1,000.000	CY	8.00		
0110	206-A001	Structure Excavation	1,319.000	CY	8.00		
0120	206-B001	Select Material for Undercuts, Contractor Furnished, FM	257.000	CY	110.00		
0130	209-A005	Geotextile Stabilization, Type V, Non-Woven	6,016.000	SY	2.80		
0140	211-B001	Topsoil for Slope Treatment, Contractor Furnished	780.000	CY	1.00		
0150	213-C001	Superphosphate	2.000	TON	850.00		
0160	216-A001	Solid Sodding	850.000	SY	5.00		
0170	217-A001	Ditch Liner	254.000	SY	3.00		
0180	219-A001	Watering	17.000	KGAL	20.00		
0190	220-A001	Insect Pest Control	3.000	ACRE	30.00		
0200	221-A001	Concrete Paved Ditch	75.000	CY	900.00		
0210	225-A001	Grassing	3.000	ACRE	875.00		
0220	225-B001	Agricultural Limestone	9.000	TON	90.00		
0230	225-C001	Mulch, Vegetative Mulch	6.000	TON	190.00		
0240	226-A001	Temporary Grassing	3.000	ACRE	800.00		
0250	236-A008	Silt Basin, Type D	1.000	EA	3,000.00		
0260	237-A002	Wattles, 20"	5,200.000	LF	4.00		

Bridge Replacements on SR 182 at White Creek Canal (Bridge No. 122.1) & Little Black Creek (Bridge No. 122.4), known as Federal Aid Project No. BR-0730-00(003) / 106976301 in Webster County.					Cotton Creek Transport, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,813,849.00					\$6,221,515.15		
Ref#	Item	Item Description	Item Qty	Units	4		
0270	239-A001	Temporary Slope Drains	2,657.000	LF		10.00	
0280	245-A001	Silt Dike	52.000	LF		20.00	
0290	246-B001	Rockbags	198.000	EA		10.00	
0300	247-A001	Temporary Stream Diversion	1.000	EA		120,000.00	
0310	249-A001	Riprap for Erosion Control	40.000	TON		119.00	
0320	249-B001	Remove and Reset Riprap	22.000	CY		24.00	
0330	304-A002	Granular Material, LVM, Class 3, Group C	100.000	CY		63.00	
0340	304-C001	Granular Material, AEA, Class 3, Group C	341.000	CY		91.00	
0350	403-A003	12.5-mm, ST, Asphalt Pavement	619.000	TON		254.10	
0360	403-A006	19-mm, ST, Asphalt Pavement	788.000	TON		214.20	
0370	403-A015	9.5-mm, ST, Asphalt Pavement	559.000	TON		267.75	
0380	406-D001	Fine Milling of Bituminous Pavement, All Depths	1,244.000	SY		13.50	
0390	407-A001	Asphalt for Tack Coat	848.000	GAL		6.30	
0400	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	78.000	LF		10.00	
0410	423-A001	Rumble Strips, Ground In	1.000	MI		300.00	
0420	501-K001	Transverse Grooving	24.000	SY		2.40	
0430	502-A001	Reinforced Cement Concrete Bridge End Pavement	166.000	SY		346.50	
0440	503-C010	Saw Cut, Full Depth	112.000	LF		12.00	
0450	601-B001	Class "B" Structural Concrete, Minor Structures	1.000	CY		175.00	
0460	603-ALT006	24" Type A Alternate Pipe	40.000	LF		95.00	
0470	605-AA001	Geotextile for Subsurface Drainage, Type III	44.000	SY		60.00	
0480	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	80.000	LF		70.00	
0490	605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	12.000	LF		70.00	
0500	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	3.000	CY		245.00	
0510	606-B001	Guard Rail, Class A, Type 1	75.000	LF		33.00	
0520	606-D022	Guard Rail, Bridge End Section, Type 1	4.000	EA		3,950.00	

Bridge Replacements on SR 182 at White Creek Canal (Bridge No. 122.1) & Little Black Creek (Bridge No. 122.4), known as Federal Aid Project No. BR-0730-00(003) / 106976301 in Webster County.					Cotton Creek Transport, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,813,849.00					\$6,221,515.15		
Ref#	Item	Item Description	Item Qty	Units	4		
0530	606-E005	Guard Rail, Terminal End Section, Flared	4.000	EA		3,800.00	
0540	615-A024	Concrete Bridge End Barrier, 37.5"	40.000	LF		72.50	
0550	617-A001	Right-of-Way Marker	19.000	EA		300.00	
0560	618-A001	Maintenance of Traffic	1.000	LS		125,000.00	
0570	619-A1002	Temporary Traffic Stripe, Continuous White	4,675.000	LF		2.00	
0580	619-A2002	Temporary Traffic Stripe, Continuous Yellow	4,675.000	LF		2.00	
0590	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	78.000	SF		10.00	
0600	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	321.000	SF		10.00	
0610	619-G4001	Barricades, Type III, Double Faced	24.000	LF		23.00	
0620	619-G4005	Barricades, Type III, Single Faced	96.000	LF		21.00	
0630	619-G5001	Free Standing Plastic Drums	25.000	EA		45.00	
0640	619-G7001	Warning Lights, Type "B"	12.000	EA		150.00	
0650	620-A001	Mobilization	1.000	LS		550,000.00	
0660	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	4,675.000	LF		3.50	
0670	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	4,675.000	LF		3.50	
0680	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	29.000	EA		15.00	
0690	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	10.000	SF		28.00	
0700	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	44.000	SF		30.00	
0710	630-C001	Square Tube Posts, 4.0 lb/ft	48.000	LF		68.00	
0720	630-C005	Square Tube Posts, 2.0 lb/ft	83.000	LF		44.00	
0730	630-F006	Delineators, Guard Rail, White	14.000	EA		25.00	
0740	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	4.000	EA		95.00	
0750	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	4.000	EA		95.00	
0760	699-A001	Roadway Construction Stakes	1.000	LS		60,000.00	
0770	815-A007	Loose Riprap, Size 300	271.000	TON		105.00	
0780	815-E001	Geotextile under Riprap	239.000	SY		2.80	



Bridge Replacements on SR 182 at White Creek Canal (Bridge No. 122.1) & Little Black Creek (Bridge No. 122.4), known as Federal Aid Project No. BR-0730-00(003) / 106976301 in Webster County.					Cotton Creek Transport, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,813,849.00					\$6,221,515.15		
Ref#	Item	Item Description	Item Qty	Units	4		
0790	815-F002	Sediment Control Stone	38.000	TON		83.00	
0800	907-234-A001	Temporary Silt Fence	4,400.000	LF		3.00	
0810	907-234-C001	Super Silt Fence	650.000	LF		12.50	
0820	907-253-A001	Coir Fiber Baffle	216.000	LF		12.50	
0830	907-257-A001	Floating Skimmer System	1.000	EA		8,000.00	
0840	907-619-E3001	Changeable Message Sign	2.000	EA		7,500.00	
0850	304-G001	Size 3/4" and Down Crushed Stone Base, AEA	945.000	CY			
0860	304-G002	Size 610 Crushed Stone Base, AEA	945.000	CY		180.00	
0870	304-G003	Size 825B Crushed Stone Base, AEA	945.000	CY			
0880	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	40.000	CY			
0890	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	40.000	CY		95.00	
0900	206-A001	Structure Excavation	219.000	CY		25.00	
0910	501-K001	Transverse Grooving	1,359.000	SY		2.40	
0920	803-D006	HP 14 x 73 Steel Piling	1,235.000	LF		95.00	
0930	803-D007	HP 14 x 89 Steel Piling	1,930.000	LF		110.00	
0940	804-C188	80' Prestressed Concrete Beam, Type FIB-36	398.000	LF		380.00	
0950	804-C192	100' Prestressed Concrete Beam, Type FIB-36	1,493.000	LF		380.00	
0960	805-A001	Reinforcement	213,815.000	LBS		1.65	
0970	805-C001	Reinforcement, Corrosion Resistant	4,653.000	LBS		3.05	
0980	813-A004	Concrete Railing, 36"	764.000	LF		72.50	
0990	815-A007	Loose Riprap, Size 300	1,198.000	TON		100.00	
1000	815-E001	Geotextile under Riprap	958.000	SY		2.80	
1010	907-803-B001	Conventional Static Pile Load Test	1.000	EA		5,000.00	
1020	907-803-I003	PDA Test Pile, HP Steel Pile	3.000	EA		15,500.00	
1030	907-803-J001	Pile Restrike	3.000	EA		1,500.00	
1040	907-804-A001	Bridge Concrete, Class BDX	413.000	CY		1,400.00	

Bridge Replacements on SR 182 at White Creek Canal (Bridge No. 122.1) & Little Black Creek (Bridge No. 122.4), known as Federal Aid Project No. BR-0730-00(003) / 106976301 in Webster County.					Cotton Creek Transport, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,813,849.00					\$6,221,515.15		
Ref#	Item	Item Description	Item Qty	Units	4		
1050	907-804-A002	Bridge Concrete, Class AA	133.000	CY	1,300.00		
1060	907-804-A003	Bridge Concrete, Class B	548.000	CY	900.00		
1070	907-823-A001	Preformed Joint Seal, Type I	73.000	LF	26.00		

Letting Date: 5/23/2023

Call Number: 06

Page 5 of 5